

PROJECT: #4 ROAD AND STEVESTON ESSO	TPC: 29.990 m	BOREHOLE NO: BH1
LOCATION: RICHMOND, BRITISH COLUMBIA	GR: 30.046 m	JOB NO: 10-3327
CLIENT: IMPERIAL OIL PRODUCTS DIVISION	COMPLETION DATE: 94/04/08	DRILL: AUGER
SAMPLE TYPE <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> SHELBY <input checked="" type="checkbox"/> SPLIT SPOON <input type="checkbox"/> CORE <input type="checkbox"/> DISTURBED <input type="checkbox"/> NO RECOVERY		

DEPTH (m)	SOIL DESCRIPTION	SAMPLE TYPE	VAP. CONCENTRATION		SOIL SYMBOL	SLOTTED PIEZOMETER	ADDITIONAL NOTES	DEPTH (ft)
			▲ VAP. CONCENTRATION ppm 100 200 300 400	● VAP. CONCENTRATION %LEL 20 40 60 80				
0	ASPHALT SAND (FILL) - brown, trace gravel, moist						Concrete	0
1	SILT - grayish-brown, trace sand							5
2	CLAY - gray, some silt, wet below 2.1 m						94/09/29	10
3	SILT - gray, clayey, wet						Pea gravel	15
4	- trace clay below 4.0 m							20
5	END OF HOLE at 4.6 m							25
6	Monitoring piezometer installed to 4.6 m							30
7	Screened interval from 0.6 m to 4.6 m							35
8								40
9								45
10								50

O'Connor Associates  
Vancouver, B.C.

LOGGED BY: JTB/BC  
REVIEWED BY: WBK  
DRAWING NO: B-1