

Borehole Number: BH01-24



Project Name: Olympic View Golf Course

A **tyco** INTERNATIONAL LTD. COMPANY

Project Number: 67489

Earth Tech (Canada) Inc.
6th Floor - 1901 Rosser Avenue
Vancouver, BC V5C 6S3

Location: Langford, BC

Client: Olympic View Land Development Corporation

| SUBSURFACE PROFILE | | | | SAMPLE | | | | OVM (PPM) | Remarks |
|--------------------|------|-----------|--|---------------|----------------|-------------|----------------------------------|-----------|------------------|
| Depth (m) | USCS | Soil Type | Soil Description | Sample Number | Blowcount | Sample Type | Lab Analysis | | |
| 0 | | | Ground Surface | | | | | | |
| 0 | OL | | Top Soil | | 44/59/41/23/17 | | | | |
| 1 | SM | | Fill (silty Sand) | 1 | | | BTEX/VPH, | 25 | |
| 2 | ML | | Brown, some clay, trace gravel, poorly graded, moist. | 2 | | | LEPH/HEPH, PAH, metals | 130 | |
| 3 | | | Fill (clayey Silt) | | | | | | |
| 4 | | | Some sand, trace gravel, poorly graded, debris (asphalt, brick, drywall, paint, wood). | | | | | | |
| 5 | | | -brown to dark brown, moist, 0.3 to 3.1 m. | 3 | 18/16/21/15/19 | | | | petroleum odour |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | VOC, VPH, LEPH/HEPH, PAH, metals | | |
| 11 | | | -dark grey, very moist, 3.1 to 6.1 m. | 4 | 19/12/22/20/33 | | | 160 | staining |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | 5 | 10/10/15/35/62 | | | 50 | staining |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |
| 21 | | | | 6 | | | | 30 | |
| 22 | | | | | | | | | |
| 23 | | | | | | | | | |
| 24 | | | | | | | | | |
| 25 | | | | | | | | | |
| 26 | | | | | 13/100 (0.5m) | | | | refusal at 8.1 m |
| 27 | | | End of Borehole | | | | | | |
| 28 | | | | | | | | | |
| 29 | | | | | | | | | |

Drill Method: H/S Auger

Borehole Depth: 8.1m

Ground Elevation: 83.4m

Drill Date: 11 July 01

Logged By: JM

Well Elevation: N/A

Driller: Uniwide Drilling Ltd.

Reviewed By: TS/JL

Borehole Diameter: 0.19m