

BOREHOLE No. BHI401 (MWI401)

TYPE OF RIG: Truck Mounted Auger Rig
 DRILLING CONTRACTOR: Drillwell Enterprises Ltd.
 DATE DRILLED: February 24, 1998
 STEEL CASING STICK UP: N/A
 LOCATION: Lot 14 - Amon Holdings

SURFACE CONDITION: Concrete
 ELEV. TOP OF CASING: N/A
 DEPTH TO WATER : 5.795 m
 ELEVATION OF WATER: N/A
 GROUND ELEVATION : N/A

Depth (m)	Elev. (m-asl)	LITHOLOGIC DESCRIPTION	WELL CONSTRUCTION MATERIALS	Well Diagram	Sample Interval	Type	Sample Number	
0.0	N/A	Ground surface	Piezometer covered by flushmount completion					
		Landscaping Soil	Cement Collar			AS	GV289-08	
1.0		Greenish-gray sandy silt, dry	Bentonite Plug			AS	GV289-09	
2.0						AS	GV289-10	
3.0						AS	GV289-11	
4.0		Brown silt, some pebbles	PVC Slot 20 Screen (3.3 - 6.4 m)			AS	GV289-12	
5.0						AS	GV289-13	
6.0		Gray sandy silt, moist	Silica Sand (3.1-6.4 m)			AS	GV289-14	
7.0								
		END OF HOLE (6.4 m)						
8.0								
9.0								
10.0								

Client	PWGSC	GeoViro Engineering Ltd. Consulting Engineers and Environmental Scientists
Project	Environmental Baseline Study - Victoria Harbour Lot 14 Soil and Groundwater Investigation Project No. GV289.01	
MONITORING WELL LOG		BY: TC DATE: 24-Feb-98 APPROVED: FIG: