

BOREHOLE No.

BH1506 (MW1501)

TYPE OF RIG:

Truck Mounted Auger Rig

SURFACE CONDITION:

Gravel

DRILLING CONTRACTOR:

Drillwell Enterprises Ltd.

ELEV. TOP OF PVC:

3.21

DATE DRILLED:

February 25, 1998

DEPTH TO WATER :

1.88

STEEL CASING STICK UP:

-

ELEVATION OF WATER:

1.33

LOCATION:

RV Park - Adjacent to Rose Bay

GROUND ELEVATION :

3.21

Depth (m)	Elev. (m-astl)	LITHOLOGIC DESCRIPTION	WELL CONSTRUCTION MATERIALS	Well Diagram	Sample Interval	Type	Sample Number	
0.0	-	Ground surface	Piezometer covered by flushmount completion					
		Dark brown sandy gravel (bit of surficial staining?)	Cement Collar					GV289-23
		Dark brown sandy gravel, silty pockets; no staining or odour	Bentonite Plug					GV289-24
1.0		Dark brown silty sand, bits of crushed rock; no staining or odour						GV289-25
2.0		Dark brown sand/gray silty sand (siltier with depth); slight HC odour	PVC Slot 20 Screen (1.5 - 4.5m)					GV289-26,27
3.0		END OF HOLE 3.4 m (bedrock)	Silica Sand (1.0 - 3.7m)					
4.0								
5.0								
6.0								
7.0								
8.0								
9.0								
10.0								
Client			<p>GeoViro Engineering Ltd. Consulting Engineers and Environmental Scientists</p>					
Project			MONITORING WELL LOG		BY:	DATE:		
Environmental Baseline Study - Victoria Harbour Lot 15 Soil and Groundwater Investigation Project No. GV289.01					TC	24-Feb-98		
					APPROVED:	FIG:		