

CLIENT : GWL Realty Advisors Inc.  
 PROJECT: Semiahmoo Shopping Centre, Surrey, B.C.  
 JOB#: 41244-001

# BOREHOLE LOG

BOREHOLE NO: NDM6

LOCATION: North of Former Fire Hall

ELEVATION: Top of Casing n/a  
 Ground n/a

BLOW COUNT	CLASS CODE	USCS	SAMPLE TYPE	SAMPLE I.D.	DEPTH (m)	DEPTH (ft)	LITHOGRAPHY	WELL CONSTRUCTION DETAILS	HYDROCARBON VAPOUR LEVEL (UNITS)	WELL INSTALLATION & WATER LEVEL	DEPTH (m)
			X	NDM6 0-0.5m	0	0	0 - 0.05m Asphalt	0 - 0.5m Concrete	10ppm		
			X	NDM6 0.5-1.0m	2	2	0.05 - 1.0m SILTY SAND, brown, with gravel, no inclusions, high plasticity, damp		5ppm		
			X	NDM6 1.0-2.0m	4	4	0.5 - 10.0m SILTY SAND, brown, with gravel, no inclusions moist		4ppm		
			X	NDM6 2.0-3.0m	6	6		0.5 - 5.0m Filter Sand Pack	4ppm		
			X	NDM 3.0-4.0m	8	8			6ppm		
			X	NDM6 4.0-5.0m	10	10			3ppm		
			X	NDM6 5.0-6.0m	14	14		5.0 - 6.0m Bentonite Chips	4ppm		
			X	NDM6 6.0-7.0m	16	16			5ppm		
			X	NDM6 7.0-8.0m	20	20		6.0 - 10.0m Filter Sand Pack	5ppm		
			X	NDM6 8.0-9.0m	22	22		7.0 - 10.0m PVC Screen	4ppm		
			X	NDM6 9.0-10.0m	24	24			4ppm		
					26	26					
					28	28					
					30	30					
					32	32					
					34	34	EOH at 10.0m				
					36	36					
								Borehole Dia.		8"	

DRILLING CONTRACTOR: Uniwide Drilling Ltd.  
 DRILLING METHOD: Solid Stem Auger  
 DATE: May 24, 2000  
 LOGGED BY: Robin Jones

SAMPLE TYPE: CORE SAMPLE  
 GRAB SAMPLE  
 SPLIT SPOON SAMPLE  
 NO RECOVERY