



**Hardy BBT Limited**  
CONSULTING ENGINEERING & PROFESSIONAL SERVICES

**LOG OF BOREHOLE NO. BH 1**

Site Investigation  
Texaco Service Station Nos. S/S 763  
Kamloops, B.C.

LOGGED/DWN. T.M.

CKD.

DATE OF INVEST. April 4, 1989

JOB NO. CG19042

Hydrocarbon Vapour Concentration (ppm)	DEPTH (m)	SOIL SYMBOL	DRILL TYPE	CONDITION	SAMPLE TYPE	OTHER TESTS	
			Becker Hammer			N	
100    200    300			SOIL DESCRIPTION				
			DATUM				
			SURFACE ELEVATION 99.85				
			Asphalt				
			19mm Crush (sand & gravel)				
	2		Sand- fine to coarse, trace fine to coarse gravel, brown, wet.				
			Sand - fine to coarse, and gravel fine to coarse, trace fines, brown, moist. (FILL)				
	4						
			Sand - fine to coarse, some gravel fine to coarse, frequent cobbles to 150mm, trace fines, dense, brown, moist.				
	6						
			Sand - fine to coarse, little gravel, some fines, dense, brown, dry.				
	8		-interbedded hard silt and fine sand layers to approx 10cm thick.				
			Sand - coarse, uniform, compact, brown, moist.				
	10						
			Sand - fine to medium, compact, uniform, brown, moist.				
	12						
			Sand - fine to coarse, and gravel fine to coarse, occasional cobbles, dry.				
	16						
			Sand - fine to coarse and little gravel fine to coarse, some fines, dense, moist.				
	18						
			Sand - fine to medium, little gravel fine to coarse, rounded, trace fines, dense, brown, moist.				
							Plate



**Hardy BBT Limited**  
CONSULTING ENGINEERING & PROFESSIONAL SERVICES

**LOG OF BOREHOLE NO. BH 1**

Site Investigation  
Texaco Service Station Nos. 5/S 763  
Kamloops, B.C.

LOGGED/DWN. T.M. CKD.

DATE OF INVEST. April 4, 1989

JOB NO. CG19042

Hydrocarbon Vapour Concentration (ppm)			DEPTH (m)	SOIL SYMBOL	DRILL TYPE	CONDITION	SAMPLE TYPE	OTHER TESTS	
100	200	300			SOIL DESCRIPTION			N	
					DATUM SURFACE ELEVATION 99.85				
					Sand - fine to coarse, trace gravel fine to coarse, rounded, trace fines, dense, brown, moist.				
			22		Sand - coarse, and gravel fine to coarse, sub-rounded to sub-angular, dense, grey, moist.				
			24		Sand - fine to coarse, and gravel fine to coarse, occ. cobbles to 150mm, hard, dark brown, moist. Water Level				
			26		Sand - fine to medium, compact, grey, saturated.				
			28		Sand - fine to coarse, and gravel fine to coarse, trace fines, hard, grey, saturated.				
			30		Silt - and clay, trace gravel fine to coarse, hard, moist. (Till)				
			32		END OF HOLE AT 29.6m. Water Level at 24.1m.  Piezometer installed to 29.6 m slotted 20.4 - 29.6 m				
			34						
			36						
			38						
									Plate