

Borehole no. : MW01

Equipment : TRUCK MOUNTED DRILL RIG

Location : SEE LOCATION PLAN

Ground Surface Elevation : 99.64

Method of sampling: GRAB SAMPLE

Ground Water Elevation : 94.82
(at time of investigation)

depth, ft.	depth, m	blows on sampler	symbol	Description	sample no.	Headspace (ppm)	Remark
0	0						
1				SAND & GRAVEL (FILL), brown, damp, no odour	1-8	0.5	
5							
2							
10	3			SILT (TILL) grey, some sand, moist @ 8'	8-10	0.7	
3							
4				SILT & SAND (TILL), dry, grey, no odour	10-15	0.6	
15							
5				SILT & SAND (TILL), damp, grey, no odour	15-20	0.9	Estimated Water Table Depth 5.51 m Sept. 12/05
20	6						
7							
25							
8				SILT & SAND (TILL), wet @ 28', grey, possible odour	28-30	1.9	
30	9						
10				End of Borehole @ 30'			
				overdrilled to 35' to get hole to stay open for well			

Georgia Laine Development Corporation



TROW ASSOCIATES INC.

Preliminary & Detailed Site Investigations &
Remedial Excavation
3707 Delbrook Ave., North Vancouver, BC

Borehole No.
MW01

By: RS

Date of Drilling: SEPT. 7/05

Sheet: 1 of 1

Dwg No. 048-01026-01-MW01