

BOREHOLE LOG

LOGGED BY: LEO
DRILLER: Downright Drilling Ltd.

O.D. & TYPE: 150mm Solid Stem
RIG: Track-mounted

HOLE No: BH3A
WELL PIPE TOP EL. (m): 99.40

Depth (m)	DESCRIPTION	Symbol	Depth/Elev.	Well	SAMPLE		VAPOUR ("TOV") CONC.				COMMENTS	
					Type	Rec. (%)	% LEL					
							20	40	60	80		
							ppmv					
							100	200	300	400		
	ASPHALT Degraded asphalt and gravel underlay	[Cross-hatch symbol]	-0.15									
	SILT Light brown soft sandy silt	[Dotted symbol]	-0.46									
1	SAND Coarse grey sand with gravel	[Dotted with circles symbol]										
			-2.13									
	SILT Medium brown sandy silt with some gravel	[Dotted with circles symbol]	-2.59									
	SAND Coarse grey sand with gravel	[Dotted with circles symbol]	-3.05									
	GRAVEL Washed gravel	[Large circles symbol]	-3.35									
4	SILT Moist grey and brown sandy silt	[Dotted with circles symbol]	-4.72									
5	SAND Moist brown silty sand	[Dotted with circles symbol]										
6			-6.1									
	Bottom of Borehole											

groundwater
monitored 06/11/99

hydrocarbon odour
observed in soil

test
BTEX / VPH

test
BTEX / VPH



LEVELTON
Engineering Solutions

PROJECT: Detailed Site Investigation

JOB No: 099-0076

CLIENT: Maril Developments Ltd.

Sheet No: 1 of 1

DATE: June 9, 1999