

# BOREHOLE RECORD

BH 7

CLIENT Canada Safeway Limited

PROJECT No. BCV 61023

LOCATION 1143 - 56th Street, Tsawwassen, B.C.

DATUM Local

DATES: BORING 07/03/00 WATER LEVEL 09/03/00

TPC ELEV. 99.943

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION	SOIL SYMBOL	WATER LEVEL	DEPTH (ft)	VAPOUR CONCENTRATIONS				SAMPLES			WELL CONSTRUCTION	
						● %LEL	▲ ppm	TYPE	NUMBER	N-VALUE				
0		Asphalt				● 20	▲ 100	40	60	80				
		Brown, loose, SAND and GRAVEL (FILL), trace silt, damp												
		Brown, stiff, SILT, some sand, damp			2						SS	1		
					4						SS	2		
					6						SS	3		
					8						SS	4		
		Brown, very stiff, SILT, trace sand, trace clay, moist			10						SS	5		
					12						SS	6		
		Brown, very dense, SAND, some silt, wet			14						SS	7		
					16						SS	8		
		- trace silt			18									
					20						SS	9		
		End of borehole at 6.1 m			22									
					24									

Flushmount road-box casing  
50 mm ID slotted PVC with silica sand backfill  
DNAPL sump

LABORATORY ANALYSES: Soil: Sample 3 and 5 for VOCs.  
Groundwater: VOCs.

