

# BOREHOLE LOG


# BH4

SUPERVISOR: **Theresa Keenan**  
 TYPE OF RIG: **Solid Stem Auger**  
 CONTRACTOR: **Uniwide Drilling Co. Ltd.**  
 DATE DRILLED: **October 10, 2001**  
 GROUND ELEV: **98.709m**

CLIENT: **Bank of Montreal**  
 PGL PROJECT No.: **423-10.03**

Depth (m)	Elev. (m- asl)	LITHOLOGY	SAMPLES NAMES AND DEPTHS	COMMENTS	Vapours (ppm)
0.0	0.0	Ground surface			
1.0	-1.0	Grey/brown, medium SAND (fill), some gravel, trace silt, trace cobbles, moist, loose	BH4-1		
2.0	-2.0	Orange/brown, medium/course SAND, some gravel, trace cobbles, moist, loose	BH4-2		
3.0	-3.0	Grey TILL (native), some gravel, moist, compact	BH4-3		
4.0	-4.0	Grey/brown TILL, some gravel, minor cobbles, moist, compact	BH4-4		
5.0	-5.0	Grey/blue SILTSTONE, dry, dense			
6.0	-6.0	End of Hole at 6.0m			
7.0	-7.0				
8.0	-8.0				
9.0	-9.0				

DETAILED SITE INVESTIGATION  
 2410 Marine Drive, West Vancouver, BC



POTTINGER GAHERTY  
 ENVIRONMENTAL  
 CONSULTANTS LTD.