



Client :
Bishop of Victoria

Borehole No. : BH02-3

Location :
840 - 844 View Street, Victoria

(Page 1 of 1)

Drilling Contractor: Drillwell Enterprises Ltd.
Drilling Method : Solid Stem Auger
Borehole Dia. (m) : 0.15
Pipe/Slotted Pipe Dia. (m): 0.05, 0.05

Ground Surf Elev. (m) : 9.889
Top of Casing Elev. (m) : 10.168

Project Number : V2700
Borehole Logged By : RAS
Date Drilled : 2002 07 17
Log Typed By : SAG

Depth in Metres	Drilling Legend	Water/LPH Levels	Stratigraphy Plot	Sample Interval/ Core Run	Sample Number	Blow Count	% Recovery	Soil Vapour (ppm)	Well Name 1 : MW02-3
	Sample Interval Water Level 1 Water Level 2 LPH Level 1 LPH Level 2	Reading within indicated scale Reading outside indicated scale							
	Soil Description							1 2 3 4 10 10 10 10	Solid PVC Slotted PVC
0	ASPHALT								
0.5	SAND, some silt, some gravel, dark brown, loost, moist, (FILL), hydrocarbon odour.								SAND
0.5	SAND, fine grained, light grey, loose, moist, (NATIVE).			3-01				0.275	
1.5	CLAY, silt, dark grey / brown, stiff, medium plasticity, moist, (NATIVE).				3-02			0.25	BENTONITE
5.0	SAND and GRAVEL, medium to coarse grained, rounded, grey, dense, moist to wet, (TILL).								SAND
7.0					3-03			0.25	
7.6	End of borehole at 7.6 m.								
8.0									
9.0									
10.0									

Print Date: 2003 03 28, Date Updated: 2003 03 28

Notes: