

BOREHOLE BH10

Drilling contractor: KEL Drilling
 Drilling equipment: B-61 mobile drill rig
 Drilling method: Hollow stem auger
 Core / casing: 8 inch outside diameter (203 mm)
 Survey method: Surveyed by GMD
 Logged by: GMD

Start date: June 17, 2013
 Finish date: June 17, 2013
 Final depth of hole: 5.2 m
 Ground elevation: 518.303 m
 Top of monitoring well elevation: 518.241 m
 Groundwater: 2.740 m below grade (June 26, 2013)
 Well screen size: 020 slot Sch40 PVC (51 mm diameter)
 Depth of screen below grade: 1.498 - 4.546 m

Depth (m)	Sample Type	Sample No.	Soil Symbol	Soil Description	Well Detail	Soil Analysis	Gastech Readings (ppmv)		
							100	1000	10000
1				ASPHALT					
2				SAND (backfill) some gravel, brown, moist					
3	X	10-12							
4									
5	X	15-17		CLAY (till) some sand, some slit, trace gravel, brown, hard, moist		VOC/VP, LEPH/HEPH	45		
6									
7									
8									



GD Assessments Inc.

Project: GDA 029
 Drawn by: CMM
 Date: January 2015

This drawing is for conceptual purposes only. Actual locations may vary and not all features are shown.

Borehole Logs

Preliminary and Detailed Site Investigation
 and Remediation Confirmation
 H.V. Foods Ltd.
 6221 Barnhartvale Road, Kamloops, BC