

Project No: 1898-1127.3

Borehole No: BH 99-4

Project: DSI - Alert Bay Site

Client: BC Packers Ltd.

Location: Alert Bay, B.C.

Engineer: M. Gallo, B.Sc.



SUBSURFACE PROFILE					SAMPLE		Soil Samples / Comments
Depth (m)	Elevation (m)	Description	Symbol	Well Data	Number	Type	
0	0	Ground Surface					Monitoring Well MW 4 installed
		SAND Medium-grained grey and reddish brown sand, dry.					
	-0.9						
1		SILTY SAND Grey with a trace of gravel, dry.					
	-1.5				99-4-1.4	GR	
		SAND AND GRAVEL Trace of silt, grey, saturated			99-4-1.6	GR	
2	-2.1						
	-2.4	SILTY CLAY Trace of gravel, moist					
		SAND Very fine, grey, wet with a trace of silt.			99-4-2.7	GR	
	-3.8						
4		End of Borehole					
5							

Drilled By: Mud Bay Drilling

Drill Method: Hollow Stem Auger

Drill Date: 1999 06 22

Levelton Engineering Ltd.
218 Prideaux Street
Nanaimo, B.C.
V9R 2N1

Hole Size: 15.2 cm

Datum: Ground

Sheet: 1 of 1