

1700 Marine Drive
 North Vancouver, BC

Project 452

 Date Started : April 6, 2012
 Date Completed : April 10, 2012
 Hole Diameter : 152 mm
 Drilling Method : Sonic
 Sampling Method : Grab

 Company Rep. : BR
 Lab Analysis : *indicates sent for analysis
 Drilled By : Downrite Drilling
 Logged By : BR

Depth in Meters	Surf. Elev	USCS	GRAPHIC	DESCRIPTION	Lab Analysis	Sample No.	Soil Vapours ppm	Sample Type	Well Details	
									Soil Vapour Well AE12-SV-2	Monitoring Well AE12-MW-2
0		AR		ASPHALT and GRAVEL, backfill to 0.3 m						
		SW		SAND, fine grained, trace silt, poorly sorted, grey/brown, no odour (FILL)						
1		SM		GRAVEL and SAND, brown, dry, no odour (FILL)		2-1	15	grab		
2		GW		GRAVEL, coarse and rounded, trace sand, no odour		2-2	20	grab		
3		SW		SAND, fine grained, some silt, some gravel, brown, pockets of grey staining, no odour		2-3	200	grab		
4				COBBLY SAND, fine grained, grey, dry, no odour						
5										
6										
7		CG								
8										
9				no/trace sand at 8.84 m		2-4	220	grab		
10						2-5	440	grab		
11				End of Hole						

