



August 28, 2026

PUP No. 925-0002-26-29

VIA EMAIL

BC Ministry of Environment and Parks
PO Box 9337 STN PROV GOVT
Victoria, BC
V8W 9M1

Attn: Amy Vallarino, B.C. Ministry of Environment and Parks

In response to your application dated March 12, 2026, enclosed is Pesticide Use Permit No. 925-0002-26-29 issued under the provisions of the *Integrated Pest Management Act*. Your attention is respectfully directed to the conditions of the permit that must be complied with.

It is the responsibility of the permit holder to ensure that all activities conducted under this permit are carried out with due regard to the rights of third parties, and comply with other applicable legislation that may be in force - including, but not limited to, using pesticide only for the use described on the label and in accordance with the instructions on that label.

This decision may be appealed to the Environmental Appeal Board in accordance with Section 14 of the *Integrated Pest Management Act*. An appeal must be delivered within 30 days from the date that notice of this decision is given. For further information, please contact the Environmental Appeal Board at (250) 387-3464.

Administration of this permit will be carried out by staff from the Environmental Protection Division's Authorizations and Remediation Branch. Plans, data and reports pertinent to the permit are to be submitted by email to the Administrator, or as further instructed.

Yours truly,

Andreas Wins-Purdy, P.Ag.
Director, Recycling and Pesticide Authorizations
for Administrator, *Integrated Pest Management Act*



MINISTRY OF ENVIRONMENT & PARKS

PESTICIDE USE PERMIT No. 925-0002-26-29

Pursuant to Section 6 of the Integrated Pest Management Act

British Columbia Minister of Environment and Parks

PO Box 9047 Stn Prov Gov
Victoria, BC
V8W 9E2

is authorized to use pesticides subject to the conditions listed below. Contravention of any of these conditions is a violation of the *Integrated Pest Management Act* and may result in prosecution.

Purpose of the Permit

1. Pesticide use shall be for the purpose of controlling Bohemian knotweed (*Reynoutria x bohemica*), Japanese knotweed (*Reynoutria japonica*), Giant knotweed (*Polygonum sachalinensis*), and Himalayan knotweed (*Persicaria wallichii*), using the herbicides Roundup WeatherPro (PCP # 33653), Habitat Aqua (PCP # 32374), and the adjuvant Aquasurf (PCP # 32152) within:
 - a. The area between water's edge and the high water mark, and
 - b. The area between the high water mark and 10m above the high water mark
 - c. Wetted areas below the water's edge (using Habitat Aqua & Adjuvant Aquasurf) as per the submitted Treatment Plan

along the shorelines of Legace Creek, Eng/McNab Creek, North and South Herford Creeks, Allen Lake, roadside and agricultural ditches and other pluvial flow potential sites within the Hatzic Valley as per the attached map. The attached map outlines the general location of known knotweed occurrence however treatment is not limited to these sites.

2. Pesticide Use under this permit must be consistent with and follow the "HATZIC VALLEY WATERWAYS KNOTWEED MANAGEMENT PLAN" dated March 15, 2026.

Date Issued: August 28, 2026



Andreas Wins-Purdy, P.Ag.
Director, Recycling and Pesticide Authorizations
for Administrator – *Integrated Pest Management Act*



Treatment Dates

3. The pesticide use described herein may be conducted from August 28, 2026, until the permit expires on August 28, 2029.

Notifications

4. Within seven days of permit issuance, the permit holder shall post a copy of the permit with relevant maps on the Ministry of Environment and Parks website. The posted permit and maps shall remain on the website until one week after all pesticide application activities under the permit have ceased.
5. Within 15 days of issuance of the permit, the permit holder shall publish a notice in at least one community newspaper circulated within the treatment area. The published notice shall contain the following information:
 - a) Name, address and telephone number of the permit holder
 - b) Permit number
 - c) Purpose of pesticide use
 - d) Pesticide used (trade name, P.C.P. No. and active ingredient)
 - e) Method of pesticide application
 - f) A description of the area to which the PUP applies
 - g) Date of project commencement and completion
 - h) Information on where copies of the permit and map of the treatment area may be examined in detail
 - i) Information on how and the public can contact the permit holder to obtain any permitted pesticide use and related integrated pest management information
6. The permit holder shall also conduct any additional notification agreed upon during the consultation process in the manner agreed upon with the parties to be notified.
7. All personnel involved in the project shall be notified of the terms and conditions of the permit and any permit amendments prior to pesticide use.

Date Issued: August 28, 2026



Andreas Wins-Purdy, P.Ag.
Director, Recycling and Pesticide Authorizations
for Administrator – *Integrated Pest Management Act*



Authorized Pesticides

8. The pesticides listed below are approved for use under the terms of this permit. Application rates indicated are maximums per application. Lower rates should be used where project objectives may still be achieved.

Trade Name	Active Ingredient (a.i.)	Product P.C.P. #.	Application Rate	Maximum Area of Pesticide Use per year (ha.)
Roundup WeatherPro	Glyphosate	33653	Foliar spray: 1.34%	40 ha
Roundup WeatherPro	Glyphosate	33653	Stem injection: 5ml/stem	
Habitat Aqua	Imazapyr	32374	3.0-4.68L/ha	
Aquasurf	Alcohol ethoxylate	32152	0.25% v/v	

Target Pest Species and Treatment Area

9. Pesticide use shall be for the sole purpose of eradicating Bohemian knotweed (*Reynoutria x bohemica*), Japanese knotweed (*Reynoutria japonica*), Giant knotweed (*Polygonum sachalinensis*), and Himalayan knotweed (*Persicaria wallichii*) in Hatzic Valley.
10. This permit authorizes the permit holder, under Section 18(2)(b) of the *Integrated Pest Management Act* Regulation, to use the pesticides listed within the wetted area to the high-water mark.
11. This permit authorizes the permit holder, under Section 18(3) of the *Integrated Pest Management Act* Regulation, to use the pesticides listed within the area between the high

Date Issued: August 28, 2026


Andreas Wins-Purdy, P.Ag.
Director, Recycling and Pesticide Authorizations
for Administrator – *Integrated Pest Management Act*



water mark and 10 metres above the high water mark as an exemption from the requirements under Pesticide Use Notice Confirmation number 402-0687-24-29 to maintain a Pesticide Free Zone under Section 73(1) of the *Integrated Pest Management Act* Regulation.

Restrictions

12. Pesticides shall not be applied by foliar spray when wind speeds are greater than 8 km/hr.
13. The permit holder must comply with the requirements of the label for the pesticide being applied.
14. All spray equipment shall be properly calibrated prior to use.
15. All pesticide products and application equipment used shall be maintained in secure conditions that prevent tampering or the introduction of contaminants.
16. All individuals conducting pesticide applications under this permit must hold a valid BC Pesticide Applicator Certificate in the *Industrial Vegetation and Noxious Weeds* category.
17. The permit holder must comply with all applicable provisions under the *Integrated Pest Management Act*.
18. Aquatic herbicide Habitat Aqua (PCP # 32374) must be used for any treatment to emergent wetted plants and must be a targeted spot treatment.
19. Habitat Aqua (PCP # 32374) must not be applied to any treatment site within the treatment area more than once per year as per label directions.
20. Where there is a risk of contact with sensitive non-target vegetation, foliar applications shall make use of drift shielding in the form of a nozzle cone or wind barrier to avoid contact with any sensitive non-target vegetation.
21. Pesticide is only authorized between the dates of June 15 to October 15 of each calendar year, when water levels are not expected to rise for an extended period following pesticide application.

Date Issued: August 28, 2026



Andreas Wins-Purdy, P.Ag.
Director, Recycling and Pesticide Authorizations
for Administrator – *Integrated Pest Management Act*



Reporting and Record Keeping

22. For each treatment location and day of pesticide use under this permit, the permit holder must keep a record containing the following information:
- a) the name and address of the owner or manager of the treatment location
 - b) if the use was performed as a service, the name and license number of the licensee who performed the service
 - c) if the use was not performed as a service, the name and certificate number of the pesticide applicator certificate holder who used the pesticide
 - d) the date and time of the pesticide use
 - e) the name of the pest targeted by the use or the purpose of the pesticide use
 - f) the trade name of each pesticide used and its registration number under the federal Act
 - g) for each pesticide used, the method and rate of application and the total quantity used
 - h) the prevailing meteorological conditions including temperature, precipitation, and velocity and direction of the wind
23. An annual report for each calendar year of pesticide use shall be submitted by email to ipmreporting@gov.bc.ca by January 31st of the following calendar year. The report shall include:
- a. the total quantity of pesticide used and total area treated for each of the four application methods
 - b. a description of the timing of treatments
 - c. pesticide treatment efficacy information
 - d. any observed or reported impacts on non-target organisms
 - e. all pertinent maps and a summary of recommended follow-up activities for the treatment area
24. Pesticide spills that result in impacts not authorized by or consistent with this permit, shall be immediately reported to the Provincial Emergency Program at 1-800-663-3456. Areas affected by spills shall be cleaned-up and decontaminated immediately. Spills, clean-up activities and decontamination actions must be reported to ipmreporting@gov.bc.ca as soon as practicable.

Date Issued: August 28, 2026



Andreas Wins-Purdy, P.Ag.
Director, Recycling and Pesticide Authorizations
for Administrator – *Integrated Pest Management Act*



25. Permit non-compliance that results in impacts not consistent with the intent of this permit shall be reported to ipmreporting@gov.bc.ca within 48 hours of the infraction's discovery.


Date Issued: August 28, 2026



Andreas Wins-Purdy, P.Ag.
Director, Recycling and Pesticide Authorizations
for Administrator – *Integrated Pest Management Act*



MAP OF HATZIC VALLEY INVASIVE KNOTWEED 2025 DISTRIBUTION & PROPOSED PESTICIDE USE PERMIT BOUNDARY (2026-29)



Date Issued: August 28, 2026


Andreas Wins-Purdy, P.Ag.
Director, Recycling and Pesticide Authorizations
for Administrator – *Integrated Pest Management Act*