
Vegetation Resources Inventory – British Columbia

Quality Assurance Procedures & Standards for Ground Sampling

Prepared by
Ministry of Forests, Lands and Natural Resource Operations
Forest Analysis and Inventory Branch

March 2018

Version 5.4

© The Province of British Columbia
Published by the
Resources Information Standards Committee

Digital Copies are available on the Internet at:

<https://www2.gov.bc.ca/gov/content/industry/forestry/managing-our-forest-resources/forest-inventory/ground-sample-inventories/vri-audits/standards>

Acknowledgments

The Government of British Columbia provides funding of the Resources Information Standards Committee work, including the preparation of this document. The Resources Information Standards Committee supports the effective, timely and integrated use of land and resource information for planning and decision making by developing and delivering focused, cost-effective, common provincial standards and procedures for information collection, management and analysis. Representatives to the Committee and its Task Forces are drawn from the ministries and agencies of the Canadian and the British Columbia governments, including academic, industry and First Nations involvement.

The Resources Information Standards Committee evolved from the Resources Inventory Committee which received funding from the Canada-British Columbia Partnership Agreement of Forest Resource Development (FRDA II), the Corporate Resource Inventory Initiative (CRII) and by Forest Renewal BC (FRBC), and addressed concerns of the 1991 Forest Resources Commission.

For further information about the Resources Information Standards Committee, please access the RISC website at:

<https://www.for.gov.bc.ca/hts/risc/>

For questions concerning the content of this publication please contact:

Manager, Vegetation Resources Inventory
Forest Analysis and Inventory Branch
PO Box 9512, Stn Prov Govt
Victoria, BC V8W 9C2
Phone: (250) 387-3650 Fax: (250) 387-5999

Major Amendments for 2018

1. Added a QA standard for damage agent severities under the Supporting Information Attributes section.

Table of Contents

Acknowledgments	iii
Major Amendments for 2018	v
Ground Sampling Quality Assurance Procedures	1
Introduction	1
Objectives	2
Feedback.....	2
Contract Administration	2
Audit Principles	2
Plot Selection.....	2
Sample Batches	3
Pass/Fail Standards.....	3
Batch Submission Requirements	3
General Procedures.....	3
Detailed Procedures.....	3
Selecting Sample Plots to be Audited	3
Office Checking	4
Field Audit.....	4
Preparing the Quality Assurance Report	5
Ground Sampling Quality Assurance Standards	7
Introduction	7
Timber Attribute Standards	9
Critical Pass/Fail Standards.....	10
Plot Cluster Location.....	10
Tree Attributes.....	10
Pass/Fail Point Standards	11
Plot Cluster Location.....	11
Tree Attributes.....	11
Sample Tree Attributes.....	11
Small Tree Attributes	11
Optional Critical Pass/Fail Standards.....	12
Supporting Information Attributes	13
Navigation and Layout	13

VRI Ground Sampling Quality Assurance Procedures & Standards

Tree Attributes	13
Stump Attributes	14
Ecological Attribute Standards	15
Critical Pass/Fail Standards	15
Supporting Information Attributes	15
Ecological Attributes	15
Coarse Woody Debris Attributes	16
Ecological Site Description.....	16
Soil Description	17
Vegetation Layers	18
Succession Interpretation	19
Appendix 1: Auditor’s List	21
Appendix 2: Audit Plot Selection List	23
Appendix 3: Audit Report Template.....	25

Ground Sampling Quality Assurance Procedures

Introduction

The Vegetation Resources Inventory (VRI) uses a two-phase sampling system to describe trees and other vegetation. The first phase (photo interpretation) involves the delineation of polygon boundaries and the estimation of a variety of vegetation polygon attributes from aerial photographs. The second phase (ground sampling) involves measurement of a variety of vegetation attributes at randomly selected ground sampling points within the Phase I polygons. A quality assurance audit is performed concurrently with the Phase II sampling.

Two monitoring/checking processes are used to ensure that quality field measurements are being collected in the ground sampling phase:

Quality Assurance is an external process, whereby the work is evaluated based on approved standards by an independent auditor and rated as having passed or failed. The auditor must be certified in VRI Ground Sampling Timber or Ecology depending on the data that is to be audited. The auditor must also be an experienced individual capable of conducting quality measurements and assessments to ensure the ground sampling procedures have been conducted within standards. There should be an arm's length relationship between the Quality Assurance auditor and the project and crew being evaluated.

Quality Control is an internal process, whereby the project manager ensures that the fieldwork is being done to the required standards in accordance with the procedures. This is the opportunity for the project manager to provide additional training to field crews.

The procedures described here are the quality assurance procedures developed by the Ministry of Forests, Lands and Natural Resource Operations (MFLNRO) to be implemented on all VRI ground sampling projects. It is expected that field sampling crews will have their own quality control procedures.

The objectives of the audit are to:

- provide feedback to improve sample quality, and
- provide information for contract administration.

The auditor identifies substandard sampling work and provides feedback to improve the crews' performance. Another important aspect of the auditor's work is to provide positive feedback to sampling crews on a task well done.

An important issue for contract managers is whether the completed work is acceptable. Several levels of standards have been established for the data collection.

- Pass/fail standards have been established for critical attributes.
- Optional pass/fail standards have also been established for the compiled gross and net volumes.
- Pass/fail point standards have also been established for specific attributes.
- Standards have also been established for supporting information that contributes to the location, establishment, and measurement of samples.

If the audit shows a batch does not meet these standards, the batch fails and the samples must be revisited.

VRI Ground Sampling Quality Assurance Procedures & Standards

The standards for ground sampling are included in this document and provide the standards of accuracy for VRI attributes measured from ground samples. A standard is a maximum allowable error for a given attribute. The standards are based on levels of precision achievable by auditors and were developed in consultation with a group of auditors in the various fields.

It is intended that quality assurance audits will be carried out as soon as possible after the samples are completed.

In order for the MFLNRO to ensure the data meets current standards, copies of all 3rd party quality assurance reports must be sent to the Ministry Representative as soon as the report is completed.

Objectives

The audit process has two main objectives:

- to provide feedback to improve sample quality, and
- to provide information for contract administration.

Feedback

Feedback from the audits is important for the continual improvement in sample establishment. The auditor will note any problems found in the audits so that the field crews will be aware of areas where they may require improvement. Positive feedback is also valuable in improving sample measurements. To successfully accomplish this objective the crews should be audited early in the project and subsequent batches should be audited as soon as possible after they are submitted. The field crews will benefit from accompanying the auditor in the field and are encouraged to attend, especially on the initial audits.

Contract Administration

The audit provides the contract administrator with information about the quality of the work being completed. Standards have been established for the location and measurement of samples. Contract administrators will use the pass/fail criteria as the basis for payment.

Audit Principles

Plot Selection

An audit system requires a statistically valid sample of ground samples. For the sample to be valid, four criteria must be met:

1. Batches of samples must be established. The criteria for defining a batch will be determined at the pre-work conference.
2. Audit samples must be chosen randomly within each batch except in specific "abnormal" circumstances as described in the detailed procedures.
3. The selection probability (i.e., number of audit samples divided by total number of samples) must be known and recorded.
4. The list of samples included in a batch must be recorded.

It is mandatory that a minimum of 10% of all samples should be audited and that auditing be more frequent (smaller batch sizes) at the beginning of the project.

Sample Batches

The exact batch size and composition of the batch will vary for each project and will be discussed at the pre-work conference.

To ensure that all types of data collected has been audited, auditors must also ensure that all sample types are audited in proportion to the numbers of samples by type in the project. For example if 15% of the samples in a project are NVAF enhanced samples (type N) then approximately 15% of the audits on the project must be on type "N" samples. Auditors should attempt to group sample types together in separate batches where possible.

To ensure early detection of potential errors the initial batch(s) should be small (3-5 samples) and should be separated by crew leader. Future batch sizes and the composition of each (for example, crew leader or company, low volume or high volume samples, immature versus mature) will be based on the outcome of the initial audits.

Pass/Fail Standards

Pass/fail standards have been established to ensure that the work meets minimum standards. These pass/fail standards are outlined in the *Ground Sampling Quality Assurance Standards* in this document.

Batch Submission Requirements

It is expected that all submitted batches will be complete as set out in the pre-work conference. This includes requirements for air photos, maps, field cards and any other project specific information. The field cards for all samples in the batch must be complete before the auditor will field audit any sample in the batch. All samples in the batch will be returned if the batch is not complete when submitted.

General Procedures

1. Select the samples to audit.
2. Perform office checking.
3. Perform field audit.
4. Prepare audit summary.

Detailed Procedures

The following is a suggested process to follow:

Selecting Sample Plots to be Audited

1. Determine the batch to be audited.
2. Randomly select the sample(s) to audit from the batch and document the selection. If "abnormal" weather, safety or access restrictions do not allow the sample to be audited, another audit sample may be randomly selected to satisfy contract administration requirements. Any time an audit sample is replaced the reasons must be documented.
3. A list of all the samples in each batch, the samples audited, dates audits were completed, and results of audits must be maintained. An example of an auditor's list is found in Appendix 1.

4. It is also mandatory that documentation around the random selection of audit samples be maintained as well. An example of such documentation is found in Appendix 2.

Office Checking

Complete an office evaluation of all samples in the batch. If any of the samples are incomplete or errors are noted, all samples will be returned and the audit will take place when the completed batch is returned. All corrections or additions to the field cards, after the field crew has left the field, must be done in **red** ink on the original cards.

Notify the field crew and project manager that an audit will take place. It is recommended that the original field crew accompany the auditor, especially in the early phase of the project.

Field Audit

Perform a field audit of the selected samples. All plots in the cluster must still be visited, however not all of the attributes will be measured in the audit. Key attributes have been identified that must be measured in all samples, while others have been identified to be measured on only a selected number of trees. The following is a list of attributes that must be checked during a standard audit. A complete audit of all attributes on any selected audit sample can also be done if the project manager decides it is necessary and is advisable at the start of a new project or with a new crew.

Audit for Timber Attributes

1. Check IPC pin location in the polygon.
2. Measure distance and bearing from Reference pin to IPC pin.
3. Measure all trees within the cluster for in/out confirmation.
4. Check all trees within the cluster for tree genus and species.
5. Check all trees within the cluster for live/dead status.
6. Select a minimum 5 measured trees within the plot cluster from the IPC and the enhanced auxiliary plot trees. Check the following attributes on these trees:
 - standing/fallen
 - DBH
 - length
 - crown class
 - first log grade
 - first log length
 - second log grade
 - second log length
 - broken top diameter
 - projected height
 - damage agents
 - loss indicators
7. Check sample tree selection on all plot locations.
8. Check all sample trees for the following attributes:
 - DBH
 - tree length
 - field bored age
 - pro-rate core length (if applicable)

9. Check the small tree plot for tree species identification and total tree count.
10. All other attributes should be evaluated to make sure they are within accepted standards. This is especially important at the beginning of a project or with a new crew.

Audit for Ecological Attributes

1. Coarse Woody Debris
 - Randomly select one transect.
 - For round pieces collect species, diameter and decay class for the piece.
 - For accumulations and/or odd shaped pieces, collect species, horizontal length and vertical depth on transect, and decay class for the piece.
2. Range
 - Use the same transect as randomly selected for the CWD.
 - Measure all values for the one transect.
3. Ecological description [EP]
 - Collect the following attributes [1] Uniformity, [2] Biogeoclimatic unit, [3] Site series and coverage, [4] SMR, [5] SNR, [6] Land cover classification, [7] Slope, [8] Aspect, [9] Elevation, [10] Surface shape, and [11] Meso slope. Collect 7 to 11 on card ED if required.
4. Tree and shrub layers [ET]
 - Collect the data as usual, excluding average height values, for all species with ≥ 1 % coverage. Do overall cover estimate for the A, B1 and B2 layers.
5. Herb and moss layers [EH]
 - Collect data as usual for those species with ≥ 1 % coverage. Do the overall % cover estimate for the C, and applicable D layers.
6. Succession interpretations [EO]
 - Collect all attributes as usual excluding attribute 29 (tree succession species).

After collecting the audit data, crosscheck the original plot data in the field to validate similar data and assess measurement differences.

No changes are to be made to the original field data cards at this time. If minor errors or data omissions have been identified that must be corrected, to enable the data to be processed, the entries will be entered in red ink on the original field cards. The project manager decides who will enter the data.

Document the major discrepancies or favourable measurements in the comments section on one of the audit field cards before leaving the sample.

The preliminary audit results should be presented to the field crew and project manager as soon as practical following the audit.

Preparing the Quality Assurance Report

1. Complete a report for each audit sample. The recommended sample summary report is included in Appendix 3. Summary reports can vary by project and any variance in format must be discussed at the pre-work conference.
2. If necessary, compile the audit sample to determine whether the data meets the established pass/fail criteria. If the pass/fail criteria are not met, the sample fails. In this case the “batch” of work will fail and the crew will be instructed to revisit, at their own

VRI Ground Sampling Quality Assurance Procedures & Standards

cost, all samples in the batch to correct the items identified as contributing to the rejection. The batch of samples will then be subjected to an additional audit.

3. Provide feedback to the field crews and project manager about any items that may need work.
4. The project manager will be advised in "writing" of the samples that comprised the batch, which sample was selected for audit, and the results of the audit. The audit summary will be attached for reference.
5. Copies of all audit reports are to be sent to the Ministry Representative as they are completed.

Ground Sampling Quality Assurance Standards

Introduction

This document contains the data collection standards for the Ground Sampling phase of the Vegetation Resources Inventory (VRI). The standards were established in consultation with quality assurance auditors, and after a review of audit field data, and are considered achievable by sampling crews.

The standards are based on the assumption that **all batches will be complete when submitted**. This means that all field cards must be completely filled out, photos and maps must meet the requirements as set out in the pre-work conference, and any other required information must be present as well. If the submitted batches are not complete they will not be accepted and will be returned to the field crew for completion. A batch is an identified number of samples to be completed by the field crew as determined at the pre-work conference.

The document has been separated into a timber section and an ecological section.

Timber Attribute Standards

There are three levels of timber attribute standards specified in this document:

- critical pass/fail standards;
- pass/fail point standards;
- Supporting information standards set for specific attributes and/or details. These attributes are not considered pass/fail criteria; however the established standards are expected to be met.

Critical pass/fail standards have been established for attributes that have an immediate impact on the ability to use the data for its main purpose of adjusting the Phase 1 inventory. If the standards are not met for any of these attributes the sample fails and the batch is rejected.

Pass/fail point standards have been established for many of the attributes that are important but individually do not have as large an impact on the overall result. Points are assigned when the measurement is outside the accepted standard. The sample is rejected when the percentage of penalty points versus penalty points possible exceeds 10%.

Optional critical pass/fail standards have also been established for volume and net value attributes. These attributes require the samples to be compiled before a determination can be made. The decision to use these optional standards will be made by the individual project managers.

Standards have been assigned to all other attributes which are considered as supporting information. It is still expected that the standards for these attributes are to be met. If it is found the attributes are repeatedly measured or conducted below standard the field crew may be required to revisit the batch to ensure project standards are attained.

It is expected that the standards will change over time. Feedback about these standards is appreciated and should be directed to:

Manager -Vegetation Resources Inventory
Ministry of Forests, Lands and Natural Resource Operations
Forest Analysis and Inventory Branch
PO Box 9512 Stn Prov Govt
Victoria, BC V8W 9C2

Critical Pass/Fail Standards

Critical pass/fail standards have been established for attributes that have an immediate impact on the ability to use the data for its main purpose of adjusting the Phase 1 inventory. If the standards are not met for any of these attributes the sample fails and the batch is rejected.

Plot Cluster Location

Attribute	Crew standard
Target polygon	no error permitted
Relative cluster location	± 30 metres when appropriate field ties available
Auxiliary plot locations	No error permitted in location of auxiliary plots in the target polygon with obvious typed boundaries (IE forest versus non forest, pure deciduous versus pure coniferous, etc).

Tree Attributes

Attribute	Crew Standard
Tree Count*	no error on clusters with ≤ 15 trees 1 error maximum for clusters with > 15 trees (missed and added trees do not cancel each other) 2 errors allowed for ½ and ¼ fixed radius plots with more than 30 trees
Tree Genus	1 error maximum per cluster
Tree Species	1 error maximum per cluster
Live/Dead	1 error maximum per cluster
DBH	Absolute variation ≤ 2% (sum of individual absolute differences/sum of audit DBHs)
Tree Length	Absolute variation ≤ 3% (sum of individual absolute differences/sum of audit heights)
Sample Tree Selection	No error allowed in determining the leading species and second species 1 error/cluster maximum in the selection of sample trees (includes all leading species, second species, and top height trees)
Net Factor	90% of the live tree net factors must be within ±10%** 90% of the dead tree net factors must be within ±20%** (samples with less than 10 logs, allowed one error) (the same log length must be used to determine the net factor)

* Borderline tree measurements will be assessed as follows: if the borderline 'in' or 'out' tree has been measured and the original in or out status using these measurements has been correctly determined, it will be accepted provided that the original critical distance calculated for the tree does not exceed one percent variation from the check plot critical distance, and the original horizontal distance measured for the tree does not exceed one percent variation from the check plot horizontal distance. For borderline trees only, the critical distance standard written here overrides the dbh standards written in this manual.

All quality assurance of borderline trees will be done using the plot radius factor to the tree face [PRF f]. The plot radius factor to the "tree face" is the plot radius factor to the tree center [PRF c] less 0.005. Using this method, the horizontal distance is measured from the plot center pin to the tree face at DBH.

**Example: net factor between 40% - 60% is acceptable for auditor's result of 50%

Pass/Fail Point Standards

Pass/fail point standards have been established for many of the attributes that are important but individually do not have as large an impact on the overall result. Points are assigned when the measurement is outside the accepted standard. The sample is rejected when the total points obtained is greater than 10% of the total points possible. If it is found that a given attribute is repeatedly measured or conducted below standard, even in a single field plot, the field crew may be required to revisit the batch to ensure project standards are attained.

Plot Cluster Location

Attribute	Standard	Point Value
Distance - reference pin to IPC (15.0 m)	± 0.2m	1
Azimuth - reference pin to IPC	± 2°	1
Replacement Auxiliary plot location selection	No error in selection based on random number table	1
Auxiliary plot location	Within correct polygon	1
Correct determination of border plot status for timber plot (full, half, quarter)	No error	1

Tree Attributes

These attributes must be checked on a minimum of five trees in the cluster. Point values are applied to each tree and are cumulative.

Attribute	Standard	Point Value
Stand/fall	Correctly identified	½
Diameter	± 3% or 0.3cm, whichever is greater	1
Tree length	± 5% or 0.2m, whichever is greater	2
Crown class	in correct class	½
First log grade	within 1 grade	½
First log length	± 30% of length	½
Second log grade	within 1 grade	½
Second log length	± 30% of length	½
Broken top diameter or Projected Height	± 20% of diameter or ± 10% of length	½
Damage agents	± 1 damage agent	½
Loss indicators	± 1 indicators identified	1

Sample Tree Attributes

These attributes must be measured on all sample trees (*top height, leading species, second species and random trees*).

Attribute	Standard	Point Value
Sample tree selection	No Error	1
Tree Length	± 3% or 0.2m, whichever is greater	2
Diameter	± 3% or 0.3cm, whichever is greater	1
Office Counted Age	± 3% or 3 years, whichever is greater	½
Pro-rate Core length	± 1.0 cm	½

Small Tree Attributes

Attribute	Standard	Point Value
Small tree species	90% correctly identified	½
Total trees	± 10%	½

Optional Critical Pass/Fail Standards

Optional critical pass/fail standards have also been established for volume and net value attributes. These attributes require the samples to be compiled before a determination on pass/fail status can be made. The decision to use these optional standards will be made by the project manager.

Attribute	Crew Standard
Gross volume (m ³ /ha) (4.0cm ⁺ live and dead)	± 10 m ³ for volumes ≤ 100 m ³ /ha ± 10% for volumes > 100 m ³ /ha
Net volume (m ³ /ha) (live trees 4.0cm ⁺)	± 10 m ³ for volumes ≤ 100 m ³ /ha ± 10% for volumes > 100 m ³ /ha
Net value (\$/m ³) (live trees 4.0cm ⁺)	± 15%

Supporting Information Attributes

Standards have been assigned to all other attributes which are considered as supporting information. It is still expected that the standards for these attributes are to be met. If it is found the attributes are repeatedly measured or conducted below standard the field crew may be required to revisit the batch to ensure project standards are attained.

Navigation and Layout

Attribute	Standard
Azimuth – tie point tree to tie point	± 2°
Azimuth – reference tree to reference pin	± 2°
Azimuth – tie point to Reference Pin	± 4°
Azimuth – IPC to auxiliary plots	± 4°
Distance from tie point to tie point tree	± 4% of distance
Distance from reference tree to reference pin	± 4% of distance
Distance from tie point to Reference Pin	± 5% of distance
Distance from IPC to auxiliary plots	± 2.0 m
Offset GPS distance to point	± 4% of distance
Random and second transect azimuth	± 4°
Transect length	± 0.5 m
Location of forage plots	± 0.2 m
Herb and bryoid plot (5.64 m)	± 0.2 m
Tree and shrub plot (10.0 m)	± 0.4 m
Azimuth for stem mapping	± 2°
Distance for stem mapping	± 2% of distance

Tree Attributes

Attribute	Standard
Field bored age	± 10%
Bark remaining %	± 10%
Height to live crown	± 2 m
Visual appearance	90% in correct or adjacent class
Crown condition	90% in correct or adjacent class
Bark retention	90% in correct or adjacent class
Wood condition	90% in correct or adjacent class
Lichen loading	90% in correct or adjacent class
Wildlife use	90% in correct class
Damage agent severity	Presence or absence for nominal severities; ± 1 class for ordinal severities; ± 10% for continuous severities
Position of loss indicator	± 1.0 m for indicator in lower 10 m ± 2.0 m for indicator in upper stem
Frequency	90% correctly identified
Bark thickness	± 2 mm or 20% (whichever is greater)
5 year growth	± 2 mm
10 year growth	± 4 mm
20 year growth	± 6 mm

Stump Attributes

Attribute	Standard
Stump species	90% correctly identified
Stump diameter inside bark	± 5 cm
Stump length	± 0.2 m
Stump percentage sound wood	± 20%
Stump bark retention code	90% in correct or adjacent class
Stump wood condition code	90% in correct or adjacent class

Ecological Attribute Standards

Critical pass/fail standards have been established for attributes that have an immediate impact on the final use of the data. If the standards are not met for any of these attributes the sample fails and the batch is rejected.

Standards have been assigned to all other attributes which are considered as supporting information. It is still expected that the standards for these attributes are to be met. If it is found the attributes are repeatedly measured or conducted below standard the field crew may be required to revisit the batch to ensure project standards are attained.

Critical Pass/Fail Standards

Critical pass/fail standards have been established for attributes that have an immediate impact on the final use of the data. If the standards are not met for any of these attributes the sample fails and the batch is rejected.

Attribute	Crew Standard
Range transect total shrub coverage (m)	± 15%
CWD – Gross volume (m ³ /hectare)	± 15%
Tree/shrub species identification ¹	> 90% of occurrences correctly identified
Herb/bryoid species identification ¹	> 80% of occurrences correctly identified

¹Species identification: the species is correctly listed as “counted” and “species correctly recorded” (either as a “known” or else collected and called an “unknown”) by the crew.

Supporting Information Attributes

Standards have been assigned to all other attributes which are considered as supporting information. It is still expected that the standards for these attributes are to be met. If it is found the attributes are repeatedly measured or conducted below standard the field crew may be required to revisit the batch to ensure project standards are attained.

Ecological Attributes

Attribute	Standard
Shrub species	85% [Maximum ± 2 added or missed]
Layer designation - B1 vs. B2	95% within correct layer
Shrub genus	90% within correct genus [Maximum 1 missed or added]
Phenology	95% within correct class
Transect – percent shrub coverage per species	± 10% of actual when coverage is < 10.0 m. ± 15% of actual when coverage is ≥ 10.0 m.
Graminoid and forb separation	90% of weight within correct designation
Forage utilization	95% in correct or adjacent class
Forage (dry wt.) abundance	± 2 grams if 0–50g ± 4% if ≥ 50g

Coarse Woody Debris Attributes

Attribute	Standard
CWD pieces	± 2 pieces per transect
Species	90% correct species identified for decay class 1, 2 or 3 pieces 75% correct species identified for decay class 4 or 5 pieces
Diameter	± 4 cm for stems < 40 cm ± 10% for stems ≥ 40 cm
Length (optional in VRI)	± 0.4 m for pieces < 10 m ± 5% for pieces > 10 m
Percent decay class 1	± 10% when sound portion > 80% ± 20% when sound portion < 80%
Other decay class	90/100 in correct class
Tilt angle	± 5°
Merchantability	80% correctly identified as “X” grade or better [Maximum 1 error]
Product to remove	98% in correct class [Maximum 1 error]
Decay class for the piece	90% in correct or adjacent class

Ecological Site Description

Attribute	Standard
Uniformity code	± 1 class
Zone	No error unless on a transition boundary
Subzone	No error unless on a transition boundary
Variant	No error unless on a transition boundary
Slope	± 5%
Aspect	± 20°
Elevation	± 50 metres
Surface shape	100% within correct or adjacent class
Meso-slope position	100% within correct or adjacent class
Microtopography	100% within correct or adjacent class
% coverage of cobbles & stones	± 5% if < 20% coverage; ± 10% if ≥ 20% coverage
% coverage of bedrock	± 5% if < 20% coverage; ± 10% if ≥ 20% coverage
Flood hazard	100% in correct or adjacent category
% coverage of flowing water	± 5% if < 20% coverage; ± 10% if ≥ 20% coverage
% coverage of standing water	± 5% if < 20% coverage; ± 10% if ≥ 20% coverage
Slope failure in plot	No error
Slope failure between plots	No error
Gullies within plot	No error
Gullies between plots	No error
Soil moisture regime	± one category
Soil nutrient regime	± one category
Site series number	no error unless on boundary transition (use SMR/SNR)
Land cover - level 1 (vegetated versus non vegetated)	no error unless on boundary of class
Land cover - level 2 (treed versus non-treed)	no error unless on boundary of class
Land cover - level 3 (wetland / upland / alpine)	no error unless on boundary of class
Land cover - level 4 (cover type)	± one category
Land cover - level 5 (density description)	± one category

Soil Description

Attribute	Standard
Soil horizons	main rhizosphere identified correctly, for other layers \pm one layer
Distance from zero for each layer	\pm 10 cm
Texture for each identified layer	100 % in correct or adjacent class
Total % coarse fragments	\pm 10% for fragments < 35 % \pm 20 % for fragments \geq 35 %
% gravel	\pm 10% for fragments < 35 % \pm 20 % for fragments \geq 35 %
% cobbles and stones	\pm 10% for fragments < 35 % \pm 20 % for fragments \geq 35 %
Depth to water table	\pm 10 cm
Depth to gleying	\pm 5 cm
Depth to root restricting pan	\pm 5 cm
Depth to bedrock	\pm 10 cm
Depth to frozen layers	\pm 10 cm
Depth to carbonates	\pm 10 cm
Humus form	no error within main category (mull, moder, mor)
Surficial material (primary layer)	no error
Soil colour	\pm one category
L/F/H description and depth	layers correctly identified and within 2 cm. Cumulative depth

Vegetation Layers

Attribute	Standard
Tree Species identified	90% correctly identified
Overall cover estimate “A” layer	± 10 % for cover > 25 % ± 5 % for cover 11 to 25 % ± 3 % for cover 6 to 10 % ± 0.5 % for cover 0.5 % to 5 %
Overall cover estimate “B1” layer	± 10 % for cover > 25 % ± 5 % for cover 11 to 25 % ± 3 % for cover 6 to 10 % ± 0.5 % for cover 0.5 % to 5 %
Shrub species identified	90% correctly identified
Overall cover estimate “B2” layer	± 10 % for cover > 25 % ± 5 % for cover 11 to 25 % ± 3 % for cover 6 to 10 % ± 0.5 % for cover 0.5 % to 5 %
Species coverage Layer “A”	± 10 % for cover > 25 % ± 5 % for cover 11 to 25 % ± 3 % for cover 6 to 10 % ± 0.5 % for cover 0.5 % to 5 %
Attribute	Crew Standard
Species coverage – layer “B1”	± 10 % for cover > 25 % ± 5 % for cover 11 to 25 % ± 3 % for cover 6 to 10 % ± 0.5 % for cover 0.5 % to 5 % ± 10% if “A” layer > 10% ± 5%
Species coverage – layer “B2”	± 10 % for cover > 25 % ± 5 % for cover 11 to 25 % ± 3 % for cover 6 to 10 % ± 0.5 % for cover 0.5 % to 5 %
Average height of B 1 layer	± 1 metre
Average height of B 2 layer	± 0.4 metres
Percent coverage by species of seedlings (Dh, Dw, and Dr)	± 10 % for cover > 25 % ± 5 % for cover 11 to 25 % ± 3 % for cover 6 to 10 % ± 0.5 % for cover 0.5 % to 5 %
Herb species identified	90% correctly identified
Bryoid species identified	80% correctly identified
Overall coverage of layer C	± 10 % for coverage > 30 % ± 5 % for coverage 16 to 30 % ± 2 % for coverage 6 to 15 % ± 1 % for coverage 1 to 5 %
Overall coverage of layer D	± 10 % for coverage > 30 % ± 5 % for coverage 16 to 30 % ± 2 % for coverage 6 to 15 % ± 1 % for coverage 1 to 5 %
Species ID ¹ -layer “C,Dh,Dw,Dr”	80/100 correct species

VRI Ground Sampling Quality Assurance Procedures & Standards

Species coverage – layer “C”	± 10 % for coverage > 30 % ± 5 % for coverage 16 to 30 % ± 2 % for coverage 6 to 15 % ± 1 % for coverage 1 to 5 %
Species coverage – layer “Dh”	± 10 % for coverage > 30 % ± 5 % for coverage 16 to 30 % ± 2 % for coverage 6 to 15 % ± 1 % for coverage 1 to 5 %
Species coverage – layer “Dw”	± 10 % for coverage > 30 % ± 5 % for coverage 16 to 30 % ± 2 % for coverage 6 to 15 % ± 1 % for coverage 1 to 5 %
Species coverage – layer “Dr”	± 10 % for coverage > 30 % ± 5 % for coverage 16 to 30 % ± 2 % for coverage 6 to 15 % ± 1 % for coverage 1 to 5 %

Species identification is for species listed as “known” by crew.

Succession Interpretation

Attribute	Standard
Factors influencing vegetation establishment	± one factor missed or added
Previous species	must have at least one species of two correctly identified
Current species	must have at least one species of two correctly identified
Tree harvesting	In correct or adjacent category
Presence of snags	In correct or adjacent category
Snags and CWD presence	In correct or adjacent category
Canopy gaps	In correct or adjacent category
Vertical structure	In correct or adjacent category
Successional stability	In correct or adjacent category
Tree size	In correct or adjacent category
Tree age	In correct or adjacent category
Structural stages	In correct or adjacent category
% old trees alive	± 10%
Old growth	“No” correctly identified “No (some) or Yes in correct or adjacent class

Appendix 1: Auditor's List

Vegetation Resources Inventory

Project Jones Creek

Sampling Crew Leader Bob Johnson Ecological Attributes

Random Order	Plot Cluster No.	Date Sample Completed	Audit Batch	Date Audited	Pass / Fail	Comments
1	27	May 12	1			
2	23	May 13	1	May 21	Pass	
3	7	May 15	1			
4	13	May 16	2			
5	17	May 17	2	May 26	Fail	
6	11	May 18	2			
7	3	May 19	2			
8	15	May 20	2			
9	19	May 23	3			
10	8	May 24	3			
11	20	May 25	3			
12	4	May 26	3	June 1	Pass	
13	13	May 28	2			Re-audit
14	17	May 28	2			Re-audit
15	11	May 29	2	June 1	Pass	Re-audit
16	3	May 29	2			Re-audit
17	15	May 30	2			Re-audit
18	47	June 1	4			
19	54	June 2	4			
20	12	June 3	4			
21	46	June 4	4			
22	5	June 7	4			
23	1	June 8	4			
24	16	June 9	4			
25	25	June 10	4	June 12	Pass	
26						
27						
28						
29						
30						
31						
32						
33						
34						
35						

Appendix 2: Audit Plot Selection List

Project: Jones Creek

Random Order	Sample Number	
1	27	Crew Leader <u>Bob Johnson</u>
2	23	
3	7	Batch # <u>1</u>
4		
5		Random # selected <u>2</u>
6		
7		Date <u>May 17, 2001</u>
8		
9		Auditor <u>J. Smith</u>
10		
11		
12		Ecology <input type="checkbox"/>
13		Trees <input checked="" type="checkbox"/>
14		
15		

Random Order	Sample Number	
1	13	Crew Leader <u>Bob Johnson</u>
2	17	
3	3	Batch # <u>2</u>
4	15	
5		Random # selected <u>2</u>
6		
7		Date <u>May 23, 2001</u>
8		
9		Auditor <u>J. Smith</u>
10		
11		
12		Ecology <input checked="" type="checkbox"/>
13		Trees <input checked="" type="checkbox"/>
14		
15		

Appendix 3: Audit Report Template

Project # _____ VRI Sample Audit Report
 Sample # _____

Establishment Crew: _____ Date: _____
 Audit Crew: _____ Date: _____

Batch #: _____
 Samples in Batch: _____

Overall Audit Summary:

Timber Attributes

Plot Cluster Location:

Critical Pass- Fail standards:

Attribute	Standard	Pass(P)/Fail(F)
Target polygon	No error permitted	
Relative cluster location	± 30 metres when appropriate field ties available	

Points standards:

Attribute	Standard	Possible Points	Points Obtained
Distance - reference pin to IPC (15.0 m)	± 0.2m	1	
Azimuth - reference pin to IPC	± 2°	1	
Total Plot Cluster			

Plot Cluster Attribute comments (including supporting attributes):

Tree Attributes:

Critical Pass-Fail Standards:

Attribute	Standard	Pass(P)/Fail(F)
Tree Count*	No error on clusters with ≤ 15 trees 1 error maximum for clusters with > 15 trees (missed and added trees do not cancel each other) 2 errors allowed for $\frac{1}{2}$ and $\frac{1}{4}$ fixed radius plots with more than 30 trees	
Tree Genus	1 error maximum per cluster	
Tree Species	1 error maximum per cluster	
Live/Dead	1 error maximum per cluster	
DBH	Average absolute variation $\leq 2\%$ (sum of individual absolute differences/sum of audit DBHs)	
Tree Length	Average absolute variation $\leq 3\%$ (sum of individual absolute differences/sum of audit heights)	
Sample Tree Selection	No error allowed in determining the leading species and second species 1 error/cluster maximum allowed in the selection of sample trees (includes all leading species, second species, and top height trees)	
Net Factor	90% of the live tree net factors must be within $\pm 10\%^{**}$ 90% of the dead tree net factors must be within $\pm 20\%^{**}$ (samples with less than 10 logs, allowed one error) (the same log length must be used to determine the net factor)	

Points standards:

Attribute	Standard	Per Tree Point Value	Number of Trees	Possible Points (Point Value times number of trees audited)	Points Obtained
Stand/fall	Correctly identified	$\frac{1}{2}$			
Diameter	$\pm 3\%$ or 0.3cm	1			
Tree length	$\pm 5\%$ or 0.2m	2			
Crown class	In correct class	$\frac{1}{2}$			
First log grade	Within 1 grade	$\frac{1}{2}$			
First log length	$\pm 30\%$ of length	$\frac{1}{2}$			
Second log grade	Within 1 grade	$\frac{1}{2}$			
Second log length	$\pm 30\%$ of length	$\frac{1}{2}$			
Broken top diameter/ projected height	$\pm 20\%$ of diameter or $\pm 10\%$ of length	$\frac{1}{2}$			
Damage agents	± 1 damage agent	$\frac{1}{2}$			
Loss indicators	± 1 indicator	1			
Total Points					

VRI Ground Sampling Quality Assurance Procedures & Standards

Tree attribute comments (including supporting attributes and optional pass fail criteria):

Sample Tree Attributes:

Attribute	Standard	Point Value	Number of Trees	Possible Points (Point Value times number of trees audited)	Points Obtained
Sample Tree selection	No error	1			
Tree Length	± 3% or 0.2m	2			
Diameter	± 3% or 0.3cm	1			
Office Counted Age	± 3% or 3 years	½			
Pro-rate Core length	± 1.0 cm	½			
Total					

Sample Tree attribute comments (including supporting attributes):

Small Tree Attributes:

Attribute	Standard	Point Value	Points Obtained
Small tree species	90% correctly identified	½	
Total trees	± 10%	½	
Total			

Small Tree attribute comments (including supporting attributes):

Total Timber Attribute Points Summary:

Section	Points possible	Points obtained		
Plot Cluster Location				
Tree Attributes				
Sample Tree Attributes				
Small Tree Attributes			Percentage *	Pass/Fail
Total (Must be less than 10% to pass)			%	

Overall Timber attribute comments:

Ecological Attributes

Critical Pass/Fail Standards:

Attribute	Crew Standard	Pass(P)/Fail(F)
Range transect total shrub coverage (m)	± 15%	
CWD – Gross volume (m ³ /hectare)	± 15%	
Tree/shrub species identification	> 90% of occurrences correctly identified	
Herb/bryoid species identification	> 80% of occurrences correctly identified	

Ecological Attribute comments (including supporting attributes):

Attach a table showing DBH and Length calculations, as well as other supporting information as required.

Add additional pages as necessary for further comment.