Okanagan Lake Collaborative Monitoring Agreement
2023 Summary Report

Prepared for:
Okanagan Basin Water Board
City of Kelowna
Regional District of Central Okanagan
District of Summerland
BC Ministry of Environment and Climate Change Strategy

Larratt Aquatic Consulting Ltd. 105-2081 McDougall Rd. West Kelowna B.C. V1Z 4A2
Phone: 250.769.5444 www.lakebiology.ca

Executive Summary

The British Columbia Ministry of Environment and Climate Change Strategy (BC ENV) in partnership with local municipalities, commissioned an annual collaborative monitoring program to sample water quality in Okanagan Lake every year since 2011. Now operated by the Okanagan Basin Water Board (OBWB), sampling occurred monthly from March to September at four locations in 2023.

A primary function of the monitoring was to determine attainment of Okanagan Lake water quality objectives, along with increasing the temporal resolution of water quality data for Okanagan Lake, specifically with the goal of determining trends in nutrient and biological data. Similar to previous years, parameters such as temperature and dissolved oxygen were measured throughout the water column as well as several chemical parameters including silica, nitrogen, and phosphorus at discrete depths. Biological data including phytoplankton and zooplankton biomass with taxonomic identification were also collected. This report summarizes the 2023 findings and sets these recent data within the context of this program (2011-2023).

The results to date indicate that the Armstrong Arm is the most impacted by human activities and watershed degradation. These impacts include including agriculture, cattle range, logging, septic systems adjacent to the shoreline, and now the White Rock Lake wildfire. This site had the most exceedances and the most parameters trending towards greater exceedances. Weather was the dominant factor on water quality at Okanagan Centre, Kelowna, and Summerland but long-term data still demonstrates human impacts.

Physical

Okanagan Lake is usually stratified from May to November, it mixes in mid-November and then freely mixes over the winter. Secchi depth was highest in late winter and decreased each spring in response to increased phytoplankton activity. Water clarity was below average for Okanagan Lake in 2023 because of high algae production. All sites failed to meet the Secchi depth objective in 2023.

Chemical

Dissolved oxygen (DO) is essential for all aquatic animals and is high throughout Okanagan Lake at all times except in the hypolimnion of the Armstrong Arm where DO fell below the water quality objective each summer including 2023. Silica, an important micronutrient, had stable concentrations in Okanagan Lake over the past 20 years.

Total nitrogen (TN) exceeded the objective at Summerland, Kelowna, and Okanagan Centre during 2023 as it did in most years. Previously identified increasing trends in TN and nitrate paused with a stable period over the past few years while TN declined in the Armstrong Arm since 2017. This is an encouraging result but the long-term increasing trend may resume in future years.

Total phosphorus (TP) had a year-over-year increasing trend at all sites from 2011-2023, and forms part of a longer-term trend since the mid-2000s. TP includes phosphorus associated

with suspended sediment carried into the lake. It increased in Okanagan Lake during wet years such as 2017-2018 and decreased during dry years such as 2019 and 2021. Dissolved phosphorus is less affected by freshets than TP and was stable or declining at the three main basin sites while it also increased in the Armstrong Arm.

The ratio of total nitrogen to total phosphorus (N:P) available to phytoplankton will play a major role in which types of phytoplankton proliferate in a lake. A lower N:P ratio (abundant phosphorus relative to nitrogen) will favour the growth of cyanobacteria. The N:P ratio failed to meet the objective in the Armstrong Arm in 2023 with a downwards trend at all sites.

Biological

Chlorophyll-a was used as a measure of photosynthetic activity in Okanagan Lake. A decreasing north to south trend in the chlorophyll-a data occurred over the course of this study. All sites met the chlorophyll-a objectives during 2023. However, a significant increasing trend occurred at Kelowna and Armstrong Arm from 2011-2023, part of a trend since the mid-2000s.

Phytoplankton abundance during 2023 was high compared to 2011-2023 because of elevated cyanobacteria densities. All sites did not meet the phytoplankton biovolume objective nor did they meet the phytoplankton taxonomy objective during 2023 because of elevated cyanobacteria densities, particularly the Armstrong Arm.

Zooplankton results were not available at the time of writing but will be added as revised version of this report when they are available.

The following areas of concern have been identified that may require further investigation on the part of the Ministry:

- Chronically low Secchi depth in the Armstrong Arm
- Increasing nitrate in hypolimnion of Okanagan Lake since 1970s (although stable during past 5 years)
- Increasing total phosphorus at all sites except Summerland since early 2000s
- Decreasing N:P ratio in the Armstrong Arm
- High densities of potentially toxic cyanobacteria in Armstrong Arm during 2018-2021
- Role of Climate Change in water quality changes in Okanagan Lake
- Phosphorus loading to the Armstrong Arm and north basin of Okanagan Lake from the White Rock Lake wildfire

Water Quality Objectives, 2011-2023 Values, and Trends for Okanagan Lake

Table 1: Okanagan Lake water quality objectives

Parameter (Nordin, 2005)	**Summerland**	**Kelowna**	**Ok Centre**	**Armstrong Arm**
Secchi Depth (growing season average: Apr-Sep)	>7m	>6m	>6m	>5m
Dissolved Oxygen (minimum in bottom waters)	-	-	-	>5 mg/L
TP (mg/L as P) (maximum at spring overturn)	<0.007	<0.008	<0.008	<0.01
Chlorophyll-a (µg/L) (maximum seasonal average)	<4.5	<4.5	<4	<5
TN (mg/L as N) (maximum at spring overturn)	<0.230	<0.230	<0.230	<0.250
N:P Ratio (spring weighted ratio)	>25:1	>25:1	>25:1	>25:1
Algae Taxonomy (% heterocystous cyanobacteria)	<5%	<5%	<5%	<5%
Algae Biomass (µL/L) (growing season average)	<0.75	<0.75	<0.75	<0.75
Zooplankton Biomass (µg/L) (growing season average)	>50	>50	>50	>50
Zooplankton Taxonomy (% cladocerans)	>5%	>5%	>5%	>5%

Table 2: Attainment of Okanagan Lake water quality objectives compared to growing season averages during 2023

Objective	Summerland	Kelowna	Ok Centre	Armstrong Arm
Secchi Depth	6.0	5.3	5.8	2.8
Dissolved Oxygen	7.88	8.23	8.30	2.13
TP (mg/L) 0:10m:	0.005	0.006	0.007	0.012
20-45m:	0.005	0.005	0.006	0.019
Chlorophyll-a (µg/L)	1.74	1.97	2.16	3.08
TN (mg/L) 0-10m:	0.216	0.220	0.22	0.244
20-45m:	0.237	0.237	0.239	0.280
N:P Ratio 0-10m:	59:1	49:1	33:1	20:1
20-45m:	57:1	47:1	41:1	18:1
Algae Taxonomy (% heterocystous cyanobacteria)	12.5%	13.6%	12.5%	44.2%
Algae Biovolume (µL/L)	0.790	1.135	1.004	0.814
Zooplankton Biomass (µg/L)	6.1	10.4	9.5	11.5
Zooplankton Taxonomy (% cladocerans)	7.9	0.2	5.3	2

Legend:

Achieved objective	Achieve objective in some but not all samples	Did not achieve objective

Table 3: Summary of trends compared to attainment of water quality objectives in Okanagan Lake during 2011-2023

Objective	Summerland	Kelowna	Ok Centre	Armstrong Arm
Secchi Depth	-	-	-	-
Dissolved Oxygen	-	-	-	-
TP (mg/L) 0:10m:	↑	↑	↑	↑
Chlorophyll-a (µg/L)	-	↑	-	↓
TN (mg/L) 0-10m:	-	-	-	↓
N:P Ratio 0-10m:	↓	↓	↓	↓
Algae Taxonomy (% heterocystous cyanobacteria)	↑	↑	↑	↑
Algae Biovolume (µL/L)	↑	↑	-	-
Zooplankton Biomass (µg/L)	-	-	-	-
Zooplankton Taxonomy (% cladocerans)	-	-	-	-

Legend:

Achieved objective	Achieve objective in some but not all samples	Did not achieve objective

Preferred Citation

Self, J., 2024. Okanagan Collaborative 2023 Summary Report. Prepared by Larratt Aquatic Consulting Ltd. Prepared for Okanagan Basin Water Board.

Report prepared by: Larratt Aquatic Consulting Ltd.

Jamie Self: BSc, RPBio
Senior Aquatic Biologist



Copyright and Disclaimer: This document is for the sole use of Okanagan Basin Waterboard (OBWB) and British Columbia Ministry of Environment and Climate Change Strategy (ENV) and Larratt Aquatic Consulting Ltd. (LAC). This report contains information that shall not be reproduced in any manner without the written permission of OBWB or ENV. In preparing this report, LAC exercised the level of care and skill normally exercised by science professionals, subject to the same time, financial and physical constraints applicable to the services. This report includes data gathered during the investigations and the authors' professional judgement considering those investigations at the time of report writing. No liability is incurred by LAC, OBWB, or ENV for accidental omissions or errors made in the preparation of this report, or for results obtained from use of this information by another party.

Table of Contents

Okanagan Collaborative 2023 Report 1
Executive Summary 2
Water Quality Objectives, 2011-2023 Values, and Trends for Okanagan Lake 4
Table of Contents 7
Table of Figures and Tables 8
Definitions 10
1.0 Introduction 11
1.1 Overview 11
1.2 Weather and Climate Conditions in 2023 13
2.0 Results & Discussion 15
2.1 Physical 15
2.1.1 Temperature 15
2.1.2 Water Clarity and Secchi Depth 16
2.2 Chemistry 19
2.2.1 Dissolved Oxygen 19
2.2.2 Silica 20
2.2.3 Nitrogen and Phosphorus 21
2.3 Biology 28
2.3.1 Phytoplankton 28
2.3.2 Zooplankton 34
3.0 Conclusions 37
4.0 Recommendations 41
5.0 References 42
6.0 Appendices 44
6.1 Appendix 1: 2011-2023 Sampling Data 44
6.2 Appendix 2: Statistics and Graphing Overview 45

Table of Figures and Tables

Figure 1: Okanagan Basin Watershed with four sampling locations identified 12
Figure 2: Water level in Okanagan Lake at Kelowna from 2016-2023 13
Figure 3: Water level in Okanagan Lake during 2023 compared to previous 10 years 14
Figure 4: Temperature profiles for Okanagan Lake at Summerland (left) and Armstrong Arm (right), 2023 15
Figure 5: Temperature at Okanagan Lake sampling sites during 2023 compared to 2011-2022 16
Figure 6: Secchi depth at Okanagan Lake sampling sites during 2023 compared to 2011-2022 18
Figure 7: Annual average secchi depth in Okanagan Lake from 1973-2023 18
Figure 8: Dissolved oxygen profiles for Okanagan Lake at Summerland (left) and Armstrong Arm (right) during 2023 20
Figure 9: Annual average silica concentration in Okanagan Lake at each sampling site by year with trends highlighted, 1973-2023 21
Figure 10: Annual average total nitrogen in Okanagan Lake, 2011-2023 22
Figure 11: Annual average nitrite (NO_2) + nitrate (NO_3) in mg/L as N in the deep water of Okanagan Lake, 2011-2023 23
Figure 12: Nitrate + nitrite in Okanagan Lake at Armstrong Arm by month illustrating seasonal accumulation of nitrate in low oxygen hypolimnion, 2011-2023 23
Figure 13: Annual average total phosphorus in Okanagan Lake at the three major basin sampling sites by year from 2011-2023 25
Figure 14: Total phosphorus in the Armstrong Arm, 2011-2023 26
Figure 15: Annual average dissolved phosphorus in Okanagan Lake illustrating declining long-term trend at Okanagan Centre, Kelowna, and Summerland from 2011-2023 27
Figure 16: Nitrogen to phosphorus ratio at Okanagan Lake sampling sites 2011-2023 28
Figure 17: Annual chlorophyll-a concentration at the four Okanagan Lake sampling sites, 2011-2023 29
Figure 18: Phytoplankton Biovolume at Summerland and Kelowna, 2015-2023 30
Figure 19: Taxonomic breakdown of algae by major types during 2023 32
Figure 20: Total algae, cyanobacteria, and diatom counts in Okanagan Lake, 2011-2023 33
Figure 21: Percent of total algae counts that were heterocystous cyanobacteria, 2011-2023 34
Figure 22: Zooplankton Biomass at the Okanagan Lake sampling locations by year, 2015-2023 35

Table 1: Okanagan Lake water quality objectives 4
Table 2: Attainment of Okanagan Lake water quality objectives compared to growing season averages during 2023 5
Table 3: Summary of trends compared to attainment of water quality objectives in Okanagan Lake during 2011-2023 5
Table 4: GPS coordinates of sampling sites 11
Table 5: Growing Season (Apr-Sep) Secchi depth in meters at Okanagan Lake sampling sites, 2023 17
Table 6: Silica concentration in mg/L at Okanagan Lake sampling sites, 2023 21
Table 7: Total nitrogen in mg/L as N concentration at Okanagan Lake sampling sites, 2023 .22

Table 8: Total phosphorus (mg/L as P) at Okanagan Lake sampling sites during 2023.....24
Table 9: Ratio of average TN to average TP during spring at Okanagan Lake sampling locations, 2011-2023.....28
Table 10: Chlorophyll-a in µg/L at Okanagan Lake sampling sites, 2023.....29
Table 11: Phytoplankton biovolume in µL/L at Okanagan Lake sampling sites, 2023.....30
Table 12: Average phytoplankton counts by major algae groups in cells/mL, 2023.....31
Table 13: Percent of total algae counts that were heterocystous cyanobacteria from 2023.....34
Table 14: Zooplankton biomass in µg/L at Okanagan Lake sampling sites, 2023.....34
Table 15: Growing Season average percent cladocerans zooplankton, 2023.....36
Table 14: Okanagan Lake Water Quality Objectives.....39
Table 15: Attainment of Okanagan Lake water quality objectives compared to growing season averages during 2023.....40
Table 16: Summary of trends (2011-2023) and the water quality objectives for Okanagan Lake collaborative sampling program during 2023.....40

Definitions

The following terms are defined as they are used in this report.

Term	Definition
Algae bloom	A superabundant growth of algae that may result in surface scum depending on type of algae that is blooming
Anoxic	Devoid of oxygen
Bioavailable	Available for use by plants or animals
Chlorophyll-a	Primary photosynthetic pigment in algae; used as a measure of photosynthetic activity
Cyanobacteria	Bacteria-like algae having cyanochrome as the main photosynthetic pigment
Diatoms	Algae that have hard, silica-based "shells" frustules
Fall overturn	Surface waters cool and sink, until a fall storm mixes the water column
Eutrophic	Nutrient-rich, biologically productive water body
Hypoxic	Very low dissolved oxygen
Macronutrient	The major constituents of cells: nitrogen, phosphorus, carbon, sulphate, H
Micronutrient	Small amounts are required for growth; Si, Mn, Fe, Co, Zn, Cu, Mo etc.
Microflora	The sum of algae, bacteria, fungi, *Actinomycetes,* etc., in water or biofilms
Monomictic	"One Mixing": describes lakes that are thermally stratified in summer and mixed in winter
Nutrient limitation	A nutrient will limit or control the potential growth of organisms e.g. P or N
Phytoplankton	Algae that float, drift or swim in water columns of reservoirs and lakes
Plankton	Those organisms that float or swim in water
Riparian	The interface between land and a stream or lake
Secchi depth	Depth where a 20 cm Secchi disk can be seen; measures water transparency
Thermocline	The lake zone of greatest change in water temperature with depth (> 1°C/m); it separates the surface water (epilimnion) from the cold hypolimnion below
Zooplankton	Minute animals that graze algae, bacteria and detritus in water bodies

Term	Definition
AFDM	Ash-free dry mass
Chl-a	Chlorophyll-a units µg/L
DO	Dissolved oxygen units mg/L
N	Nitrogen units mg/L as N
Ortho-P	Orthophosphate ≈ SRP monomeric inorganic phosphorus units mg/L as N
P	Phosphorus units mg/L as P
DIN	Dissolved inorganic nitrogen = ammonia + nitrate + nitrite units mg/L as N
TDN	Total dissolved nitrogen = ammonia + nitrate + nitrite + dissolved organic N units mg/L as N
TDP/DP	Total dissolved phosphorus units mg/L as P
TN	Total nitrogen: organic + dissolved units mg/L as N
TP	Total phosphorus: organic + dissolved units mg/L as P

Lake Classification by Trophic Status Indicators (Nordin, 1985)

Trophic Status	chlorophyll-a ug/L	Total P ug/L	Total N ug/L	Secchi disc m	Phytoplankton density (cells/mL)	Phytoplankton biomass (mg/m^3)
Oligotrophic	0 – 2	1 – 10	<100	> 6	<1000	0-500
Mesotrophic	2 – 5	10 – 20	100 – 500	3 – 6	1000-5000	500-2000
Eutrophic	>5	> 20	500-1000	< 3	>5000	>2000

Nutrient Balance Definitions for Microflora (Dissolved Inorganic N : Dissolved Inorganic P) (Nordin,1985)

Phosphorus Limitation	Co-Limitation of N and P	Nitrogen Limitation
>15 : 1	<15 : 1 – 5 : 1	5 : 1 or less

1.0 Introduction

1.1 Overview

The British Columbia Ministry of Environment and Climate Change Strategy (ENV) in partnership with the City of Kelowna, the Regional District of Central Okanagan, and the District of Summerland began a seasonal sampling program of Okanagan Lake in 2011 to increase the temporal resolution of water quality data being gathered. This program was performed collaboratively between ENV staff, Okanagan Nation Alliance (ONA; 2011), and Larratt Aquatic Consulting (2012-2023). The current program is overseen by the Okanagan Basin Water Board (OBWB). Okanagan Lake was sampled monthly from March to September from 2011-2023 at four key sites (Figure 1, Table 4).

Table 4: GPS coordinates of sampling sites

Site Name	EMS ID	Latitude	Longitude
Summerland	0500454	49.600550°	-119.628030°
Kelowna	0500236	49.861350°	-119.513420°
Ok Centre	0500730	50.089900°	-119.478270°
Armstrong Arm	0500239	50.315450°	-119.357180°

Note: EMS = Environmental Monitoring System and serves as ENV's database of water quality

Sampling focused on three broad subjects at each site: physical parameters, water chemistry, and biological activity.

Physical parameters including temperature profiles were taken at each site on each date to build a composite image of conditions in Okanagan Lake over time (Figure 4). Secchi depth, a measure of water clarity, was also recorded for each site.

In addition, dissolved oxygen profiles were taken and a range of parameters were chemically analyzed from samples taken in the epilimnion (1-5-10 m composite) and the hypolimnion (20-32-45 m composite). Chemistry focused on the major nutrients in their various forms. Chemistry results were analyzed by ALS Environmental throughout this study.

Biological sampling included generic parameters such as chlorophyll-a concentration and biomass, as well as detailed taxonomic classification of phytoplankton (algae) and zooplankton.

The 2023 data were added to the existing 2011 – 2022 database upon which all the analyses in this report were performed. Water quality objectives were based upon Nordin (2005) (Appendix 1).



Figure 1: Okanagan Basin Watershed with four sampling locations identified

1.2 Weather and Climate Conditions in 2023

The weather during any given year will have a major impact on physical conditions, water chemistry, and biological activity in Okanagan Lake during that and subsequent years. The weather during 2023 was another unusual year for the Okanagan climate (Figure 2). Spring was cooler than normal for the Okanagan with a large freshet in the Mission Creek watershed followed by a shift to hot dry weather that extended through the end of the year; 2023 was the driest year on record for the Okanagan. The water level of Okanagan Lake was held near normal despite the very hot and dry conditions because of very low outflows in the Okanagan River (Figure 3). The summer drought primed the conditions for the McDougall Creek wildfire that devastated West Kelowna. Numerous large wildfires have occurred recently within the Okanagan that affect the hydrology of the watershed. For example, damage to the Whiteman Creek watershed from the 2021 White Rock Lake wildfire caused major flooding and infrastructure damage during the large 2023 freshet. This type of extreme weather is expected to become more frequent and more intense because of Climate Change.



Figure 2: Water level in Okanagan Lake at Kelowna from 2016-2023
Source: (Water Office, 2024)



Figure 3: Water level in Okanagan Lake during 2023 compared to previous 10 years
Source: (Water Office, 2024)

2.0 Results & Discussion

2.1 Physical

2.1.1 Temperature

Okanagan Lake is a deep monomictic lake. From May to November each year, the surface water (epilimnion) is thermally isolated from the deep water (hypolimnion) by a thermocline. The sun warms the epilimnion to over 20 °C each summer while water below 20 m changes temperature by less than 4 °C annually (Figure 4).

The three main basin sites (Summerland, Kelowna, and OK Centre) exhibit similar thermal behavior while the northern Armstrong Arm site is shallower and reaches a higher surface temperature each summer (Figure 4). Thermal stratification in Okanagan Lake breaks down each November and the water column freely circulates through the winter. There were no statistically significant trends in the 2011–2023 temperature data either annually, seasonally (Mann-Kendall trend tests).



Figure 4: Temperature profiles for Okanagan Lake at Summerland (left) and Armstrong Arm (right), 2023

Notes: Lines represent contours of same temperature or dissolved oxygen within the water column through time. Samples not collected during March 2020 at Armstrong Arm because of ice-cover

Surface water temperatures of Okanagan Lake at all four sites were below average throughout the cool, wet spring before transitioning to above average during the late spring into fall months (Figure 5). Surface temperatures during May and June were among the warmest recorded for that time of year (Figure 5).



Figure 5: Temperature at Okanagan Lake sampling sites during 2023 compared to 2011-2022

2.1.2 Water Clarity and Secchi Depth

Water clarity, as measured by Secchi depth, ranged from a minimum of only 1.8 m at Armstrong Arm in May to a maximum of 11.7 m at Okanagan Centre in March during 2023 (Table 5). Secchi depth annual averages were below the 2011-2022 average during 2023 (Figure 6, Figure 7). All sites failed to meet their respective objectives during 2023 (Table 5). The overall average for Okanagan Lake historically has been 6.5-6.6 m but averaged 5.6 ± 2.9 m in 2023 (Andrusak et al., 2006; Nordin, 2005). The relatively low water clarity during 2022 may relate to an increasing trend in chlorophyll-a observed throughout the lake during the past 10 years (Figure

17). Extensive watershed damage from recent large wildfires also contributes fine sediment and nutrients to Okanagan Lake that directly and indirectly impair water clarity.

Secchi depth followed a consistent pattern each year. Maximum Secchi depths occurred in the late winter when biological activity was the lowest. During increased spring algal growth and freshet, the Secchi depth dropped dramatically to the lowest of the year at all sites. As nutrients were used up, algae concentrations diminished, and water clarity increased through the summer and into the fall (Figure 6).

The Secchi depth in the Armstrong Arm was much lower than at the other sites in Okanagan Lake during all years. This is clearly illustrated in Figure 7. Secchi depth was stable from 2011-2023 and there were no statistically significant year-over-year trends in the Secchi depth data from 2011-2023 but there was a significant drop when the 1973-2023 historical data was considered (Mann-Kendall tests, Figure 7). This long-term trend is related to a period of high water-clarity in the years following the installation of nutrient removal systems at wastewater treatment plants; the current lower water clarity likely relates to the cumulative effects of increased population and human activities within the Okanagan watershed over the past 30 years.

Table 5: Growing Season (Apr-Sep) Secchi depth in meters at Okanagan Lake sampling sites, 2023

Site	Objective	Average	StdDev	Max	Min
Summerland	7.0	6.0	1.5	8.3	4.1
Kelowna	6.0	5.3	1.5	7.4	3.4
Ok Centre	6.0	5.8	3.1	11.4	2.5
Armstrong Arm	5.0	2.8	0.8	3.8	1.8

Note: Objective refers to growing season average (Apr-Sep); Coloured shading indicates status of objective during that year with green meaning met objective and red meaning failed to meet objective



Figure 6: Secchi depth at Okanagan Lake sampling sites during 2023 compared to 2011-2022



Figure 7: Annual average secchi depth in Okanagan Lake from 1973-2023

2.2 Chemistry

Chemistry sampling focused on dissolved oxygen, nitrogen and phosphorus (the most important aquatic nutrients), and silica, a key micronutrient. Increasing nutrient trends frequently result from human activities such as wastewater effluent disposal, riparian degradation, agriculture, fertilizer use, storm water, etc. These human-caused impacts are gradual and are easiest to detect as year-over-year trends.

2.2.1 Dissolved Oxygen

Dissolved oxygen (DO) is essential for all aquatic animals. Low DO will stress fish and possibly preclude them from certain portions of the water column. Hypoxic conditions occur when DO is very low (<2 mg/L) and this has a profound impact on water chemistry through the mobilization of nutrients and metals from the sediment. The three major basin sites (Summerland, Kelowna, and OK Centre) exhibit similar thermal and high dissolved oxygen behavior while the northern Armstrong Arm site is shallower and behaves differently. The later reaches a higher surface temperature and experiences a reduction in dissolved oxygen in the deep water each summer (Figure 8). The reduction in dissolved oxygen is caused by decomposition of organic material in the sediment and deep water and can lead to internal nutrient loading if oxygen becomes depleted. The Armstrong Arm is the only site with a dissolved oxygen objective (>5 mg/L in bottom water), a threshold that it fails to meet every year. By September 2022, the low dissolved oxygen zone (depth below red line in Figure 8) had expanded to 35 m thick with a minimum concentration of only 2.13 mg/L.



Figure 8: Dissolved oxygen profiles for Okanagan Lake at Summerland (left) and Armstrong Arm (right) during 2023

Dissolved oxygen profile illustrates high dissolved oxygen concentrations at Summerland and characteristic oxygen depletion in deep waters of the Armstrong Arm. Lines represent contours of same dissolved oxygen within the water column through time. Note: The red line on dissolved oxygen plot represents Water Quality Objective; all water below this line does not meet the objective.

2.2.2 Silica

Diatoms, a major group of algae in Okanagan Lake, use silica (measured as dissolved silica) as a structural building block for their cell walls. While no objectives for silica concentrations in Okanagan Lake have been set, monitoring continues as silica is a key micronutrient for this important group of algae. Silica sampling shifted to only March and September beginning in 2015 because it did not change significantly over the course of the growing season from 2011-2014. Silica was higher during 2017-2018, likely an effect of the flooding and intense freshets during those years, but when looking at the long-term data, there was an increasing trend from the 1970s to 2000 followed by a period of stability since 2000 (Table 6, Figure 9).

Table 6: Silica concentration in mg/L at Okanagan Lake sampling sites, 2023

Site	Average	StdDev	Max	Min
Armstrong Arm	8.06	1.10	10.30	6.78
Kelowna	6.69	0.50	7.32	5.89
Ok Centre	7.06	0.47	7.64	6.39
Summerland	6.35	0.99	7.31	3.27



Figure 9: Annual average silica concentration in Okanagan Lake at each sampling site by year with trends highlighted, 1973-2023

2.2.3 Nitrogen and Phosphorus

Nitrogen and phosphorus are the most important nutrients in most aquatic environments. Nutrient limitation occurs when an essential element (most commonly nitrogen and/or phosphorus) is in relatively short supply. Algae production is limited by the availability of that nutrient despite potential abundance of other nutrients. In the Okanagan, phosphorus is the main limiting nutrient while dissolved inorganic nitrogen also limits productivity during the summer. Their concentrations are directly linked to the amount of algae that the lake produces (Nordin, 2005).

Nitrogen

Total nitrogen (TN) averaged 0.225 ± 0.031 mg/L as N in the epilimnion of Okanagan Lake during 2023. The objective for Okanagan Lake was set as a spring value (March sample date[1]) of 0.230 mg/L for the main basins and 0.250 mg/L for the Armstrong Arm. The objective was exceeded at Summerland, Kelowna, and Okanagan Centre during 2023 as it has in most years (Table 7). TN, previously identified as increasing, appears to have stabilized in the main basins while TN showed a declining trend in the Armstrong Arm from 2017-2023 (Mann-Kendall, p≤0.02; Table 7). Average TN values were comparable to those found in the literature for Okanagan Lake (0.17-0.23 mg/L as N; Andrusak et al.,2000).

[1] The Armstrong Arm sample is typically collected in early April because of ice-cover in that part of the lake

Table 7: Total nitrogen in mg/L as N concentration at Okanagan Lake sampling sites, 2023

Summerland	<10m	0.230	-		0.025	0.26	0.181
	>20m		-		0.019	0.268	0.212
Kelowna	<10m	0.230	-		0.026	0.261	0.192
	>20m		-		0.016	0.26	0.219
Ok Centre	<10m	0.230	-		0.028	0.254	0.185
	>20m		-		0.022	0.278	0.204
Armstrong	<10m	0.250	↓*		0.041	0.31	0.193
Arm	>20m		↓*		0.039	0.353	0.245

Note: Red shaded cells indicate that the Spring value exceeded the objective while green indicates that the value met the objective. Statistical significance of general trends derived from all data for a site may disappear when depths are split apart due to smaller sample size | * = Trend from 2017-2023



Figure 10: Annual average total nitrogen in Okanagan Lake, 2011-2023

Hypolimnetic nitrate increased at all sites from 2011-2023 (Mann-Kendall, $p<0.001$; Figure 11), but was stable at all sites from 2019-2023, despite the longer-term trend. Analysis of the entire Okanagan Lake water chemistry database indicates that this trend has been ongoing for decades (1973-2023 dataset; Mann-Kendall, $p<0.001$; Figure 11). This suggests a connection to human activities in the region because the trend has continued through several wet-dry climate cycles. There is also recent research noting that changes in nitrate concentration are a marker of climate change (Mas-Pla & Menció, 2019; Stuart et al., 2011). Layered on top of this trend are short-term variations depending on a given year's weather.



Figure 11: Annual average nitrite (NO_2) + nitrate (NO_3) in mg/L as N in the deep water of Okanagan Lake, 2011-2023

Nitrate is rapidly consumed by algae in the epilimnion each spring and thermal stratification prevents replenishment from the deeper water during the summer (Figure 11). Nitrate increased dramatically each summer in the hypolimnion of the Armstrong Arm because of chemistry associated with the low-DO conditions (Figure 12). For example, nitrate increased from <0.0032 mg/L as N in the epilimnion to 0.179 mg/L as N in the hypolimnion by Sept 2023.



Figure 12: Nitrate + nitrite in Okanagan Lake at Armstrong Arm by month illustrating seasonal accumulation of nitrate in low oxygen hypolimnion, 2011-2023

Phosphorus

Total phosphorus (TP) measures all forms of phosphorus including those that may not be bioavailable. Total phosphorus averaged 0.008 ± 0.006 mg/L as P across Okanagan Lake during 2023 (Table 8). The TP objective for Okanagan Lake applies to the maximum phosphorus concentration at the spring overturn (Nordin, 2005; taken as March[2]). The objectives range from 0.007 mg/L in the south basin to 0.010 mg/L in the Armstrong Arm.

The TP objective was exceeded in the epilimnion and hypolimnion of Armstrong Arm in 2023, as it was in most years from 2011-2023 (Table 8). Increasing trends in TP occurred at all sites from 2011-2023 (Mann-Kendall, p≤0.04; Table 8, Figure 13). This trend was driven, in part, by large increases in TP during wet years such as 2012-2013 and 2017-2018, 2020, and 2022. The trend was also more pronounced in the Armstrong Arm and north basin compared to the central or south basins. TP includes phosphorus associated with suspended sediment carried into the lake and it increases in Okanagan Lake during wet years and decreases during dry years (Figure 13).

Table 8: Total phosphorus (mg/L as P) at Okanagan Lake sampling sites during 2023

Site	Depth	Objective	Trend	Avg	SD	Max	Min
Summerland	<10m	0.007	↑	0.005	0.000	0.005	0.004
	>20m		↑	0.005	0.001	0.007	0.004
Kelowna	<10m	0.008	-	0.006	0.001	0.009	0.005
	>20m		↑	0.005	0.001	0.006	0.005
Ok Centre	<10m	0.008	↑	0.007	0.002	0.010	0.005
	>20m		↑	0.006	0.001	0.008	0.004
Armstrong	<10m	0.010	↑	0.012	0.005	0.020	0.007
Arm	>20m		↑	0.019	0.009	0.036	0.013

Note: Red shaded cells indicate that spring overturn value exceeded the objective while green shaded cells met the objective during 2022. Trends are based upon 2011-2023 data only

[2] The Armstrong Arm spring sample is typically collected in early April because of ice-cover in March



Figure 13: Annual average total phosphorus in Okanagan Lake at the three major basin sampling sites by year from 2011-2023

Notes: Grey boxes indicate wet years, decreasing trend from 1973-2005 and increasing trend from 2005-2023

TP experienced minor seasonal variation with a slight increase during freshet in some years at Summerland, Kelowna, and Okanagan Centre while there was dramatic variation in the Armstrong Arm over the course of each growing season. TP increased in the hypolimnion during the summer, possibly from phosphorus released from the sediment under low-oxygen conditions while algae productivity reduced surface concentrations over the growing season (Figure 14).



Figure 14: Total phosphorus in the Armstrong Arm, 2011-2023
Note: small reduction in eplimnetic TP over the growing season but it does not drop below detection as nitrate does

Dissolved phosphorus (TDP) measures the more bioavailable forms of phosphorus and is a good indicator of potential impacts to biota. TDP in the epilimnion and the hypolimnion of the Armstrong Arm increased (Mann-Kendall for 2011-2023 in the hypolimnion, $p \leq 0.02$). TDP was stable at Kelowna and Okanagan Centre but decreased in the epilimnion at Summerland from 2011-2023 (Mann-Kendall, $p \leq 0.02$). Despite the stable long-term trend, TDP was noticeably higher in the Okanagan Centre epilimnion samples immediately following the White Rock Lake Fire (Sep 2021) followed by a short-term decline through 2023 (Figure 15). Ortho-phosphate measures only the soluble reactive phosphorus fraction of the TDP and there were no significant trends in ortho-phosphate data at any of the sites from 2011-2023 with 93% of samples from the major basin sample sites having undetectable concentrations during 2023. Anoxic conditions in the Armstrong Arm increase hypolimnetic orthophosphate each summer.



Figure 15: Annual average dissolved phosphorus in Okanagan Lake illustrating declining long-term trend at Okanagan Centre, Kelowna, and Summerland from 2011-2023

N:P Ratio

The ratio of nitrogen to phosphorus is a key factor in determining which types of phytoplankton will proliferate. Many species of cyanobacteria can fix atmospheric nitrogen and are therefore limited primarily by available phosphorus. These algae are more likely to bloom when phosphorus is abundant relative to nitrogen. The Okanagan Lake objective for the spring ratio of total nitrogen to total phosphorus is >25:1 in March samples. The objective was met at Summerland, Kelowna, and Okanagan Centre during 2023 while the Armstrong Arm had higher phosphorus concentrations than the rest of Okanagan Lake and did not meet the objective in 2023 (Figure 13, Table 9). The TN:TP ratio decreased at all sites from 2011-2023 (Mann-Kendall, $p \leq 0.02$) (Figure 13). The declining TN:TP trend is related to corresponding increasing trends in TP in Okanagan Lake (Table 8).

Table 9: Ratio of average TN to average TP during spring at Okanagan Lake sampling locations, 2011-2023

Summerland	<10m	0.216	0.0045		>25:1	↓
	>20m	0.237	0.0051		>25:1	↓
Kelowna	<10m	0.220	0.0063		>25:1	-
	>20m	0.237	0.0052		>25:1	↓
Ok Centre	<10m	0.220	0.0067		>25:1	↓
	>20m	0.239	0.0056		>25:1	↓
Armstrong Arm	<10m	0.244	0.0118		>25:1	↓
	>20m	0.280	0.0194		>25:1	↓

Note: red shaded cells indicate that the value did not meet the objective while green shaded cells met the objective during 2022 | TN and TP columns display annual averages while ratio column is specific to the spring sample date



Figure 16: Nitrogen to phosphorus ratio at Okanagan Lake sampling sites 2011-2023

2.3 Biology

2.3.1 Phytoplankton

The Armstrong Arm of Okanagan Lake is shallower and has the potential to produce more phytoplankton and zooplankton than the deep basins of Okanagan Lake regardless of human activity. Phytoplankton and zooplankton samples were taken from all four sites were analyzed during 2022. Biomass analysis and taxonomic identification were performed on the taxonomy samples while chlorophyll-a concentrations were monitored as a productivity metric for phytoplankton abundance.

Chlorophyll-a

Chlorophyll-a (chl-a) is a photosynthetic pigment found in most freshwater algae species. As expected, chl-a followed an inverse trend to Secchi depth (Figure 6, Figure 17). Chl-a was lowest in the late winter and peaked in April-May during the increased spring algal growth before decreasing through the summer. During 2023, chl-a concentrations met the objectives at all sites (Table 10). Spring chl-a concentrations were high with a maximum of 5.2 µg/L in the Armstrong Arm (Table 10). Average chl-a concentrations in the Armstrong Arm have declined significantly since 2017 and averaged the lowest since 2014 (Mann-Kendall, p=0.01). Chl-a followed a similar if less pronounced pattern at Okanagan Centre (Figure 17), an encouraging result despite the watershed damage from the White Rock Lake wildfire (Figure 17).

In most years, including 2023, there was a north to south decreasing trend in the chlorophyll-a data with the Armstrong Arm having the highest and Summerland having lowest average concentrations (Table 10).

Table 10: Chlorophyll-a in µg/L at Okanagan Lake sampling sites, 2023

Summerland	4	-	1.74	0.91	2.94	0.81
Kelowna	4.5	↑	1.97	0.84	3.03	1.10
Ok Centre	4.5	-*	2.16	0.42	2.59	1.48
Armstrong Arm	5	↓*	3.08	1.12	5.16	1.78

Note: Green shading indicates met objective during 2022 | * = 2017 to 2023



Figure 17: Annual chlorophyll-a concentration at the four Okanagan Lake sampling sites, 2011-2023

Phytoplankton Biovolume

Phytoplankton biovolume samples were collected as one litre composites from 1-10 m and the biovolumes were determined taxonomically. From 2011-2014, biomass was determined using

ash-free dry mass (AFDM). It is not possible to directly compare the results from the two methodologies and only the 2015-2023 results are considered here.

The objective is that the growing season average should be <0.75 µL/L (Table 11). Samples from all sites failed to meet the objective during 2023 because of above average phytoplankton production (Table 11, Figure 18, Figure 19).

Phytoplankton biovolume increased significantly from 2015-2023 at Summerland and at Kelowna (MK tests, p=0.001) - a trend that matches chlorophyll-a (Figure 18). Productivity was lower during 2022 than 2021 but increased again during 2023. A one-year lag has been observed between wet years and elevated productivity in Okanagan Lake and this effect helps explain why 2019 and 2021 production was very high despite the much smaller freshets (Figure 18). This is likely related to the higher productivity in 2023 because of the large 2022 freshet. Production in 2024 is therefore expected to be remain elevated after a smaller the moderate freshet combined with extensive watershed damage from wildfires.

Table 11: Phytoplankton biovolume in µL/L at Okanagan Lake sampling sites, 2023

Summerland	<0.75	↑	0.790	0.710	2.168	0.224
Kelowna	<0.75	↑	1.135	1.263	3.673	0.199
Ok Centre	<0.75	-	1.004	0.820	2.281	0.142
Armstrong Arm	<0.75	-	0.814	0.256	1.316	0.553

Notes: Green shading = met objective while red shading = did not meet objective.



Figure 18: Phytoplankton Biovolume at Summerland and Kelowna, 2015-2023

Phytoplankton Taxonomy

Algae samples were identified to the species level and then grouped into broad algae types for analysis in this report. Diatoms tend to proliferate in the spring and their numbers decrease through the summer. Cyanobacteria were always numerous throughout the growing season in Okanagan Lake, but typically peaked in the late summer (Figure 19, Table 12). Algae counts were highest in the Armstrong Arm throughout the year but all sites experienced high densities of

cyanobacteria during 2023 (



Figure 20). Very high cyanobacteria densities in the Armstrong Arm may be a marker for nutrients delivered to Okanagan Lake from the areas burned in the White Rock Lake wildfire.

Table 12: Average phytoplankton counts by major algae groups in cells/mL, 2023

	2023 Averages			
Algae Type	Summerland	Kelowna	Okanagan Centre	Armstrong Arm
Diatoms	800	838	624	420
Greens	129	102	261	180
Yellow-Brown	212	266	282	299
Cyanobacteria	5622	7086	10422	11954
Dinoflagellates	0	5	0	0
Other.Flagellates	127	175	177	165
Total Algae	6913	8472	11797	13032

Figure 19: Taxonomic breakdown of algae by major types during 2023



Figure 20: Total algae, cyanobacteria, and diatom counts in Okanagan Lake, 2011-2023

The Okanagan Lake objective for phytoplankton taxonomy states that no more than 5% of total cell counts should be heterocystous cyanobacteria in a given sample. These and other cyanobacteria can produce toxins that are harmful to human health when they are present in high concentrations. The heterocystous cyanobacteria objective was exceeded during most years including 2023 (82% of samples from 2023 exceeded this objective; Table 13). While problematic, the cyanobacteria densities observed during 2023 were not high enough to cause acute health concerns at any of the sites. Significant year-over-year increasing trends were detected in the heterocystous cyanobacteria counts from 2011-2023 at all sites (Mann-Kendall, $p \leq 0.02$).

Table 13: Percent of total algae counts that were heterocystous cyanobacteria from 2023

Site	Objective	Trend	# Exceeding	Average	StdDev	Max	Min
Summerland	<5%	↑	5/7	12.5%	12%	38%	5%
Kelowna	<5%	↑	6/7	13.6%	9%	26%	3%
Ok Centre	<5%	↑	5/7	12.5%	8%	26%	1%
Armstrong Arm	<5%	↑	7/7	44.2%	18%	66%	22%

Note: Yellow shading indicates that the site did not meet the objective in most but not all samples



Figure 21: Percent of total algae counts that were heterocystous cyanobacteria, 2011-2023

2.3.2 Zooplankton

Biomass

Zooplankton biomass samples were obtained using a 150 µm net lowered to 45 m and raised vertically at a rate of approximately 0.5 m/second. The 150 µm net mesh size lets most phytoplankton pass through, while collecting most zooplankton. Samples were identified taxonomically and the biomass was calculated from the abundance.

The Okanagan Lake objective is a growing season average of >50 µg/L (Nordin, 2005). This objective was met at none of the sites during 2023 with all sites also below the 2015-2023 average (Table 14, Figure 22). While biomass during 2021 was unusually high, skewing trend results, there appeared to be a declining trend in zooplankton biomass from 2015-2023. The cause of the elevated 2021 zooplankton density remains uncertain and was not repeated during 2022-2023.

Table 14: Zooplankton biomass in µg/L at Okanagan Lake sampling sites, 2023

Site	Objective	Trend	Average	StdDev	Max	Min
Summerland	>50 µ/L	-	6.1	2.6	10.7	3.0
Kelowna		-	10.4	5.7	20.7	3.3
Okanagan Centre		-	9.5	2.9	12.5	4.3
Armstrong Arm		-	11.5	1.4	14.1	9.6

Note: Data includes only Apr-Aug results, Mar and Sep results not released by lab at time of writing.



Figure 22: Zooplankton Biomass at the Okanagan Lake sampling locations by year, 2015-2023

Note: top and bottom panes are the same graph but the y-axis is changed to highlight variation in the data

Zooplankton Taxonomy

Zooplankton samples were taxonomically identified to the species level and then grouped for analysis in this report. Copepods were the most numerous during every year of the study and averaged between 69% at Okanagan Centre and 92% at Kelowna 2023 (Table 15).

The objective for Okanagan Lake is a minimum of 5% of the sample counts be cladocerans. Most samples at Summerland met this objective and approximately half of the samples met this objective at Okanagan Centre,. However, Armstrong Arm and Kelowna had poorer objective achievement during 2023.

The average zooplankton abundances were consistent with values found in the literature (Andrusak et al., 2000; Rae and Andrusak, 2006; Andrusak et al., 2006). There was a decreasing trend in total zooplankton abundance in the Armstrong Arm from 2018-2023 (Table 15).

Table 15: Growing Season average percent cladocerans zooplankton, 2023

Site	Objective	# of samples exceeding	Trend	Average	StdDev	Max	Min
Summerland	>5% / sample	5/7	-	7.9%	3.8%	14.7%	3.1%
Kelowna		0/7	-	0.2%	0.3%	0.7%	0.0%
Okanagan Centre		3/7	-	5.3%	2.8%	10.9%	2.7%
Armstrong Arm		1/5	-	2.0%	2.6%	6.9%	0.3%

Notes: Yellow shading = met objective in approximately half of samples, red shading = rarely met objective; Data includes only Apr-Aug results, Mar and Sep results not released by lab at time of writing.

3.0 Conclusions

This report summarizes the 2023 findings within the context of the 2011-2023 dataset. This report also extracts trends from the data accumulated by the Okanagan Lake Collaborative Sampling program to date (2011-2023) and compares those to the long-term historical database (1973-2023). The effects of Climate Change are already being felt in the Okanagan in recent years with repeated swings between large freshets and intensely dry summers; 2023 was the driest year on record for the Okanagan. While the results to date indicate that Okanagan Lake exhibits evidence of human activities, the Armstrong Arm is most impacted by continued human activities and watershed degradation, a situation likely to get worse because of the White Rock Lake wildfire; major flooding occurred on the Whiteman Creek drainage during freshet 2023. This site had the most exceedances and the most problematic trends, that is, trends moving parameters towards greater exceedances and poorer water quality.

Dissolved Oxygen Each year the temperature of Okanagan Lake increases seasonally in the surface waters until the lake becomes thermally stratified, usually in May. This physical dynamic isolates the deep water from the atmosphere and leads to oxygen depletion below the thermocline in Armstrong Arm. The Armstrong Arm therefore failed to meet the dissolved oxygen objective in 2023, as it has in each year of this study.

Nutrients
Silica analysis of water samples revealed a long period of stable conditions over the past 20 years.

Total nitrogen had been identified as increasing during this study but appears to have stabilized in recent years except for the Armstrong Arm where a declining trend was observed from 2017-2023. Total nitrogen exceeded the water quality objectives at Summerland, Kelowna, and Okanagan Centre during 2023. Nitrate increased significantly in the Armstrong Arm and in the hypolimnion at all sites from 2011-2023, although as with TN, appears to have stabilized over the past few years, an encouraging shift. This is part of a decades long increasing trend in hypolimnetic nitrate in Okanagan Lake that has continued through multiple wet-dry climate cycles and is likely caused by increasing human impacts within the Okanagan region.

Phosphorus concentrations were highest in the Armstrong Arm where they exceeded the objective during 2023. There were increasing trends in TP from 2011-2023 at all four sites driven in part by increases during wet years such as 2017-2018. The Armstrong Arm is more heavily impacted by human activities and has numerous phosphorus sources such as nutrient enrichment of the Deep Creek watershed from over 100 years of agriculture, and the rise may become exacerbated by nutrients shed from the areas burned during the 2021 White Rock Lake fire. Dissolved phosphorus (TDP) and ortho-P represent the more bioavailable forms of phosphorus and were stable or declining at Summerland, Kelowna, Okanagan Centre while TDP increased at the Armstrong Arm. TDP was elevated at Okanagan Centre since the 2021 White Rock Lake wildfire. Samples from the Armstrong Arm exceeded the nitrogen-phosphorus ratio objective in 2022, with a decreasing trend in that ratio from 2011-2023 at all sites.

Phytoplankton Productivity Chlorophyll-a (chl-a) concentrations increased each spring during the annual spring high algal growth period and then decreased over the summer and into the fall. Peak chl-a was moderate at all sites during 2023. Previous research by ENV has identified a one-year lag between major nutrient inputs and increases in phytoplankton productivity so it was expected that 2023 productivity would be higher after the large 2022 freshet. As expected, the phytoplankton biovolume was high and did not met the objective at any site during 2023.

The taxonomic data indicated that cyanobacteria numerically dominated the phytoplankton samples in 2023, as in every year studied. Samples from all sites exceeded the <5% heterocystous cyanobacteria objective in most samples during 2023 and Armstrong Arm exceeded the objective in all samples.

Table 16 to Table 18 summarize the findings of this report for 2011-2023 by pairing trends to objective exceedances. Special focus should be paid to parameters that did not meet the objective and for which the data trended in the adverse direction over the course of the sampling program.

The following areas of concern have been identified that may require further investigation on the part of the Ministry:

- Chronically low Secchi depth in the Armstrong Arm
- Increasing nitrate in hypolimnion of Okanagan Lake since 1970s (although stable during past 5 years)
- Increasing total phosphorus at all sites since early 2000s
- Decreasing N:P ratio in the Armstrong Arm
- High densities of potentially toxic cyanobacteria in Armstrong Arm during 2018-2023
- Phosphorus loading to the Armstrong Arm and north basin of Okanagan Lake from the White Rock Lake wildfire (2021) and the McDougall Creek wildfire (2023).

Armstrong Arm frequently exceeds most objectives and is the site most at risk of water quality degradation including harmful algae blooms, poor drinking water quality, anoxic conditions, and further eutrophication. There is also high likelihood of further degradation because of the White Rock Lake wildfire. It must be acknowledged that Armstrong Arm is shallower and therefore would be more productive than the deep basins of Okanagan Lake regardless of human activity. However, human activities in the watershed have impacted this northern-most basin of the lake.

The period of 2016-2023 was marked by multiple extreme weather events that have left a distinct mark on the water quality record of Okanagan Lake. Climate Change and is expected to increase the frequency and intensity of extreme weather events in the future. Climate Change also compounds the loss of resilience in Okanagan watersheds leading to greater water quality changes from those extreme weather events.

Table 16: Okanagan Lake Water Quality Objectives

Objectives (Nordin, 2005)	**Summerland**	**Kelowna**	**Ok Centre**	**Armstrong Arm**
Secchi Depth (growing season average)	7m	6m	6m	5m
Dissolved Oxygen (minimum in bottom waters)	-	-	-	>5 mg/L
TP (mg/L as P) (maximum at spring overturn)	0.007	0.008	0.008	0.01
Chlorophyll-a (µg/L) (maximum seasonal average)	<4.5	<4.5	<4	<5
TN (mg/L as N) (maximum at spring overturn)	0.230	0.230	0.230	0.250
N:P Ratio (spring weighted ratio)	>25:1	>25:1	>25:1	>25:1
Algae Taxonomy (% heterocystous cyanobacteria)	<5%	<5%	<5%	<5%
Algae Biomass (µL/L) (growing season average)	<0.75	<0.75	<0.75	<0.75
Zooplankton Biomass (µg/L) (growing season average)	>50	>50	>50	>50
Zooplankton Taxonomy (% cladocerans)	>5%	>5%	>5%	>5%

Table 17: Attainment of Okanagan Lake water quality objectives compared to growing season averages during 2023

Objective	Summerland	Kelowna	Ok Centre	Armstrong Arm
Secchi Depth	6.0	5.3	5.8	2.8
Dissolved Oxygen	7.88	8.23	8.30	2.13
TP (mg/L) 0:10m:	0.005	0.006	0.007	0.012
20-45m:	0.005	0.005	0.006	0.019
Chlorophyll-a (µg/L)	1.74	1.97	2.16	3.08
TN (mg/L) 0-10m:	0.216	0.220	0.22	0.244
20-45m:	0.237	0.237	0.239	0.280
N:P Ratio 0-10m:	59:1	49:1	33:1	20:1
20-45m:	57:1	47:1	41:1	18:1
Algae Taxonomy (% heterocystous cyanobacteria)	12.5%	13.6%	12.5%	44.2%
Algae Biovolume (µL/L)	0.790	1.135	1.004	0.814
Zooplankton Biomass (µg/L)	6.1	10.4	9.5	11.5
Zooplankton Taxonomy (% cladocerans)	7.9	0.2	5.3	2

Legend:

Achieved objective	Achieve objective in some but not all samples	Did not achieve objective

Table 18: Summary of trends (2011-2023) and the water quality objectives for Okanagan Lake collaborative sampling program during 2023

Objective	Summerland	Kelowna	Ok Centre	Armstrong Arm
Secchi Depth	-	-	-	-
Dissolved Oxygen	-	-	-	-
TP (mg/L) 0:10m:	↑	↑	↑	↑
Chlorophyll-a (µg/L)	-	↑	-	↓
TN (mg/L) 0-10m:	-	-	-	↓
N:P Ratio 0-10m:	↓	↓	↓	↓
Algae Taxonomy (% heterocystous cyanobacteria)	↑	↑	↑	↑
Algae Biovolume (µL/L)	↑	↑	-	-
Zooplankton Biomass (µg/L)	-	-	-	-
Zooplankton Taxonomy (% cladocerans)	-	-	-	-

Legend:

Achieved objective	Achieve objective in some but not all samples	Did not achieve objective

↑ = Increasing Trend ↓ = Decreasing Trend - = No Trend

4.0 Recommendations

The following recommendations are made for the program moving forward:

- Continue the monitoring program, unchanged in 2024
- Complete another summary report at the end of the next three-year cycle (next in 2024)

5.0 References

Andrusak, H., Matthews, S., Wilson, A., Andrusak, G., Webster, J., Sebastian, D., Scholten, G., Woodruff, P., Rae, R., Vidmanic, L., Stockner, J., & Branch, E. (2006). *Okanagan Lake Action Plan Year 10 (2005) Report - Introduction* (Vol. 10, Issue 2005).

Andrusak, H., Sebastian, D., Mcgregor, I., Matthews, S., Smith, D., Ashley, K., Pollard, S., Scholten, G., Stockner, J., Ward, P., Kirk, R., Lasenby, D., Webster, J., Whall, J., Wilson, G., & Yassien, H. (2000). *Okanagan Lake Action Plan Year 4 (1999) Report*. *4*(1999).

Bergman, B., Gallon, J. R., Rai, A. N., & Stal, L. J. (1997). N2 fixation by non-heterocystous cyanobacteria. In *FEMS Microbiology Reviews* (Vol. 19, Issue 3, pp. 139–185). https://doi.org/10.1016/S0168-6445(96)00028-9

Clemens, W. A., Rawson, D. S., & McHugh, J. L. (1939). *Biological Survey of Okanagan Lake B.C.* http://a100.gov.bc.ca/appsdata/acat/documents/r1954/oklkstudy_1362690263031_964b8eb84253194546e8eed7b6cea9606f70d159938f36e216459469b9d7bcce.pdf

Felip, M., & Catalan, J. (2000). The relationship between phytoplankton biovolume and chlorophyll in a deep oligotrophic lake: decoupling in their spatial and temporal maxima. *Journal of Plankton Research*, *22*(1), 91–106. https://doi.org/10.1093/plankt/22.1.91

Larratt, H. (2009). *Deep Okanagan Lake Biology Report*.

Mas-Pla, J., & Menció, A. (2019). Groundwater nitrate pollution and climate change: learnings from a water balance-based analysis of several aquifers in a western Mediterranean region (Catalonia). *Environmental Science and Pollution Research*, *26*(3), 2184–2202. https://doi.org/10.1007/s11356-018-1859-8

Nordin, R. (1985). *Water Quality Criteria for Nutrients and Algae. Overview Report*.

Nordin, R. N. (2005). *Water Quality Objectives for Okanagan Lake* (Issue January).

Okanagan Basin Water Board. (2021). *Okanagan Drought Bulletin – August 14, 2021 – Okanagan Basin Water Board*. https://www.obwb.ca/okanagan-drought-bulletin-august-13-2021/

Rae, R., & Andrusak, H. (2006). *Ten- Ten - Year summary of the Okanagan Lake Action Plan* (Issue January).

Schelske, C. L. (1988). Historic Trends in Lake Michigan Silica Concentrations. *Internationale Revue Der Gesamten Hydrobiologie Und Hydrographie*, *73*(5), 559–591. https://doi.org/10.1002/iroh.19880730506

Sokal, M. (2013). *Okanagan Lake Collaborative Monitoring Agreement 2013 Summary Report*.

Stuart, M. E., Gooddy, D. C., Bloomfield, J. P., & Williams, A. T. (2011). A review of the impact of climate change on future nitrate concentrations in groundwater of the UK. *Science of the Total Environment*, *409*(15), 2859–2873. https://doi.org/10.1016/j.scitotenv.2011.04.016

The Weather Network - B.C. sets new Canadian record for hottest temperature ever recorded. (n.d.). Retrieved March 9, 2022, from https://www.theweathernetwork.com/ca/news/article/canadas-hottest-june-temperature-recorded-amid-western-canada-heat

Water Office. (2017). *Real-Time Hydrometric Data Graph for Okanagan Lake At Kelowna (08nm083) [Bc]*. https://wateroffice.ec.gc.ca/report/real_time_e.html?mode=Graph&type=&stn=08NM083&startDate=2016-06-21&endDate=2017-12-21&prm1=46&y1Max=&y1Min=&prm2=-1&y2Max=&y2Min=

Wehr, J. (2002). *Freshwater algae of North America: ecology and classification*. http://books.google.ca/books?hl=en&lr=&id=IikPwCt1ioEC&oi=fnd&pg=PP2&dq=Freshwater+Algae+of+North+America:+Ecology+and+Classification+&ots=hL32vxVcVg&sig=wMq94pq1DoQb6FBYBpZWg8_QayU

6.0 Appendices

6.1 Appendix 1: 2011-2023 Sampling Data

All data used in this report can be found in the data transfer file
MoE-Synth-DB.xlsx

6.2 Appendix 2: Statistics and Graphing Overview

Statistical analyses were performed on data to support interpretations made throughout this report. The use of the word 'significantly' within this report is understood to signify that the claim being made has stood up under statistical analysis. Unless otherwise stated, all statistical analyses were performed to a confidence of greater than or equal to 95% ($p \leq 0.05$). The ± symbol indicates plus or minus the standard deviation throughout this report.

Trends were determined through Mann-Kendall linear regression. Mann-Kendall is a non-parametric test for linearity in data. The test produces a Tau-value and a p-value. The Tau value gives the direction of the data and the p-value indicates whether the trend is statistically significant.

Throughout this report the monthly sampling data was grouped seasonally for additional analyses. March, April, and May data were combined as "Spring"; June, July, and August as "Summer"; and September as "Fall".

Correlations were performed using the Pearson's Correlation method and all R values reported at Pearson's Correlation Coefficients.





Figure i: Example scatterplot and boxplot

Includes all data for a parameter sorted by depth, LOESS polynomial trendlines and the standard errors of those trendlines are also included. Example boxplot is labeled with key information. Whiskers represent the distance to the highest or lowest point within 1.5 * IQR where IQR represents the range between the upper and lower quartiles.

How to Read Temperature/DO Profile Plot

Temperature and dissolved oxygen profiles were routinely collected as part of this study. They are displayed in several locations throughout this report. An example of a temperature graph and a dissolved oxygen graph, descriptions of their key features and how to read them are presented here.



Isoclines = areas of equivalent temperature. That is, the space between two lines is approximately the same temperature. Large spaces between lines indicate homogenous water column while many lines close together indicates stratified conditions



Tight concentration of lines = rapid change in temperature over short depth (i.e. thermocline)

Scale: Lighter shading = warmer water

Gray area indicates lake bottom. This appears on the plot when profiles were taken at sites with different depths on different dates. For example, on Jul 20, the profile was at a site 24 m deep but on Oct 26, the profile was done only at a site 19 m deep. This can occur when weather conditions move the sampling boat into a slightly different location on the lake.





Scale: Lighter shading = Low DO (anoxic conditions)
Darker shading = High DO (algae blooms)

Light area indicates oxygen depletion along sediments

Each vertical column in graph represents conditions within a column of the lake on given date. For example, on Apr 25, DO was very high through entire water column but on Sept 28, there was significant oxygen depletion in the deep water

----------End of Report----------