

ANNUAL RYEGRASS

LOLIUM MULTIFLORUM- COOL SEASON ANNUAL/BIENNIAL GRASS



PRODUCTION GOALS



Not Effective



Very Effective

Quick Growth	
Lasting Residue	
Soil Builder	
Nitrogen Fixation	n/a
Nitrogen Scavenging	
Erosion Reduction	
Compaction Reduction	
Biofumigation Potential	
Weed Suppression	
Forage Harvest Value	
Grain Harvest Value	

Annual ryegrass has two subspecies grown in BC: Westerwold and Italian ryegrass. It is a rapidly growing, highly tillered cool season bunchgrass with an upright growth habit and a medium depth fibrous root. Annual ryegrass is commonly grown as a forage crop or for rapid ground cover. Italian ryegrass is a possible biannual that requires exposure to cold for flowering.

TOLERANCES

Flood	
Heat	
Drought	
Shade	
Low Fertility	
Salinity	
Optimal pH	5.5 - 7.0

SOIL DRAINAGE CLASS

Very Well	
Well	
Moderately Well	
Somewhat Poor	
Poorly	
Very Poorly	

AREA & ADAPTABILITY

Annual ryegrass is suitable for all regions of British Columbia. Italian ryegrass can overwinter in zones with milder winter and/or adequate snowcover.

Winter Hardiness Zone - 4-9

Rate Drilled	Rate Broadcast	Depth	Frost Seeding	Minimum Germination Temperature	Seeds #
10-35 lbs/ac (11-39 kg/ha)	12-42 lbs/ac (13-47 kg/ha)	0-0.5 in (0-1.25 cm)	No	4°C (40°F)	227,000 /lb (102,965 /kg)

Management Considerations

Westerwold annual ryegrass behaves as an annual and sets seed in the first season. It has more upright growth than Italian ryegrass and can volunteer if allowed to set seed. It is commonly used as a nurse crop for forage stands, interseeded within a cereal forage for a fall relay crop, and as a quick ground cover.

Inter-seeding Potential	
Volunteer Establishment	
Nitrogen Concentration	0.8-3.6%

Italian ryegrass is winterkilled in many regions of Canada and thus commonly confused as an annual. However, it is a biennial that will overwinter in southern BC and produce seed the following spring if allowed to mature. It has higher forage quality than Westerwold and can also volunteer if allowed to set seed. It is commonly used for forage for grazing or silage and interseeded with other annuals for relay or blend use. Italian ryegrass is a heavy user of nutrients and water, and an aggressive cutting schedule can produce large forage yields of high quality feed.

Dry Matter Yield

1000-9000 lbs/acre
1120-10,080 kg/ha

Both types of annual ryegrass have seed available as diploid and tetraploid (2 or 4 sets of chromosomes). Generally diploid tend to have a more vigorous establishment and smaller seed size allowing for reduced seeding rates, however tetraploids generally have higher forage quality.

Termination

Annual ryegrass can be terminated by tillage or chemical means. Mowing is not effective before seed heads are set as regrowth will occur, and multiple passes may be necessary.

References

- Cloverdale Soil Conservation Group. 1994. Final Report: Part 2 Reports, Newsletters and Bulletins.
- Ismail, I. 1994. Establishment and Evaluation of Cover Crops Underseeded in Sweet Corn in Delta, British Columbia. University of British Columbia.
- Sustainable Agriculture Research and Education (SARE). 2012. Managing Cover Crops Profitably: 3rd Ed. National Institute of Food and Agriculture, USDA, University of Maryland & University of Vermont.
- Midwest Cover Crop Council.
- Nafuma, L. 1998. Short-term effects of graminaceous cover crops on autumn soil mineral nitrogen cycling in western lower Fraser Valley soils. University of British Columbia.
- Odhiambo, J., A. Bomke. 2001. Grass and Legume Cover Crop Effects on Dry Matter and Nitrogen Accumulation. Soil and Crop Management 93:2, pp. 299-307.
- Odhiambo, J., Temple, W.D., A. Bomke. 2012. Managing Cover Crops for Conservation Purposes in the Fraser River Delta, British Columbia. In: Crop Management - Cases and Tools for Higher Yield and Sustainability.
- Sullivan, D.M., Andrews, N. and L.J. Brewer. 2020. Estimate Plant-Available Nitrogen Release from Cover Crops. Pacific Northwest Extension Publishing 636.

Disclaimer

The information contained in this document is true and accurate to the best of our knowledge without guarantee or warranty of its correctness or completeness. The content is intended to be a general guideline, but the performance of the cover crop(s) may differ from what is described in the document depending on environment and farm operation and may vary between years. The Government of British Columbia and its directors, agents, employees, or contractors will not be liable for any claims, damages, or losses of any kind whatsoever arising out of the use of, or reliance upon, this information.

FACTSHEET DEVELOPED BY: