AGRICULTURE WATER DEMAND MODEL

Report for the Bonaparte Watershed

October 2013

Canada

AGRICULTURE WATER DEMAND MODEL

Report for the Bonaparte Watershed

Authors

Ted van der Gulik, P.Eng.

Senior Engineer B.C. Ministry of Agriculture Sustainable Agriculture Management Branch Abbotsford, BC Denise Neilsen, Ph.D.

Research Scientist Agriculture and Agri-Food Canada Pacific Agri-Food Research Centre Summerland, BC

Ron Fretwell

Program Developer RHF Systems Ltd. Kelowna, BC

Stephanie Tam, P.Eng.

Water Management Engineer B.C. Ministry of Agriculture Sustainable Agriculture Management Branch Abbotsford, BC

October 2013

DISCLAIMER

The data that is presented in this report provides the best estimates for agriculture water demand that can be generated at this time. While every effort has been made to ensure the accuracy and completeness of the information, the information should not be considered as final. The Government of Canada, the BC Ministry of Agriculture, and the BC Agriculture Council or its directors, agents, employees, or contractors will not be liable for any claims, damages, or losses of any kind whatsoever arising out of the use of, or reliance upon, this information.

Table of Contents

ACKNOWLEDGEMENTS	5
BACKGROUND	6
METHODOLOGY	7
Cadastre	8
Land Use Survey	8
Soil Information	10
Climate Information	11
MODEL CALCULATIONS	12
Crop	12
Irrigation	12
Soil	12
Climate	13
Agricultural Water Demand Equation	13
LIVESTOCK WATER USE	18

DEFINITION AND CALCULATION OF INDIVIDUAL TERMS USED IN THE IRRIGATION WATER

DEMAND EQUATION		19
Growing Season Boun	daries	19
Evapotranspiration (ET)	21
Availability Coefficient	(AC)	21
Rooting Depth (RD)		21
Stress Factor (stressFa	actor)	22
Available Water Storag	ge Capacity (AWSC)	22
Maximum Soil Water D	Deficit (MSWD)	22
Deep Percolation Factor	or (soilPercFactor)	
Maximum Evaporation	Factor (maxEvaporation)	23
Irrigation Efficiency (I _e)		23
Soil Water Factor (swF	actor)	23
Early Season Evapora	tion Factor (earlyEvaporationFactor)	23
Crop Coefficient (K _c)		23
Growing Degree Days	(GDD)	24
Frost Indices		24
Corn Heat Units (CHU))	24
Corn Season Start and	I End	25
Tsum Indices		25
Wet/Dry Climate Asses	ssment	25
Groundwater Use		25

LAND USE RESULTS	26
AGRICULTURAL WATER DEMAND MODEL RESULTS	28
Annual Crop Water Demand – Tables A and B	28
Annual Water Demand Reported by Irrigation System – Table C	28
Annual Water Demand by Soil Texture – Table D	28
Annual Water Demand by Local Government – Table E	28
Irrigation Management Factors – Table F	29
Deep Percolation – Table G	30
Improved Irrigation Efficiency and good Management – Table H	30
Livestock Water Use – Table I	30
Climate Change Water Demand for 2050 – Table J	30
Agricultural Buildout Crop Water Demand Using 2003 Climate Data – Table K	32
Agricultural Buildout Crop Water Demand for 2050 – Table L	34
Irrigation Systems Used for the Buildout Scenario – Table M	34
Water Demand by Local Government for the Buildout Scenario – Table N	34
LITERATURE	35
APPENDIX TABLES	

List of Figures

Figure 1	Map of ALR in Bonaparte	6
Figure 2	Overlaid Survey Map Sheets, Bonaparte	7
Figure 3	Land Use Survey	8
Figure 4	GIS Map Sheet	9
Figure 5	Cadastre with Polygon	9
Figure 6	GIS Model Graphic	10
Figure 7	Bonaparte Area Climate Stations	11
Figure 8	Area of Water	27
Figure 9	Area of ALR	27
Figure 10	Area of Land Parcels	27
Figure 11	Annual ET and Effective Precipitation in 2050's	31
Figure 12	Future Irrigation Demand for All Outdoor Uses in the Okanagan in Response to	
·	Observed Climate Data (Actuals) and Future Climate Data Projected from a Range of	f
	Global Climate Models	32
Figure 13	Bonaparte Irrigation Expansion Potential	33

List of Tables

Table 1	Livestock Water Demand (Litres/day)	. 18
Table 2	Overview of Land and Inventoried Area in Bonaparte	.26
Table 3	Summary of Primary Agricultural Activities within the ALR where Primary Land Use is	
	Agriculture in Bonaparte	.26
Table 4	Irrigation Management Factors	.29

Acknowledgements

There are many people that have been involved with the preparation and collection of data used in the development of the Water Demand Model for the Bonaparte River. The authors wish to express appreciation to the following for their efforts and/or in-kind contribution for the tasks noted.

PROFESSIONALS AND CONTRACTORS

Alex Cannon Sam Lee Corrine Roesler Linda Hokanson Andrew Petersen Kari Lynn Dundass Nancy Portman Environment Canada Ministry of Agriculture Climate Data Downscaling GIS Coordination GIS Coordination Cover and Publication Design Land Use Inventory Land Use Inventory Land Use Inventory The Agriculture Water Demand Model (AWDM) was originally developed in the Okanagan Watershed. It was developed in response to rapid population growth, drought conditions from climate change, and the overall increased demand for water. Many of the watersheds in British Columbia (BC) are fully allocated or will be in the next 15 to 20 years. The AWDM helps to understand current agricultural water use and helps to fulfil the Province's commitment under the "*Living Water Smart – BC Water Plan*" to reserve water for agricultural lands. The Model can be used to establish agricultural water reserves throughout the various watersheds in BC by providing current and future agriculture water use data.

Climate change scenarios developed by the University of British Columbia (UBC) and the Pacific Agri-Food Research Centre (PARC) in Summerland predict an increase in agricultural water demand due to warmer and longer summers and lower precipitation during summer months in the future.

The Agriculture Water Demand Model was developed to provide current and future agricultural water demands. The Model calculates water use on a property-by-property basis, and sums each property to obtain a total water demand for the entire basin or each sub-basin. Crop, irrigation system type, soil texture and climate data are used to calculate the water demand. Climate data from 2003 was used to present information on one of the hottest and driest years on record and 1997 data was used to represent a wet year. Lands within the Agriculture Land Reserve (ALR), depicted in green in Figure 1 were included in the project.



Figure 1 Map of ALR in Bonaparte

Methodology

The Model is based on a Geographic Information System (GIS) database that contains information on cropping, irrigation system type, soil texture and climate data. An explanation of how information was compiled for each is given below. The survey area included all properties within the ALR and areas that were zoned for agriculture by the local government. The inventory was undertaken by Ministry of Agriculture (AGRI) staff, hired professional contractors and summer students. Figure 2 provides a schematic of the map sheets that were generated to conduct the survey.



Figure 2 Overlaid Survey Map Sheets, Bonaparte

Cadastre

Cadastre information was provided by the Thompson Nicola Regional District. The entire regional district is covered in one dataset which allows the Model to report out on each sub-basin, local government, water purveyor or groundwater aquifer. A GIS technician used aerial photographs to conduct an initial review of cropping information by cadastre, and divided the cadastre into polygons that separated farmstead and driveways from cropping areas. Different crops were also separated into different polygons if the difference could be identified on the aerial photographs. This data was entered into the database that was used by the field teams to conduct and complete the land use survey.

Land Use Survey

The survey maps and database were created by AGRI for the survey crew to enter data about each property. Surveys were done during the summer of 2012. The survey crew drove by each property where the team checked the database for accuracy using visual observation and the aerial photographs on the survey maps. A Professional Agrologist verified what was on the site and a GIS technician altered the codes in the database as necessary (Figure 3). Corrections were handwritten on the maps. The map sheets were then brought back to the office to have the hand- drawn lines digitized into the GIS system and have the additional polygons entered into the database.

Once acquired through the survey, the land use data was brought into the GIS to facilitate analysis and produce maps. Digital data, in the form of a database and GIS shape files (for maps), is available upon request through a data sharing agreement with the Ministry of Agriculture.



Figure 3 Land Use Survey

Figure 4 provides an example of a map sheet from Bonaparte. The region was divided into 186 map sheets. Each map sheet also had a key map to indicate where it was located in the region.

The smallest unit for which water use is calculated are the polygons within each cadastre. A polygon is determined by a change in land use or irrigation system within a cadastre. Polygons are designated as blue lines within each cadastre as shown in Figures 4 and 5. The dataset for Bonaparte encompasses 1,570 inventoried land parcels that are in or partially in the ALR. There are a total of 2,542 polygons (land covers) generated within these land parcels. Figure 5 provides an enhanced view of a cadastre containing three polygons. Each cadastre has a unique identifier as does each polygon. The polygon identifier is acknowledged by PolygonID. This allows the survey team to call up the cadastre in the database, review the number of polygons within the cadastre and ensure the land use is coded accurately for each polygon.



Figure 4 GIS Map Sheet



Figure 5 Cadastre with Polygon

Soil Information

Soil information was obtained digitally from the Ministry of Environment's Terrain and Soils Information System. The Computer Assisted Planning and Map Production application (CAPAMP) provided detailed (1:20,000 scale) soil surveys that were conducted in the Lower Mainland, on Southeast Vancouver Island, and in the Okanagan-Similkameen areas during the early 1980s. Products developed include soil survey reports, maps, agriculture capability and other related themes. Soil information required for this project was the soil texture (loam, etc.), the available water storage capacity and the peak infiltration rate for each texture type.

The intersection of soil boundaries with the cadastre and land use polygons creates additional polygons that the Model uses to calculate water demand. Figure 6 shows how the land use information is divided into additional polygons using the soil boundaries. The Model calculates water demand using every different combination of crop, soil and irrigation system as identified by each polygon.



Figure 6 GIS Model Graphic

The next section will discuss about climate information where the climate grid does not develop additional polygons. Each polygon has the climate grid cell which is prominent for that polygon assigned to it.

Climate Information

The agricultural water demand is calculated using climate, crop, irrigation system and soil information data. To incorporate the climatic diversity, climate layers were developed for the entire region on a 500 m x 500 m grid. Each grid cell contains daily climate data, minimum and maximum temperature (T_{min} and T_{max}), and precipitation which allows the Model to calculate a daily reference evapotranspiration rate (ET_o) value. A range of agro-climatic indices such as growing degree days (GDD), corn heat units (CHU), frost free days and temperature sum (Tsum) can also be calculated for each grid cell based on temperature data. These values are used to determine seeding dates and the length of the growing season in the Model.

The climate dataset is generated using existing data from climate stations in and around the Bonaparte River from 1961 to 2003, and other station data close to the region. This climate data set was then downscaled to provide a climate data layer for the entire watershed on the 500 m x 500 m grid. A detailed description of the climate modeling can be obtained by contacting the authors.

Some of the existing climate stations that were used to determine the climate coverage are shown in Figure 7. The attributes attached to each climate grid cell include:

- Latitude
- Longitude
- Elevation
- Aspect
- Slope
- Daily Precipitation
- Daily T_{max} and T_{min}



Figure 7 Bonaparte Area Climate Stations

The climate database generated contains T_{min} , T_{max} , T_{mean} and Precipitation for each day of the year from 1961 to 2003. The parameters that need to be selected, calculated and stored within the Model are evapotranspiration (ET_o), Tsum of 1,000 (for the Island), effective precipitation (EP), frost free days, GDD with base temperatures of 5 °C and 10 °C, CHU, and first frost date. These climate and crop parameters are used to determine the growing season length as well as the beginning and end of the growing season in Julian day.

The Model calculates the water demand for each polygon by using crop, irrigation, soil and climate parameters as explained below. Each polygon has been assigned an ID number as mentioned previously.

Crop

The CropID is an attribute of the PolygonID as each polygon will contain a single crop. The crop information (observed during the land use survey) has been collected and stored with PolygonID as part of the land use survey. CropID will provide cropping attributes to the Model for calculating water use for each polygon. CropID along with the climate data will also be used to calculate the growing season length and the beginning and end of the growing season. The attributes for CropID include rooting depth, availability coefficient, crop coefficient and a drip factor.

Rooting depth is the rooting depth for a mature crop in a deep soil.

An availability coefficient is assigned to each crop. The availability coefficient is used with the IrrigID to determine the soil moisture available to the crop for each PolygonID.

The crop coefficient adjusts the calculated ET_o for the stages of crop growth during the growing season. Crop coefficient curves have been developed for every crop. The crop coefficient curve allows the Model to calculate water demand with an adjusted daily ET_o value throughout the growing season.

The drip factor is used in the water use calculation for polygons where drip irrigation systems are used. Since the Model calculates water use by area, the drip factor adjusts the percentage of area irrigated by the drip system for that crop.

Irrigation

The IrrigID is an attribute of the PolygonID as each polygon will have a single irrigation system type operating. The irrigation information has been collected and stored (as observed during the land use survey) with the land use data. The land use survey determined if a polygon had an irrigation system operating, what the system type was, and if the system was being used. The IrrigID has an irrigation efficiency listed as an attribute.

Two of the IrrigID's, Overtreedrip and Overtreemicro are polygons that have two systems in place. Two irrigation ID's occur when an overhead irrigation system has been retained to provide crop cooling or frost protection. In this case, the efficiencies used in the Model are the drip and microsprinkler efficiencies.

Soil

The soil layer came from CAPAMP at the Ministry of Environment. In addition, soil data provided by Agriculture and Agri-Food Canada (AAFC) was also used to generate multiple soil layers within each polygon. Each parcel was assigned the most predominant soil polygon, and then for each crop field

within that soil polygon, the most predominant texture within the crop's rooting depth was determined and assigned to the crop field.

Note that textures could repeat at different depths – the combined total of the thicknesses determined the most predominant texture. For example, a layer of 20 cm sand, followed by 40 cm clay and then 30 cm of sand would have sand be designated at the predominant soil texture.

The attributes attached to the SoiIID is the Available Water Storage Capacity (AWSC) which is calculated using the soil texture and crop rooting depth.

The Maximum Soil Water Deficit (MSWD) is calculated to determine the parameters for the algorithm that is used to determine the Irrigation Requirement (IR). The Soil Moisture Deficit at the beginning of the season is calculated using the same terms as the MSWD.

Climate

The climate data in the Model is used to calculate a daily reference evapotranspiration rate (ET_o) for each climate grid cell. The data that is required to calculate this value are:

- Elevation, metres (m)
- Latitude, degrees (°)
- Minimum Temperature, degree Celsius (°C)
- Maximum Temperature, degree Celsius (°C)
- Classification as Coastal or Interior
- Classification as Arid or Humid
- Julian Day

Data that is assumed or are constants in this calculation are:

٠	Wind speed	2 m/s
٠	Albedo or canopy reflection coefficient,	0.23
•	Solar constant, G _{sc}	0.082 MJ ⁻² min ⁻¹
٠	Interior and Coastal coefficients, K _{Rs}	0.16 for interior locations
		0.19 for coastal locations
•	Humid and arid region coefficients, K _o	0 °C for humid/sub-humid climates
	-	2 °C for arid/semi-arid climates

Agricultural Water Demand Equation

The Model calculates the Agriculture Water Demand (AWD) for each polygon, as a unique crop, irrigation system, soil and climate data is recorded on a polygon basis. The polygons are then summed to determine the AWD for each cadastre. The cadastre water demand values are then summed to determine AWD for the basin, sub-basin, water purveyor or local government. The following steps provide the process used by the Model to calculate Agricultural Water Demand. The entire process is outlined although not all of the steps may be used for the Bonaparte, e.g flood harvesting. Detailed information is available on request.

1. Pre-Season Soil Moisture Content

Prior to the start of each crop's growing season, the soil's stored moisture content is modelled using the soil and crop evaporation and transpiration characteristics and the daily precipitation values. Precipitation increases the soil moisture content and evaporation (modelled using the reference potential evapotranspiration) depletes it. In general, during the pre-season, the soil moisture depth cannot be reduced beyond the maximum evaporation depth; grass crops in wet climates, however, can also remove moisture through crop transpiration.

The process used to model the pre-season soil moisture content is:

- 1. Determine whether the modelling area is considered to be in a *wet* or *dry* climate (see *Wet/Dry Climate Assessment*), and retrieve the early season evaporation factor in the modelling area
- 2. For each crop type, determine the start of the growing season (see *Growing Season Boundaries*)
- 3. For each crop and soil combination, determine the *maximum soil water deficit* (MSWD) and *maximum evaporation factor* (maxEvaporation)
- 4. Start the initial storedMoisture depth on January 1 at the MSWD level
- 5. For each day between the beginning of the calendar year and the crop's growing season start, calculate a new stored moisture from:
 - a. the potential evapotranspiration (ET_o)
 - b. the early season evaporation factor (earlyEvaporationFactor)
 - c. the effective precipitation (EP) = actual precipitation x earlyEvaporationFactor
 - d. daily Climate Moisture Deficit (CMD) = $ET_o EP$
 - e. storedMoisture = previous day's storedMoisture CMD

A negative daily CMD (precipitation in excess of the day's potential evapotranspiration) adds to the stored moisture level while a positive climate moisture deficit reduces the amount in the stored moisture reservoir. The stored moisture cannot exceed the maximum soil moisture deficit; any precipitation that would take the stored moisture level above the MSWD gets ignored.

For all crops and conditions except for grass in wet climates, the stored moisture content cannot drop below the maximum soil water deficit minus the maximum evaporation depth; without any crop transpiration in play, only a certain amount of water can be removed from the soil through evaporative processes alone. Grass in wet climates does grow and remove moisture from the soil prior to the start of the irrigation season, however. In those cases, the stored moisture level can drop beyond the maximum evaporation depth, theoretically to 0.

Greenhouses and mushroom barns have no stored soil moisture content.

2. In-Season Precipitation

During the growing season, the amount of precipitation considered effective (EP) depends on the overall wetness of the modelling area's climate (see *Wet/Dry Climate Assessment*). In dry climates, the first 5 mm of precipitation is ignored, and the EP is calculated as 75% of remainder:

$$EP = (Precip - 5) \times 0.75$$

In wet climates, the first 5 mm is included in the EP. The EP is 75% of the actual precipitation:

$$EP = Precip \times 0.75$$

Greenhouses and mushroom barns automatically have an EP value of 0.

3. Crop Cover Coefficient (K_c)

As the crops grow, the amount of water they lose due to transpiration changes. Each crop has a pair of polynomial equations that provide the crop coefficient for any day during the crop's growing season. It was found that two curves, one for modelling time periods up to the present and one for extending the modelling into the future, provided a better sequence of crop coefficients than using a single curve for all years (currently 1961 to 2100). The application automatically selects the current or future curve as modelling moves across the *crop Curve Changeover Year*.

For alfalfa crops, there are different sets of equations corresponding to different cuttings throughout the growing season.

4. Crop Evapotranspiration (ET_c)

The evapotranspiration for each crop is calculated as the general ET_o multiplied by the crop coefficient (K_c):

$$ET_c = ET_o \times K_c$$

5. Climate Moisture Deficit (CMD)

During the growing season, the daily Climate Moisture Deficit (CMD) is calculated as the crop evapotranspiration (ET_c) less the Effective Precipitation (EP):

$$CMD = ET_c - EP$$

During each crop's growing season, a stored moisture reservoir methodology is used that is similar to the soil moisture content calculation in the pre-season. On a daily basis, the stored moisture level is used towards satisfying the climate moisture deficit to produce an *adjusted Climate Moisture Deficit* (CMD_a):

$$CMD_a = CMD - storedMoisture$$

If the stored Moisture level exceeds the day's CMD, then the CMD_a is 0 and the stored moisture level is reduced by the CMD amount. If the CMD is greater than the stored moisture, then all of the stored moisture is used (stored Moisture is set to 0) and the adjusted CMD creates an irrigation requirement.

The upper limit for the storedMoisture level during the growing season is the maximum soil water deficit (MSWD) setting.

6. Crop Water Requirement (CWR)

The Crop Water Requirement is calculated as the adjusted Climate Moisture Deficit (CMD_a) multiplied by the soil water factor (swFactor) and any stress factor (used primarily for grass crops):

$$CWR = CMD_a x swFactor x stressFactor$$

7. Irrigation Requirement (IR)

The Irrigation Requirement is the Crop Water Requirement (CWR) after taking into account the irrigation efficiency (I_e) and, for drip systems, the drip factor (D_f):

IR = CWR x
$$\frac{D_{f}}{I_{e}}$$

For irrigation systems other than drip, the drip factor is 1.

8. Irrigation Water Demand (IWDperc and IWD)

The portion of the Irrigation Water Demand lost to deep percolation is the Irrigation Requirement (IR) multiplied by the percolation factor (soilPercFactor):

 $IWD_{perc} = IR x soilPercFactor$

The final Irrigation Water Demand (IWD) is then the Irrigation Requirement (IR) plus the loss to percolation (IWD_{perc}):

$$IWD = IR + IWD_{perc}$$

9. Frost Protection

For some crops (e.g. cranberries), an application of water is often used under certain climatic conditions to provide protection against frost damage. For cranberries, the rule is: when the temperature drops to 0 °C or below between March 16 and May 20 or between October 1 and November 15, a frost event will be calculated. The calculated value is an application of 2.5 mm per hour for 10 hours. In addition, 60% of the water is recirculated and reused, accounting for evaporation and seepage losses.

This amounts to a modelled water demand of 10 mm over the cranberry crop's area for each day that a frost event occurs between the specified dates.

10. Annual Soil Moisture Deficit

Prior to each crop's growing season, the Model calculates the soil's moisture content by starting it at full (maximum soil water deficit level) on January 1, and adjusting it daily according to precipitation and evaporation. During the growing season, simple evaporation is replaced by the crop's evapotranspiration as it progresses through its growth stages. At the completion of each crop's growing season, an annual soil moisture deficit (SMD) is calculated as the difference between the soil moisture content at that point and the maximum soil water deficit (MSWD):

$$SMD = MSWD$$
 - stored Moisture

In dry/cold climates, this amount represents water that the farmer would add to the soil in order to prevent it from freezing. Wet climates are assumed to have sufficient precipitation and warm

enough temperatures to avoid the risk of freezing without this extra application of water; the SMD demand is therefore recorded only for dry areas.

There is no fixed date associated with irrigation to compensate for the annual soil moisture deficit. The farmer may choose to do it any time after the end of the growing season and before the freeze up. In the Model's summary reports, the water demand associated with the annual soil moisture deficit shows as occurring at time 0 (week 0, month 0, etc.) simply to differentiate it from other demands that do have a date of occurrence during the crop's growing season.

Greenhouses and mushroom barns do not have an annual soil moisture deficit.

11. Flood Harvesting

Cranberry crops are generally harvested using flood techniques. The Model calculates the flood harvesting demand as 250 mm of depth for 10% of the cranberry farmed area. For modelling purposes, it is assumed that 250 mm of water gets applied to the total cranberry crop area, 10% at a time. The water is reused for subsequent portions, but by the time the entire crop is harvested, all of the water is assumed to have been used and either depleted through losses or released from the farm.

The water demand is therefore calculated as a fixed 25 mm over the entire cranberry crop area. The harvesting generally takes place between mid-October and mid-November where the Model treats it as occurring on the fixed date of November 16.

Livestock Water Use

The Model calculates an estimated livestock water demand using agricultural census data and an estimate of the water use per animal. Water use for each animal type is calculated a bit differently depending on requirements. For example, for a dairy milking cow, the water demand for each animal includes, drinking, preparation for milking, pen and barn cleaning, milking system washout, bulk tank washout and milking parlor washing. However, for a dry dairy cow, the demand only includes drinking and pen and barn cleaning.

The water use is estimated on a daily basis per animal even though the facility is not cleaned daily. For example, for a broiler operation, the water use for cleaning a barn is calculated as 4 hours of pressure washing per cycle at a 10 gpm flow rate, multiplied by 6 cycles per barn with each barn holding 50,000 birds. On a daily basis, this is quite small with a value of 0.01 litres per day per bird applied.

For all cases, the daily livestock demand is applied to the farm location. However, in the case of beef, the livestock spend quite a bit of the year on the range. Since the actual location of the animals cannot be ascertained, the water demand is applied to the home farm location, even though most of the demand will not be from this location. Therefore, the animal water demand on a watershed scale will work fine but not when the demand is segregated into sub-watersheds or groundwater areas.

Table 1 Livestock Water Demand (Litres/day)									
Animal Type	Drinking	Milking Preparation	Barn Component	Total					
Milking Dairy Cow	65	5	15	85					
Dry Cow	45		5	50					
Swine	12		0.5	12.5					
Poultry – Broiler	0.16		0.01	0.17					
Poultry – Layer	0.08		0.01	0.09					
Turkeys	0.35		0.01	0.36					
Goats	8			8					
Sheep	8			8					
Beef – range, steer, bull, heifer	50			50					
Horses	50			50					

The estimates used for each livestock are shown in Table 1.

Growing Season Boundaries

There are three sets of considerations used in calculating the start and end of the irrigation season for each crop:

- temperature-based growing season derivations, generally using Temperature Sum (Tsum) or Growing Degree Day (GDD) accumulations
- the growing season overrides table
- the irrigation season overrides table

These form an order of precedence with later considerations potentially overriding the dates established for the previous rules. For example, the temperature-based rules might yield a growing season start date of day 90 for a given crop in a mild year. To avoid unrealistic irrigation starts, the season overrides table might enforce a minimum start day of 100 for that crop; at that point, the season start would be set to day 100. At the same time, a Water Purveyor might not turn on the water supply until day 105; specifying that as the minimum start day in the irrigation season overrides table would prevent any irrigation water demands until day 105.

This section describes the rules used to establish growing season boundaries based on the internal calculations of the Model. The GDD and Tsum Day calculations are described in separate sections. The *standard end of season* specified for several crops is the earlier of the end date of Growing Degree Day with base temperature of 5 $^{\circ}$ C (GDD₅) or the first frost.

1. Corn (silage corn)

- uses the corn_start date for the season start
- season end: earlier of the killing frost or the day that the CHU2700 (2700 Corn Heat Units) threshold is reached

2. Sweetcorn, Potato, Tomato, Pepper, Strawberry, Vegetable, Pea

- corn_start date for the season start
- corn start plus 110 days for the season end

3. Cereal

- GDD5 start for the season start
- GDD5 start plus 130 days for the season end

4. AppleHD, AppleMD, AppleLD, Asparagus, Berry, Blueberry, Ginseng, Nuts, Raspberry, Sourcherry, Treefruit, Vineberry

- season start: (0.8447 x tsum600_day) + 18.877
- standard end of season

5. Pumpkin

- corn_start date
- standard end of season

6. Apricot

- season start: (0.9153 x tsum400_day) + 5.5809
- standard end of season

7. CherryHD, CherryMD, CherryLD

- season start: (0.7992 x tsum450_day) + 24.878
- standard end of season

8. Grape, Kiwi

- season start: (0.7992 x tsum450_day) + 24.878
- standard end of season

9. Peach, Nectarine

- season start: (0.8438 x tsum450_day) + 19.68
- standard end of season

10. Plum

- season start: (0.7982 x tsum500_day) + 25.417
- standard end of season

11. Pear

- season start: (0.8249 x tsum600_day) + 17.14
- standard end of season

12. Golf, TurfFarm

- season start: later of the GDD₅ start and the tsum300_day
- standard end of season

13. Domestic, Yard, TurfPark

- season start: later of the GDD₅ start and the tsum400_day
- standard end of season

14. Greenhouse (interior greenhouses)

• fixed season of April 1 – October 30

15. GH Tomato, GH Pepper, GH Cucumber

• fixed season of January 15 – November 30

16. GH Flower

• fixed season of March 1 – October 30

17. GH Nursery

• fixed season of April 1 – October 30

18. Mushroom

• all year: January 1 – December 31

19. Shrubs/Trees, Fstock, NurseryPOT

- season start: tsum500_day
- end: julian day 275

20. Floriculture

- season start: tsum500_day
- end: julian day 225

21. Cranberry

- season start: tsum500_day
- end: julian day 275

22. Grass, Forage, Alfalfa, Pasture

- season start: later of the GDD₅ and the tsum600_day
- standard end of season

23. Nursery

- season start: tsum400_day
- standard end of season

Evapotranspiration (ET_o)

The ET_o calculation follows the FAO Penman-Montieth equation. Two modifications were made to the equation:

- Step 6 Inverse Relative Distance Earth-Sun (d_r) Instead of a fixed 365 days as a divisor, the actual number of days for each year (365 or 366) was used.
- Step 19 Evapotranspiration (ET_o) For consistency, a temperature conversion factor of 273.16 was used instead of the rounded 273 listed.

Availability Coefficient (AC)

The availability coefficient is a factor representing the percentage of the soil's total water storage that the crop can readily extract. The factor is taken directly from the crop factors table (*crop_factors*) based on the cropId value.

Rooting Depth (RD)

The rooting depth represents the crop's maximum rooting depth and thus the depth of soil over which the plant interacts with the soil in terms of moisture extraction. The value is read directly from the crop factors table.

Stress Factor (stressFactor)

Some crops, such as *grasses*, are often irrigated to a less degree than their full theoretical requirement for optimal growth. The *stress factor* (*crop_groups_and_factors*) reduces the calculated demand for these crops.

Available Water Storage Capacity (AWSC)

The available water storage capacity is a factor representing the amount of water that a particular soil texture can hold without the water dropping through and being lost to deep percolation. The factor is taken directly from the soil factors table (*soil factors*).

Maximum Soil Water Deficit (MSWD)

The maximum soil water deficit is the product of the crop's availability coefficient, rooting depth, and the available water storage capacity of the soil:

$$MSWD = RD \times AWSC \times AC$$

Deep Percolation Factor (soilPercFactor)

The soil percolation factor is used to calculate the amount of water lost to deep percolation under different management practices.

For greenhouse crops, the *greenhouse leaching factor* is used as the basic soil percolation factor. This is then multiplied by a greenhouse recirculation factor, if present, to reflect the percentage of water recaptured and re-used in greenhouse operations.

soilPercFactor = *soilPercFactor* **x** (*l* - *recirculationFactor*)

For Nursery Pot (Nursery POT) and Forestry Stock (Fstock) crops, the soil percolation factor is fixed at 35%. For other crops, the factor depends on the soil texture, the MSWD, the irrigation system, and the Irrigation Management Practices code. The percolation factors table (*soil_percolation_factors*) is read to find the first row with the correct management practices, soil texture and irrigation system, and a MSWD value that matches or exceeds the value calculated for the current land use polygon.

If the calculated MSWD value is greater than the index value for all rows in the percolation factors table, then the highest MSWD factor is used. If there is no match based on the passed parameters, then a default value of 0.25 is applied.

For example, a calculated MSWD value of 82.5 mm, a soil texture of sandy loam (SL) and an irrigation system of solid set overtree (Ssovertree) would retrieve the percolation factor associated with the MSWD index value of 75 mm in the current table (presently, there are rows for MSWD 50 mm and 75 mm for SL and Ssovertree).

Maximum Evaporation Factor (maxEvaporation)

Just as different soil textures can hold different amounts of water, they also have different depths that can be affected by evaporation. The factor is taken directly from the soil factors table.

Irrigation Efficiency (I_e)

Each irrigation system type has an associated efficiency factor (inefficient systems require the application of more water in order to satisfy the same crop water demand). The factor is read directly from the irrigation factors table (*irrigation_factors*).

Soil Water Factor (swFactor)

For the greenhouse "crop", the soil water factor is set to 1. For other crops, it is interpolated from a table (*soil_water_factors*) based on the MSWD. For Nurseries, the highest soil water factor (lowest MSWD index) in the table is used; otherwise, the two rows whose MSWD values bound the calculated MSWD are located and a soil water factor interpolated according to where the passed MSDW value lies between those bounds.

For example, using the current table with rows giving soil water factors of 0.95 and 0.9 for MSWD index values of 75 mm and 100 mm respectively, a calculated MSWD value of 82.5 mm would return a soil water factor of:

$$0.95 + \left[\frac{82.5 - 75}{100 - 75} \times (0.9 - 0.95)\right]$$

= 0.935

If the calculated MSWD value is higher or lower than the index values for all of the rows in the table, then the factor associated with the highest or lowest MSWD index is used.

Early Season Evaporation Factor (earlyEvaporationFactor)

The effective precipitation (precipitation that adds to the stored soil moisture content) can be different in the cooler pre-season than in the growing season. The early season evaporation factor is used to determine what percentage of the precipitation is considered effective prior to the growing season.

Crop Coefficient (K_c)

The crop coefficient is calculated from a set of fourth degree polynomial equations representing the crop's ground coverage throughout its growing season. The coefficients for each term are read from the crop factors table based on the crop type, with the variable equalling the number of days since the start of the crop's growing season. For example, the crop coefficient for Grape on day 35 of the growing season would be calculated as:

$$K_c = \begin{bmatrix} 0.000000031 \times (35)^4 \end{bmatrix} + \begin{bmatrix} -0.0000013775 \times (35)^3 \end{bmatrix} + (0.0001634536 \times (35)^2 \end{bmatrix} + (-0.0011179845 \times 35) + 0.2399004137$$

=
$$0.346593241$$

Alfalfa crops have an additional consideration. More than one cutting of alfalfa can be harvested over the course of the growing season, and the terms used for the crop coefficient equation changes for the different cuttings. For alfalfa, the alfalfa cuttings table is first used to determine which cutting period the day belongs to (first, intermediate or last), and after that the associated record in the crop factors table is accessed to determine the terms.

There are two sets of polynomial coefficients used to calculate the crop coefficient; the first set is used for modelling time periods up to the year specified as the *crop curve changeover year*; and the second for modelling into the future. The changeover year will be modified as time goes on and new historical climate observations become available.

Growing Degree Days (GDD)

The Growing Degree Day calculations generate the start and end of GDD accumulation.

1. Start of GDD Accumulation

For each base temperature (bases 5 and 10 are always calculated, other base temperature can be derived), the start of the accumulation is defined as occurring after 5 consecutive days of T_{mean} matching or exceeding the base temperature (BaseT). The search for the start day gets reset if a killing frost (< -2 °C) occurs, even after the accumulation has started. The search also restarts if there are 2 or more consecutive days of $T_{min} \leq 0$ °C. The GDD start is limited to Julian days 1 to 210; if the accumulation has not started by that point, then it is unlikely to produce a reasonable starting point for any crop.

2. End of GDD accumulation

The search for the end of the GDD accumulation begins 50 days after its start. The accumulation ends on the earlier of 5 consecutive days where T_{mean} fails to reach BaseT (strictly <u>less than</u>) or the first killing frost (-2 °C).

During the GDD accumulation period, the daily contribution is the difference between T_{mean} and BaseT, as long as T_{mean} is not less than BaseT:

 $GDD = T_{mean} - BaseT; 0 if negative$

Frost Indices

Three frost indices are tracked for each year:

- the last spring frost is the latest day in the first 180 days of the year with a $T_{min} \le 0$ °C
- the first fall frost is the first day between days 240 and the end of the year where $T_{min} \le 0$ °C
- the killing frost is the first day on or after the first fall frost where $T_{min} \le -2$ °C

Corn Heat Units (CHU)

The Corn Heat Unit is the average of two terms using T_{min} and T_{max} . Prior to averaging, each term is set to 0 individually if it is negative.

term1 =
$$[3.33 \times (T_{max} - 10)] - [0.084 \times (T_{max} - 10) \times (T_{max} - 10)]; 0 \text{ if negative}$$

term2 = $1.8 \times (T_{min} - 4.44); 0 \text{ if negative}$
CHU = $\frac{(\text{term1 + term2})}{2}$

Corn Season Start and End

The corn season boundary derivations are similar to the GDD determinations. The start day is established by 3 consecutive days where $T_{mean} \ge 11.2$ °C. As in the case of the GDD calculations, the search for the corn season start day gets reset if $T_{min} \le -2$ °C, or if there are 2 or more consecutive days of -2 °C $\le T_{min} \le 0$ °C.

The search for the silage corn season end begins 50 days after the start. The season ends on the earlier of a mean temperature dropping below 10.1 or a killing frost.

The end of the sweet corn season is defined as 110 days after the season start.

Tsum Indices

The Tsum day for a given number is defined as the day that the sum of the positive daily T_{mean} reaches that number. For example, the Tsum400 day is the day where the sum of the positive T_{mean} starting on January 1 sum to 400 units or greater.

Days where T_{mean} falls below 0 $^{\circ}C$ are simply not counted; therefore, the Model does not restart the accumulation sequence.

Wet/Dry Climate Assessment

Starting with the Lower Mainland, some of the modelling calculations depend on an assessment of the general climatic environment as *wet* or *dry*. For example, when modelling the soil moisture content prior to the start of the crop's growing season, the reservoir can only be drawn down by evaporation except for *grass* crops in *wet* climates which can pull additional moisture out of the soil.

The assessment of wet or dry uses the total precipitation between May 1 and September 30. If the total is more than 125 mm during that period, the climate is considered to be *wet* and otherwise *dry*.

Groundwater Use

The Model generates water sources for irrigation systems. This is done by first determining which farms are supplied by a water purveyor, and then coding those farms as such. Most water purveyors use surface water but where groundwater is used, the farms are coded as groundwater use. The second step is to check all water licences and assign the water licences to properties in the database. The remaining farms that are irrigating will therefore not have a water licence or be supplied by a water purveyor. The assumption is made that these farms are irrigated by groundwater sources.

Land Use Results

A summary of the land area and the inventoried area of Bonaparte is shown in Table 2. The primary agricultural use of the ARL area is shown in Table 3. Figures 8, 9 and 10 show the areas of water, ALR and land parcels in the Bonaparte Watershed graphically.

Table 2 Overview of Land and Inventoried Area in Bonaparte									
Area Type	Area (ha)	Number of Parcels							
Bonaparte									
Total Area	397,317	-							
Area of Water Feature	16,398	-							
Area of Land (excluding water features)	380,919	-							
ALR Area	66,590	1,578							
Area of First Nations Reserve	3,463	18							
Inventoried Area									
Total Inventoried Area	66,565	1,570							
Area of First Nations Reserve in ALR	2,545	12							

Table 3Summary of Primary Agricultural Activities within the ALR where Primary Land Use is Agriculture in Bonaparte									
Primary Agriculture Activity Total ALR Area (ha) Number of Parcels									
Forage and Pasture	11,770	362							
Tree Fruits	5	1							
Vegetables	40	5							
Total	11,815	368							



Figure 8 Area of Water

Figure 9 Area of ALR



Figure 10 Area of Land Parcels

The Model has a reporting feature that can save and generate reports for many different scenarios that have been pre-developed. This report will provide a summary of the reported data in the Appendices. Climate data from 1997 and 2003 were chosen as they represent a relatively wet year and dry year respectively. Most reports are based on the 2003 data since the maximum current demand can then be presented.

Annual Crop Water Demand – Tables A and B

The Model can use three different irrigation management factors, good, average and poor. Unless otherwise noted, average management were used in the tables. Table A provides the annual irrigation water demand for current crop and irrigation systems for the year 2003 using average irrigation management, and Table B provides the same data for 1997.

The irrigated acreage in the ALR for the Bonaparte region is 2,963 hectares (ha). The total annual irrigation demand for this area was 24,874,308 m³ in 2003 (a dry year), and dropped to 16,076,023 m³ in 1997 (a wet year). Of interest is that during a wet year like 1997, the demand was only 65% of a hot dry year like 2003.

In addition, the Model also calculates demand based on relatively good practices. As such, actual use may actually be higher or lower than what is calculated by the Model.

The predominant irrigated agriculture crop in Bonaparte is forage which forms 60% of the total irrigated acreage. The next largest irrigated agriculture crop is alfalfa (37%).

Annual Water Demand Reported by Irrigation System – Table C

The crop irrigation demand can also be reported by irrigation system type as shown in Tables C. As forage is the predominant crop type, there is limited acreage that is currently irrigated by efficient systems, such as drip, microsprinkler or microspray. Approximately 15% of the systems are centre pivot which may have higher efficiencies. Handline, wheelline, flood irrigation, and travelling gun systems used on forage and alfalfa crops account for approximately 80% of the irrigation system types.

Annual Water Demand by Soil Texture – Table D

Table D provides the annual water demand by soil texture. Where soil texture data is missing, the soil texture has been defaulted to sandy loam. The defaults are shown in Table D.

Annual Water Demand by Local Government – Table E

Table E provides a breakdown of the agricultural irrigated areas within the boundaries of each local government within Bonaparte.

Irrigation Management Factors – Table F

The Model can estimate water demand based on poor, average and good irrigation management factors. This is accomplished by developing an irrigation management factor for each crop, soil and irrigation system combination. The Maximum Soil Water Deficit (MSWD) is the maximum amount of water that can be stored in the soil within the crop rooting zone. An irrigation system applying more water than what can be stored will result in percolation beyond the crop's rooting depth. Irrigation systems with high application rates will have a probability of higher percolation rates, a stationary gun for instance.

For each soil class, ranges of four MSWD are provided, which reflect a range of crop rooting depths. An irrigation management factor, which determines the amount of leaching, is established for each of the MSWD values for the soil types (Table 4). The management factor is based on irrigation expertise as to how the various irrigation systems are able to operate. For example, Table 4 indicates that for a loam soil and a MSWD of 38 mm, a solid set overtree system has a management factor of 0.1 for good management while the drip system has a management factor of 0.05. This indicates that it is easier to prevent percolation with a drip system than it is with a solid set sprinkler system. For poor management, the factors are higher.

	Table 4 Irrigation Management Factors										
Coll Touture	MOWD	S	olid Set Overtr	96	Drip						
Soil Texture	INISVUD	Good	Average	Poor	Good	Average	Poor				
Loam	38	0.10	0.15	0.20	0.05	0.10	0.15				
	50	0.05	0.10	0.15	0.05	0.075	0.10				
	75	0.05	0.10	0.15	0.05	0.075	0.10				
	100	0.05	0.075	0.10	0.05	0.075	0.10				
Sandy loam	25	0.20	0.225	0.25	0.10	0.15	0.20				
	38	0.10	0.15	0.20	0.10	0.125	0.15				
	50	0.05	0.10	0.15	0.05	0.10	0.10				
	75	0.05	0.10	0.15	0.05	0.075	0.10				

There are a total of 1,344 irrigation management factors established for the 16 different soil textures, MSWD and 21 different irrigation system combinations used in the Model.

The management factors increase as the MSWD decreases because there is less soil storage potential in the crop rooting depth. For irrigation systems such as guns, operating on a pasture which has a shallow rooting depth, on a sandy soil which cannot store much water, the poor irrigation management factor may be as high as 0.5.

The management factor used in the Model assumes all losses are deep percolation while it is likely that some losses will occur as runoff as well.

Table F provides an overview of the impacts on the management factor and irrigation systems used. Since 92% of the crops in Bonaparte are forage and alfalfa crops which are currently irrigated with sprinkler systems. Table F provides percolation rates based on good, average and poor management using 2003 climate data. In summary, there is 3,468,626 m³ of water lost to percolation on good management, 3,795,045 m³ on average management, and 4,121,464 m³ on poor management. Percolation rates for poor management are 19% higher than for good management.

Deep Percolation – Table G

The percolation rates vary by crop, irrigation system type, soil and the management factor used. Table G shows the deep percolation amounts by irrigation system type for average management. The last column provides a good indication of the average percolation per hectare for the various irrigation system types. For example, the percolation rate for pivots is about 60% that of a gun system.

Improved Irrigation Efficiency and good Management – Table H

There is an opportunity to reduce water use by converting irrigation systems to a higher efficiency for some crops. For example, drip systems could be used for all berry crops, vegetable crops and some of the other horticultural crops. Forage crops could be converted from gun or sprinkler systems to low pressure pivot. In addition, using better management such as irrigation scheduling techniques will also reduce water use. Table H provides a scenario of water demand if all sprinkler systems are converted to drip systems for horticultural crops in Bonaparte, and all forage crops larger than 10 ha are converted to pivot, using good irrigation management. The water demand for 2003 would reduce from 24,874,308 m³ to 20,126,935 m³ if for the system conversions outlined above were implemented.

Livestock Water Use – Table I

The Model provides an estimate of water use for livestock. The estimate is based on the number of animals in Bonaparte as determined by the latest census, the drinking water required for each animal per day and the barn or milking parlour wash water. Values used are shown in Table I. For Bonaparte, the amount of livestock water is estimated at 139,682 m³.

Climate Change Water Demand for 2050 – Table J

The Model also has access to climate change information until the year 2100. While data can be run for each year, the three driest years in the 2050's were selected to give a representation of climate change. Figure 11 shows the climate data results which indicate that 2053, 2056, and 2059 generate the highest annual ET_o and lowest annual precipitation. These three years were used in this report.



Figure 11 Annual ET and Effective Precipitation in 2050's

Table J provides the results of climate change on irrigation demand for the three years selected using current crops and irrigation systems. Current crops and irrigation systems are used to show the increase due to climate change only, with no other changes taking place.

Figure 12 shows all of the climate change scenario runs for the Okanagan using 12 climate models from 1960 to 2100. This work was compiled by Denise Neilsen at the Agriculture and Agri-Food Canada – Summerland Research Station. There is a lot of scatter in this figure, but it is obvious that there is a trend of increasing water demand.

The three climate change models used in this report are RCP26, RCP45 and RCP85. Running only three climate change models on three selected future years in Bonaparte is not sufficient to provide a trend like in Figure 12. What the results do show is that in an extreme climate scenario, it is possible to have an annual water demand that is 35% higher than what was experienced in 2003 based on the estimated demand in 2059 with climate change model RCP45. Averaging the data between the three climate

change models shows that if the data for just the year 2053 is examined, the increase in demand is 19% higher than 2003. More runs of the climate change models will be required to better estimate a climate change trend for Bonaparte.



Figure 12 Future Irrigation Demand for All Outdoor Uses in the Okanagan in Response to Observed Climate Data (Actuals) and Future Climate Data Projected from a Range of Global Climate Models

Agricultural Buildout Crop Water Demand Using 2003 Climate Data – Table K

An agricultural buildout scenario was developed that looked at potential agricultural lands that could be irrigated in the future. The rules used to establish where potential additional agricultural lands were located in Bonaparte are as follows:

- within 1,000 m of water supply (lake)
- within 1,000 m of water supply (water course)
- within 1,000 m of water supply (wetland)
- within 1,000 m of high productivity aquifer
- within 1,000 m of water purveyor
- with Ag Capability class 1-4 only where available
- must be within the ALR
- below 650 m average elevation (for south of and including Allen Creek), below 1,000 m average elevation (for north of Allen Creek)

For the areas that are determined to be eligible for future buildout, a crop and irrigation system need to be applied. Where a crop already existed in the land use inventory, that crop would remain and an irrigation system assigned. If no crop existed, then a crop and an irrigation system are assigned as per the criteria below.

- Grass: 75% of buildout area with sprinkler irrigation or low pressure pivot
- Alfalfa: 25% of buildout area with sprinkler irrigation or low pressure pivot

For the current irrigated area equal to or over 10 ha, and if the crop type is not ginseng, golf, nursery, turf park or blank, then the irrigation system type will be changed from sprinkler to low-pressure pivot (if not already using a low-pressure pivot). It is anticipated that current irrigation systems will be replaced by more efficient systems like low-pressure pivots in the future to reduce water demand when water resources are more stretched.

Figure 13 indicates the location of agricultural land that is currently irrigated (dark green) and the land that can be potentially irrigated (red). Based on the scenario provided for Bonaparte, the additional agricultural land that could be irrigated is 2,430 ha, bringing the total irrigated area to 5,393 ha. The water demand for a year like 2003 would be 36,541,881 m³ assuming efficient irrigation systems and good management.





Agricultural Buildout Crop Water Demand for 2050 – Table L

The same irrigation expansion and cropping scenario used to generate the values in Table K were used to generate the climate change water demand shown in Table L. Three climate models were used and the results averaged. When climate change is added to the buildout scenario the water demand increases from 36.5 million m³ for 2003 climate data to 43.3 million m³ if averaging the three climate change models for the 2053 scenario. The average for all three climate models for all three years (2053, 2056, 2059) is 39.4 million m³. Again, more runs are required to develop a good trend with the climate change data. See discussion under Table J.

Irrigation Systems Used for the Buildout Scenario – Table M

Table M provides an account of the irrigation systems used by area for the buildout scenario in the previous two examples. Note that centre pivot irrigation is the most predominant irrigation system as forage is projected to the major crop.

Water Demand by Local Government for the Buildout Scenario – Table N

Table N provides the water demand based on local governments for the buildout scenario in Table J. It can be compared with the values in Table E without the irrigated agriculture buildout scenario.

Cannon, A.J., and Whitfield, P.H. (2002), Synoptic map classification using recursive partitioning and principle component analysis. *Monthly Weather Rev.* 130:1187-1206.

Cannon, A.J. (2008), Probabilistic multi-site precipitation downscaling by an expanded Bernoulligamma density network. *Journal of Hydrometeorology*. http://dx.doi.org/10.1175%2F2008JHM960.1 Intergovernmental Panel on Climate Change (IPCC) (2008), Fourth Assessment Report –AR4. http://www.ipcc.ch/ipccreports/ar4-syr.htm

Neilsen, D., Duke, G., Taylor, W., Byrne, J.M., and Van der Gulik T.W. (2010). Development and Verification of Daily Gridded Climate Surfaces in the Okanagan Basin of British Columbia. *Canadian Water Resources Journal* 35(2), pp. 131-154. http://www4.agr.gc.ca/abstract-resume/abstract-resume.htm?lang=eng&id=21183000000448

Allen, R. G., Pereira, L. S., Raes, D. and Smith, M. (1998). Crop evapotranspiration Guidelines for computing crop water requirements. FAO Irrigation and Drainage Paper 56. United Nations Food and Agriculture Organization. Rome. 100pp

Appendix Tables

- Appendix Table A 2003 Water Demand by Crop with Average Management
- Appendix Table B 1997 Water Demand by Crop with Average Management
- Appendix Table C 2003 Water Demand by Irrigation System with Average Management
- Appendix Table D 2003 Water Demand by Soil Texture with Average Management
- Appendix Table E 2003 Water Demand by Local Government with Average Management
- Appendix Table F 2003 Management Comparison on Irrigation Demand and Percolation Volumes
- Appendix Table G 2003 Percolation Volumes by Irrigation System with Average Management
- Appendix Table H 2003 Crop Water Demand for Improved Irrigation System Efficiency and Good Management
- Appendix Table I 2003 Water Demand by Animal Type with Average Management
- Appendix Table J Climate Change Water Demand Circa 2050 for a High Demand Year with Good Management using Current Crops and Irrigation Systems
- Appendix Table K Buildout Crop Water Demand for 2003 Climate Data and Good Management
- Appendix Table L Buildout Crop Water Demand for Climate Change Data Circa 2050 and Good Management
- Appendix Table M Buildout Irrigation System Demand for 2003 Climate Data and Good Management
- Appendix Table N Buildout Demand by Local Government for 2003 Climate Data and Good Management

Appendix Table A				2003 V	Nater Dem	nand by	Crop wit	h Average	Manage	ement		
Water Source		Surface Water		Reclaimed Water			Groundwater			Total		
Agriculture Crop Group	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
Alfalfa	912.6	7,403,018	811	-	-	-	177.9	1,462,495	822	1,090.6	8,865,512	813
Apple	5.1	51,549	1,012	-	-	-	-	-	-	5.1	51,549	1,012
Forage	1,741.5	14,966,728	859	-	-	-	46.5	377,155	811	1,788.0	15,343,883	858
Golf	-	-	-	-	-	-	17.2	179,038	1,041	17.2	179,038	1,041
Recreational Turf	-	-	-	-	-	-	4.1	27,172	658	4.1	27,172	658
Vegetable	58.7	407,154	693	-	-	-	-	-	-	58.7	407,154	693
TOTALS	2,718.0	22,828,449	840	-	-	-	245.7	2,045,859	833	2,963.7	24,874,308	839

	Appendix Table B 1997 Water Demand by Crop with Average Management											
Water Source		Surface Water		Reclaimed Water			Groundwater			Total		
Agriculture Crop Group	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
Alfalfa	912.6	4,423,748	485	-	-	-	177.9	891,704	501	1,090.6	5,315,452	487
Apple	5.1	33,375	655	-	-	-	-	-	-	5.1	33,375	655
Forage	1,741.5	10,019,481	575	-	-	-	46.5	240,620	518	1,788.0	10,260,101	574
Golf	-	-	-	-	-	-	17.2	140,898	819	17.2	140,898	819
Recreational Turf	-	-	-	-	-	-	4.1	19,325	468	4.1	19,325	468
Vegetable	58.7	306,872	523	-	-	-	-	-	-	58.7	306,872	523
TOTALS	2,718.0	14,783,477	544	-	-	-	245.7	1,292,547	526	2,963.7	16,076,023	542

	Appe	ndix Table	C 2003	8 Water	Demand b	y Irrigat	ion Syst	em with Av	verage M	lanagem	ent	
Water Source		Surface Water		F	Reclaimed Wate	ər		Groundwater			Total	
Agriculture Irrigation System	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
Flood	603.0	7,195,142	1,193	-	-	-	14.7	180,445	1,229	617.7	7,375,587	1,194
Gun	66.1	613,718	929	-	-	-	3.9	42,115	1,074	70.0	655,832	937
Handline	677.2	4,822,307	712	-	-	-	94.7	663,656	701	771.9	5,485,962	711
Pivot	429.6	3,447,516	802	-	-	-	96.7	867,021	897	526.2	4,314,537	820
SDI	45.6	303,188	665	-	-	-	-	-	-	45.6	303,188	665
Sprinkler	84.0	545,920	650	-	-	-	35.7	292,622	819	119.7	838,543	701
Subirrig	9.1	57,323	629	-	-	-	-	-	-	9.1	57,323	629
Travgun	340.2	2,538,534	746	-	-	-	-	-	-	340.2	2,538,534	746
Wheelline	463.3	3.304.801	713	-	-	-	-	-	-	463.3	3.304.801	713
TOTALS	2,718.0	22,828,449	840	-	-	-	245.7	2,045,859	833	2,963.7	24,874,308	839

	Ар	oendix Tal	ole D 20	003 Wate	er Demano	d by Soil	Texture	with Aver	<mark>age Ma</mark> n	lagemen	t	
Water Source		Surface Water		F	Reclaimed Wate	ər		Groundwater			Total	
Agriculture Soil Texture	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
Clayey Sandy Loam	19.5	105,739	542	-	-	-	33.4	164,564	493	52.9	270,303	511
Loam	624.2	4,265,624	683	-	-		25.2	145,893	579	649.4	4,411,517	679
Loamy Sand	96.9	650,971	672	-	-	-	4.4	28,880	652	101.3	679,851	671
Sand	38.0	319,650	841	-	-	-	1.9	22,298	1,193	39.9	341,948	857
Sandy Loam	506.4	5,223,029	1,031	-	-	-	17.2	187,368	1,092	523.5	5,410,398	1,033
Sandy Loam (defaulted)	936.1	8,298,363	886	-	-	-	161.3	1,484,904	921	1,097.4	9,783,267	891
Silt Loam	496.9	3,965,072	798	-	-	-	2.4	11,952	505	499.2	3,977,024	797
TOTALS	2,718.0	22,828,449	840	-	-	-	245.7	2,045,859	833	2,963.7	24,874,308	839

	Appen	dix Table	E 2003	Water D	emand by	Local G	overnm	ent with A	verage I	Managen	nent	
Water Source		Surface Water		F	Reclaimed Wate	ər		Groundwater			Total	
Local Government	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
Ashcroft	18.5	145,655	788	-	-	-	-	-	-	18.5	145,655	788
Bonaparte	7.8	60,377	777	-	-	-	-	-	-	7.8	60,377	777
Cache Creek	21.0	181,912	867	-	-	-	17.2	179,038	1,041	38.2	360,950	945
Clinton	49.6	330,851	667	-	-	-	4.1	27,172	658	53.7	358,023	667
Thompson-Nicola	2,621.2	22,109,653	844	-	-	-	224.4	1,839,649	820	2,845.6	23,949,302	842
TOTALS	2,718.0	22,828,449	840	-	-	-	245.7	2,045,859	833	2,963.7	24,874,308	839

	A	ppendix	Tab	le F 200	3 Man	ageme	nt Co	mpariso	on on l	rrigatio	n De	mand an	d Perc	olation	Volu	mes	
Water Source	er Surface Water Reclaimed Water						er		Groun	dwater				Tota	al		
Agriculture Management	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Deep Percolation (m³)	Irrigated Area (ha)	Irrigation Demand (m³)	Avg. Req. (mm)	Deep Percolation (m ³)	Irrigated Area (ha)	Irrigation Demand (m³)	Avg. Req. (mm)	Deep Percolation (m ³)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Deep Percolation (m ³)	Percolation (m ³ /ha)
Poor	2,718.0	23,134,961	851	3,860,618	-	-	-	-	245.7	2,065,766	841	260,846	2,963.7	25,200,727	850	4,121,464	1,391
Avg	2,718.0	22,828,449	840	3,554,105	-	-	-	-	245.7	2,045,859	833	240,939	2,963.7	24,874,308	839	3,795,045	1,281
Good	2,718.0	22,521,936	829	3,247,593	-	-	-	-	245.7	2,025,952	825	221,033	2,963.7	24,547,888	828	3,468,626	1,170

	Арр	endix Tab	le G 20	03 Perco	olation Vo	lumes b	y Irrigati	on System	with Av	erage M	anageme	nt	
Water Source		Surface Water		F	Reclaimed Wate	ər		Groundwater			То	tal	
Agriculture Irrigation System	Irrigated Area (ha)	Irrigation Demand (m ³)	Deep Percolation (m ³)	Irrigated Area (ha)	Irrigation Demand (m ³)	Deep Percolation (m ³)	Irrigated Area (ha)	Irrigation Demand (m ³)	Deep Percolation (m ³)	Irrigated Area (ha)	Irrigation Demand (m ³)	Deep Percolation (m ³)	Percolation (m³/ha)
Gun	66.1	613,718	106,982	-	-	-	3.9	42,115	5,790	70.0	655,832	112,772	1,611
Handline	677.2	4,822,307	607,309	-	-	-	94.7	663,656	63,506	771.9	5,485,962	670,815	869
Pivot	429.5	3,446,482	284,092	-	-	-	96.7	867,021	71,770	526.2	4,313,503	355,862	676
PivotLP	0.1	1,034	85	_	-	_	-	-	-	0.1	1,034	85	850
SDI	45.6	303,188	35,595	_	-	_	-	-	-	45.6	303,188	35,595	781
Sprinkler	84.0	545,920	66,584	_	-	_	35.7	292,622	54,161	119.7	838,543	120,745	1,009
Subirria	9.1	57.323	5.931	-	-	-	-	-	_	9.1	57.323	5.931	652
Travoun	340.2	2.538.534	307.756	-	-	-	-	-	-	340.2	2.538.534	307.756	905
Wheelline	463.3	3.304.801	375.014	-	-	-	-	-	-	463.3	3.304.801	375.014	809
TOTALS	2,718.0	22,828,449	3,554,105	-	-	-	245.7	2,045,859	240,939	2,963.7	24,874,308	3,795,045	1,281

	Apper	ndix Table H	2003 Croj	o Water De	emand for	Improved	Irrigation S	System Effic	iency and	Good Manag	ement	
Water Source		Surface Water		R	eclaimed Wa	ter		Groundwater			Total	
Agriculture Crop Group	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
Alfalfa	912.6	6,883,105	754	-	-	-	177.9	1,368,259	769	1,090.6	8,251,365	757
Apple	5.1	21,191	416	-	-	-	-	-	-	5.1	21,191	416
Forage	1,741.5	10,931,164	628	-	-	-	46.5	366,887	789	1,788.0	11,298,051	632
Golf	-	-	-	-	-	-	17.2	175,570	1,021	17.2	175,570	1,021
Recreational Turf	1.3	10,939	824	-	-	-	4.1	26,608	645	5.5	37,547	688
Vegetable	69.2	343,211	496	_	-	-	_	-	-	69.2	343,211	496
TOTALS	2,729.8	18,189,611	666	-	-	-	245.7	1,937,324	788	2,975.5	20,126,935	676

Appendix Table I 2003 Animal Ty	Water Demand by pe
Animal Type	Demand (m ³)
Beef	131,984
Goats	146
Horses	6,789
Poultry – broiler	6
Poultry – laying	3
Sheep	753
TOTALS	139,682

Apper	ndix Table	e J Climat	e Change	e Water E Curi	emand C rent Crop	Circa 205 s and Irri	0 for Higl igation S	h Demanc ystems	l Year wi	th Good M	anagement	Using
Climate Change Model		Irrigated Area Irrigation Avg. Req. Irrigated Irrigation Avg. 1						rcp85			Average	
Year	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
2053	2,963.7	31,849,693	1,075	2,963.7	25,167,235	849	2,963.7	31,642,551	1,068	2,963.7	29,553,160	997
2056	2,963.7	26,442,152	892	2,963.7	30,283,159	1,022	2,963.7	19,740,835	666	2,963.7	25,488,715	860
2059	2,963.7	16,064,221	542	2,963.7	33,564,350	1,133	2,963.7	28,508,879	962	2,963.7	26,045,817	879
Average	2,963.7	24,785,355	836	2,963.7	29,671,581	1,001	2,963.7	26,630,755	899	2,963.7	27,029,231	912

	Ар	pendix Tabl	e K Build	lout Crop	Water Dema	and for 20	03 Climate	e Data with (Good Man	agement		
Water Source		Surface Water		F	Reclaimed Wate	er		Groundwater			Total	
Agriculture Crop Group	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
Alfalfa	1,329.9	9,752,099	733	-	-	-	334.9	2,490,583	744	1,664.7	12,242,682	735
Apple	5.1	21,191	416	-	-	-	-	-	-	5.1	21,191	416
Forage	3,081.2	19,874,596	645	-	-	-	550.3	3,855,460	701	3,631.5	23,730,056	653
Golf	-	-	-	-	-	-	17.2	175,570	1,021	17.2	175,570	1,021
Recreational Turf	1.3	10,939	824	-	-	-	4.1	26,608	645	5.5	37,547	688
Vegetable	69.2	334,835	484	-	-	-	-	-	-	69.2	334,835	484
TOTALS	4,486.7	29,993,660	669	-	-	-	906.5	6,548,221	722	5,393.2	36,541,881	678

Appendi	ix Table	L Buildou	it Crop V	Vater De	mand for	Climate	Change	Data Circa	a 2050 a	nd Good	l Managen	nent
Climate Change Model		rcp26			rcp45			rcp85			Average	
Year	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
2053	5,393.2	46,858,825	869	5,393.2	36,749,010	681	5,393.2	46,210,498	857	5,393.2	43,272,778	802
2056	5,393.2	38,566,580	715	5,393.2	43,838,468	813	5,393.2	29,023,480	538	5,393.2	37,142,843	689
2059	5,393.2	23,760,493	441	5,393.2	48,644,330	902	5,393.2	41,090,260	762	5,393.2	37,831,694	702
Average	5,393.2	36,395,299	675	5,393.2	43,077,269	799	5,393.2	38,774,746	719	5,393.2	39,415,772	731

	Арре	endix Table I	M Buildou	ut Irrigatio	on System D	emand for	2003 Clin	nate Data ar	d Good N	lanageme	nt	
Water Source		Surface Water		F	Reclaimed Wate	r		Groundwater			Total	
Agriculture Irrigation System	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
drip	74.3	356,026	479	-	-	-	-	-	-	74.3	356,026	479
Flood	98.0	1,170,258	1,194	-	-	-	-	-	-	98.0	1,170,258	1,194
Gun	50.8	452,687	891	-	-	-	-	-	-	50.8	452,687	891
Handline	320.5	2,274,315	710	-	-	-	20.2	179,875	890	340.7	2,454,190	720
Pivot	61.6	515,284	837	-	-	-	13.0	121,183	931	74.6	636,466	854
PivotLP	2,840.6	17,424,345	613	-	-	-	665.0	4,608,386	693	3,505.6	22,032,731	629
Sprinkler	808.9	6,069,093	750	-	-	-	208.3	1,638,778	787	1,017.2	7,707,872	758
Subirrig	9.1	56,137	616	-	-	-	-	-	-	9.1	56,137	616
Travgun	72.7	513,964	707	-	-	-	-	-	-	72.7	513,964	707
Wheelline	150.1	1,161,550	774	-	-	-	-	-	-	150.1	1,161,550	774
TOTALS	4,486.7	29,993,660	669	-	-	-	906.5	6,548,221	722	5,393.2	36,541,881	678

	Appendi	x Table N B	uildout De	emand by	Local Gove	ernment f	or 2003 Cl	imate Data a	nd Good	Managemo	ent	
Water Source		Surface Water		R	eclaimed Wate	ər		Groundwater			Total	
Local Government	Irrigated Area (ha) Irrigation Demand (m ³) Avg. Req. (mm) 18.5 126.449 684		Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)	Irrigated Area (ha)	Irrigation Demand (m ³)	Avg. Req. (mm)
Ashcroft	18.5	126,449	684	-	-	-	-	-	-	18.5	126,449	684
Bonaparte	8.5	56,756	669	-	-	-	-	-	-	8.5	56,756	669
Cache Creek	191.9	1,521,034	793	-	-	-	19.6	195,113	995	211.5	1,716,148	811
Clinton	66.4	423,516	637	-	-	-	4.1	26,608	645	70.6	450,124	638
Thompson-Nicola	4,200.8	27,861,581	663	-	-	-	882.7	6,326,500	717	5,083.5	34,188,081	673
TS "KW" Aylaxw First Nation	0.6	4,324	705	-	-	-	-	-	-	0.6	4,324	705
TOTALS	4,486.7	29,993,660	669	-	-	-	906.5	6,548,221	722	5,393.2	36,541,881	678