

Dutch elm disease (DED) is caused by two species of fungi (*Ophiostoma ulmi* and *Ophiostoma novo-ulmi*). It is transmitted from infected trees to healthy trees by at least three species of elm bark beetles. To date, no trees in British Columbia have been found infected with DED. Introduction of this disease would pose a significant threat to both the nursery industry and to landscape plantings of elm in the province. As one of the few areas in the world still free of DED, B.C. exports over 10,000 elm saplings annually.

Hosts

Elms (*Ulmus* spp.) are hosts of DED. American elms are the most susceptible. Siberian, Chinese and other elms are generally resistant but can harbour the disease. *Zelkova carpinifolia*, an ornamental tree in the elm family is also a host.

Distribution

DED is widely distributed around the world, including Western Asia, Europe, Canada (all provinces except B.C. and Alberta), United States, and New Zealand.

Symptoms

Symptoms of the disease first appear in June or early July. Leaves wilt, yellow and turn brown in the summer, often on one side of the tree (Figures 1, 2 & 3). This is followed by dieback of branches and eventual death of the tree. Brown staining can be seen in the sapwood of affected branches by peeling back the bark (Figure 4).



Figure 1. Flagging branches of an infected elm tree. Photo credit: Dr. Gary Platford, Winnipeg, Manitoba.



Figure 2. Branch dieback. Photo credit: Manitoba Agriculture, Food & Rural Initiatives.



Figure 3. Dieback and flagging caused by Dutch elm disease. Photo credit: Dr. Gary Platford, Winnipeg, Manitoba.



Figure 4. Vascular discoloration under bark of infected elm branch. Photo credit: Saskatchewan Environment.

Life Cycle

DED is transmitted from infected trees to healthy trees by the European elm bark beetle, *Scolytus multistriatus*, (Figure 5) an introduced species which is present throughout Southern B.C. It can also be spread by the native elm bark beetle (*Hylurgopinus rufipes*) which is common in Eastern and Central Canada, but is not known to occur in B.C. DED may also be spread by the banded elm bark beetle (*Scolytus schevyrewi*), which was first detected in B.C. near Kelowna in 2010.

The beetles breed in weakened trees in galleries constructed under the bark (Figure 6). Galleries excavated by adult European elm bark beetles are parallel with the wood grain, a feature that can be used to distinguish this species from the native elm bark beetle.

In infected trees, the beetle galleries become colonized by the Dutch elm disease fungus. In the spring, a new generation of beetles emerge which spread fungal spores to healthy elm trees as they feed on branches. Beetle feeding introduces the fungus to the vascular tissue where the fungus colonizes and clogs xylem vessels causing a vascular wilt. The disease can also spread by natural root grafting to adjacent trees.

Long distance spread usually occurs through movement of infested elm firewood or logs. Movement of infected elm nursery stock could also introduce the disease to new areas.

Prevention

If planting elm trees, obtain nursery stock only from a local, reliable source.

A voluntary elm bark beetle management program has been developed to assist nurseries to prevent beetles from feeding and potentially transmitting DED to nursery plantings.

Early detection is the most important step to prevent the spread of this disease. If you spot symptoms of DED, contact the provincial [Plant Health Laboratory](#) for instructions on submitting a sample.

Many landscape and forest pests can be spread in firewood. Never transport elm wood or wood products with bark to new locations. Leave your fire wood at home and pick up local wood when camping. Don't take extra fire wood home with you.



Figure 5. Smaller European Elm Bark Beetle. Photo credit: Thérèse Arcand, Natural Resources Canada, Canadian Forest Service



Figure 6. Left trunk: native elm bark beetle galleries; right trunk: smaller European elm bark beetle galleries. Photo credit: Natural Resources Canada, Canadian Forest Service

For Further Information

- [Canadian Food Inspection Agency Policy Directive D-97-07, Policy on Domestic Movement of Elm Material to Prevent the Spread of Dutch Elm Disease within Canada](#)
- [Alberta's Society to Prevent Dutch Elm Disease \(STOPDED\)](#)