

PROVINCE OF BRITISH COLUMBIA
REGULATION OF THE MINISTER OF PUBLIC SAFETY AND
SOLICITOR GENERAL AND MINISTER RESPONSIBLE FOR HOUSING


Local Government Act

Ministerial Order No.

M 021


I, Rich Coleman, Minister of Public Safety and Solicitor General and Minister Responsible for Housing, order that B.C. Reg. 95/2010, as amended by B.C. Reg. 289/2010, is further amended by striking out everything after "order that" and before the Schedule and substituting the following:

- (a) effective October 3, 2011, the British Columbia Building Code Regulation, BC Reg. 216/2006, is amended as set out in the attached Schedule, and
- (b) an applicant for a building permit referred to in Part 21 of the *Local Government Act* or Part 2 of the *Community Charter* is exempt from the amendments set out in the attached Schedule in respect of a building permit application submitted before October 3, 2011.



JAN 31 2011

Date


Minister of Public Safety and
Solicitor General and
Minister Responsible for Housing

(This part is for administrative purposes only and is not part of the Order.)

Authority under which Order is made:

Act and section: *Local Government Act*, R.S.B.C. 1996, c. 323, section 692

Other: M105/2010, M275/2010

January 19, 2011

R 29/2011/33


PROVINCE OF BRITISH COLUMBIA

REGULATION OF THE MINISTER OF HOUSING AND SOCIAL DEVELOPMENT

Local Government Act

Ministerial Order No. M 275

I, Rich Coleman, Minister of Housing and Social Development, order that B.C. Reg. 95/2010 is amended by striking out "October 4, 2010," and substituting "October 3, 2011,".



SEP 30 2010

Date

A handwritten signature in black ink, appearing to be "Rich Coleman".

Minister of Housing and Social Development

(This part is for administrative purposes only and is not part of the Order.)

Authority under which Order is made:

Act and section:- *Local Government Act*, R.S.B.C. 1996, c. 323, s. 692
Other (specify):- M166/2006

September 30, 2010


PROVINCE OF BRITISH COLUMBIA

REGULATION OF THE MINISTER OF HOUSING AND SOCIAL DEVELOPMENT

Local Government Act

Ministerial Order No. M 105

I, Rich Coleman, Minister of Housing and Social Development, order that, effective October 4, 2010, the British Columbia Building Code Regulation, B.C. Reg. 216/2006, is amended as set out in the attached Schedule.



APR 01 2010

Date

A handwritten signature in black ink, appearing to be "Rich Coleman".

Minister of Housing and Social Development

(This part is for administrative purposes only and is not part of the Order.)

Authority under which Order is made:

Act and section:- *Local Government Act*, R.S.B.C. 1996, c. 323, s. 692
Other (specify):- M166/2006

SCHEDULE

1 The British Columbia Building Code Regulation, B.C. Reg. 216/2006, is amended in Division B of Part 10 by repealing Article 10.3.1.2. and substituting the following:

10.3.1.2. Fixture Efficiency

- 1) Except as required by Sentence (2), the flush cycle for the installation of a water closet or urinal must not exceed the flush cycle listed for that fixture in Table 10.3.1.2 (1).

Table 10.3.1.2. (1) Maximum Flush Cycle Forming Part of Sentence 10.3.1.2. (1)	
Fixture	L
Water Closet (Tank Type)	6.0
Water Closet (Direct Flush)	6.0
Urinal (Tank Type)	1.9
Urinal (Direct Flush)	1.9

- 2) The flush cycle for the installation of a water closet or urinal in buildings classified as Group C must not exceed the flush cycle listed for that fixture in Table 10.3.1.2 (2).

Table 10.3.1.2. (2) Maximum Flush Cycle Forming Part of Sentence 10.3.1.2. (2)	
Fixture	L
Water Closet (Tank Type)	4.8 ⁽¹⁾
Water Closet (Direct Flush)	4.8
Urinal (Tank Type)	1.9
Urinal (Direct Flush)	1.9

- 3) The water supply to urinal flush tanks equipped for automatic flushing shall be controlled with a timing device in order to limit operation to the period during which the building is normally occupied.

Notes to Table 10.3.1.2. (2)

⁽¹⁾ A water closet which provides a dual flush cycle option of both 4.1 L or less and 6.0 L shall be deemed to comply.