



BCTS RECOMMENDED SEEDLING STOCK TYPE SELECTION GUIDELINE INTERIOR SUMMER

Bl	Stock Type	Ht (cm)	Min RCD (mm)	Cost \$	Est. # Box
Medium	PSB 410 2+0	8 - 36	2.6	0.36	315
Large	PSB 412A 2+0	10 - 36	3.1	0.49	210

Fdi	Stock Type	Ht (cm)	Min RCD (mm)	Cost \$	Est. # Box
Small	PSB 412B 1+0	13 - 34	2.2	0.42	315
<ul style="list-style-type: none"> Do not recommended for summer stock, root development on Fdi is very poor and may not be ready for Summer lift 					

Lw	Stock Type	Ht (cm)	Min RCD (mm)	Cost \$	Est. # Box
Small	PSB 410 1+0	12-34	2.4	0.26	315
<ul style="list-style-type: none"> Do not recommended for summer stock, root development on Lw is very poor and may not be ready for Summer lift 					

Pli	Stock Type	Ht (cm)	Min RCD (mm)	Cost \$	Est. # Box
Medium	PSB 410 1+0	6 - 23	2.2	0.35	315

Sx	Stock Type	Ht (cm)	Min RCD (mm)	Cost \$	Est. # Box
Small	PSB 410/412B 1+0	11- 32	2.2	0.35	315
Medium	PSB 412A 1+0	11 - 42	2.6	0.47	210

*If you are ordering 2+0 Bl, please do not order 2+0 Sx as the mix, order Sx 1+0 the following year to combine with Bl.

Cw is not recommended and will not have good enough roots to be planted in the summer.

	Most ordered stock type for species.
Call Seedling Services staff for other options or advice. Alan Rasmussen (250)838-2856, Scott Ruzyllo (250) 649 -2815	

For summer stock, the planting date you enter into SPAR is the date the nurseries plan the seedlings to be ready for. Please ensure this date will work for your area, the planting contractor, and the contract coordinator before approving the request. Do not use July 4th or earlier. It is recommended to plant Spring Stock wherever possible due to the drought conditions and survivability.

Cost based on 2025 tenders, this includes admin, transport, storage, seed and growing cost.