

Damage Reports

4

Whenever the codes for Blowdown, Fire and/or Insect damage are detected on card type 2s, damage reports are produced in addition to the normal (non-damage related) output. These reports will segregate the reported volumes into separate damage types and/or codes, as indicated. Root rot damage is reported for block summaries only and is optional.

The damage reports will be the same as the normal output, only there will be a designation of species and damage type and damage codes on the report.

Damage Type	Code	Description	Species
Blowdown	E	Down trees	All Species
	G	Down and shattered trees	All Species
Fire	A	Light fire	All Species
	B	Medium fire	All Species
	C	Heavy fire	All Species
Insect/Disease	1	Green attack	Balsam, Pine
	2	Red attack	Balsam, Pine
	3	Grey attack	Balsam, Pine
	4	Blister rust	White Pine
	5	Green attack - alive	Spruce, Douglas Fir
	6	Green attack - dead	Spruce, Douglas Fir
	7	Grey attack - dead	Spruce, Douglas Fir

Damage Type	Code	Description	Species
	8	Red attack	Douglas Fir
	X	Defoliator G live cambium	All Species
	Y	Defoliator D dead cambium	All Species
Root Rot	J	Light	All Species
	K	Moderate	All Species
	L	Heavy	All Species

4.1 List of Damage Reports

The following damage reports are required for damage types Blowdown, Fire, and Insect:

1. 006 Extended Forest Type Stand and Stock Table, one page with all trees, one page with non-damaged trees, and one page for each Blowdown, Fire, or Insect damage code.
2. 007 Stand and Stock Tables, one page for each species and damage type containing each of the damage codes for that damage type.
 - i 007a Block Stand Table.
 - ii 007b Block Stock Table.
 - iii 007c Block Basal Area.
 - iv 007d Timber Type Stand Table.
 - v 007e Timber Type Stock Table.
 - vi 007f Timber Type Basal Area.
 - vii 007g Cutting Permit Stand Table.
 - viii 007h Cutting Permit Stock Table.
 - ix 007i Cutting Permit Basal Area.
3. 009 Volume Summaries, one page for each species and damage type reporting each of the damage codes for that damage type.
 - i 009a Timber Type Summary.
 - ii 009b Block Summary.
 - iii 009c Cutting Permit Summary.
 - iv 009d Treatment Unit within Block Summary - Coast only.
4. 011 Plot Summary, damage code volumes segregated for each species.
5. 015 Harvesting Method Summary, percent net volumes will be segregated for each Harvesting Method under the headings Fire, Heavy Fire (Damage code C), Down trees, and Insect damage.

The following damage reports are optional:

1. 009b Root Rot Block Summary.

4.2 Damage Report Calculation

Trees with multiple damage codes will report each damage type in the *Damage Summary Reports*. The damage code or codes that will assign the highest risk group will be used in the calculation of the net volume for each of the damage types. If pathological indicator(s) move the risk group higher than the damage code(s) then use the risk group from the pathological indicator(s) to calculate the *Damage Summary Reports*.

Example

Cruise = 1 ha, 1 plot, 1.0 m³ mature Lodgepole Pine tree that represents 100 stems/ha with down tree code G, fire code B and insect 3:

Risk groups (RG) -Down Tree = RG3, Fire = RG2, Insect 3 = RG 2. Use RG 3 since it is the highest risk group.

Volume - Hypothetical loss factor DWB = 30% plus 20% for the grey attack breakage add-on = 50%.

Tree = 1.0 m³ - 0.5 m³. Cruise volume per hectare = 0.5 * 100 stems = 50 m³.

Damage reports -Type, Block and Cutting Permit Damage Report Net Volume = 50 m³ for Lodgepole pine Down Tree (G), Fire (B) and Insect (3).

4.3 Sample Damage Report Listings

Some of the DBH classes have been removed from these sample listing.

4.3.1 Extended Forest Type Stand and Stock Damage Report - Sample Listing

FOREST REVENUE BRANCH - 2001.0 FOREST TYPE STAND AND STOCK TABLE (STEMS/HA) NOT FOR APPRAISAL PURPOSES DUE TO NON-STANDARD UTILIZATION **** DOUBLE SAMPLING CRUISE **** NOTE - ALL TREES GREATER THAN 275 CM ARE INCLUDED IN THE 275 CM CLASS LICENCE NUMBER CF7080 TYPE 1 - PA H C 9 4 1 SPECIES CEDAR CUTTING PERMIT 000 ROAD/LANDINGS AREA - 5.0 OTHER AREA - 0.0 NO. OF PLOTS (M/C) 3. 3. NO. OF LIVE TREES 1. NO. OF DEAD TREES 0.										
(006) PAGE 4 COMPUTED 2001-03-19 17:42:54 AVERAGE LINE USELESS VOLUMES EXCLUDED										
DOWN & SHATTERED - UPROOTED DAMAGE										
LIVING TREES										
DBH	HT	GROSS	MESH	NET	RISK	RISK	RISK	RISK	POTENTIAL	TOTAL
CM	(M)	PER TREE	PER TREE	(M3)	GROUP 0	GROUP 1	GROUP 2	GROUP 3	DEAD	LIVE
									VETERANS	DEAD U LIVE U
40										
45										
50										
55	37.5	2.807		1.348			10.33			10.33
60										
65										
70										
75										
80										
85										
90										
TOTAL OF AVERAGES +										
PERCENT BY TREE CLASS										
TREES 12.5 +										
TREES 17.5 +										
TREES 22.5 +										
TREES 27.5 +										
TREES 32.5 +										
10.33										
100.00										
100.00										
55.50										
55.50										
55.50										
55.50										
55.50										

Figure 4.1 Extended Forest Type Stand and Stock Damage Report - Sample Listing (Partial).

4.3.2 Block Stand Damage Table - Sample Listing

FOREST REVENUE BRANCH - 2001.0 NOT FOR APPRAISAL PURPOSES DUE TO NON-STANDARD UTILIZATION		BLOCK STAND TABLE (STEMS/HA)		(007A) PAGE 42		
LICENCE NO. CF7080		**** DOUBLE SAMPLING CRUISE ****		COMPUTED 2001-03-19 17:42:55		
CP NO. 000		TOTAL MERCH AREA 12.5		INSECT DAMAGE		
BLOCK 001		AVERAGE LINE		USELESS VOLUMES EXCLUDED		
CLEARCUT 5.0 SELECTIVE		BALSAM - INSECT DAMAGE		TOTAL		
		RED ATTACK	GRAY ATTACK	DEFOL - GRN	DEFOL - GRY	
MIN DBH	NORMAL GREEN ATTACK					
20	12.5					
25	30.0					
30	10.0					
35	5.0					
40						
45	12.3	29.9	18.9			29.9
50			9.1			31.2
55						9.1
60						
65						
70						
75						
80						
85						
90						
95						
TOTAL	12.3	57.9				70.2
USELRS						
DEAD P						
12.5 +	41.5	AVERAGE DBH (CM) AT 5 LEVELS				39.6
17.5 +	41.5	39.2				39.6
22.5 +	41.5	39.2				39.6
27.5 +	41.5	39.2				39.6
32.5 +	41.5	39.2				39.6

Figure 4.2 Block Stand Damage Table - Sample Listing (Partial).

4.3.3 Block Volume Summary Damage Report - Sample Listing

FOREST REVENUE BRANCH - 2001.0		BLOCK SUMMARY	
NOT FOR APPRAISAL PURPOSES DUE TO NON-STANDARD UTILIZATION **** DOUBLE SAMPLING CRUISE ****		(009B) PAGE 51	COMPUTED 2001-03-19 17:42:57
		AVERAGE LINE	
LICENCE NUMBER CF7080	P.S.Y.U. 34-0	NO. OF BLOCKS	2
CUTTING PERMIT 000	F.I.Z. J	USELESS VOLUMES EXCLUDED	6
BLOCK NUMBER 001		NO. OF PLOTS USED (M/C)	6
CLEARCUT	5.0 SELECTIVE	TOTAL MERCH AREA	12.5
UTILIZATION	NORMAL	ALBUCAULIS PINE - UPROOTED DAMAGE	
COMPILE TYPE	3	SHATTERED	TOTAL
MINIMUM DBH	12.5		
STUMP HEIGHT	30.0		
TOP DIAMETER	10.0		
LOG LENGTH	5.0		
VOLUME AND SIZE DATA			
GROSS MERCH VOLUME M3	1200.		1742.
NET MERCH VOLUME M3	1026.		1484.
NET MERCH./HECTARE M3	205.		297.
% DISTRIBUTION/HECTARE	69.		100.
DECAY % GROSS	9.		9.
WASTE % GROSS	3.		3.
WASTE (BILLING) % NET	4.		4.
BREAVAGE % GROSS	2.		2.
TOTAL CULL (DWB) % GROSS	15.		15.
STEMS/HA (GREEN & DP)	82.9		46.6
SNAGS/HA (DU)	12.3		0.0
AVG. DBH (GREENDP) CM	0.4		0.5
AVG. DBH (SNAGS) CM	0.6		0.0
GROSS MERCH VOL/TREE M3	2.91		2.50
NET MERCH VOL/TREE M3	2.49		2.13
AVG. WEIGHT TOTAL HT M	0.0		0.1
AVG. WEIGHT MERCH HT M	0.0		0.0
AVG. 5M LOG NET MER M3	0.48		0.44
AVG. # OF 5M LOGS/TREE	5.34		5.00
LUMBER AND CHIPS			
% NET MERCH - STUD LOG	20		20
% NET MERCH - SMALL LOG	80		48
% NET MERCH - LARGE LOG	10		52
LRF SMALL LOGS BD FT/M3	3		4
LRF LARGE LOGS BD FT/M3	2		3
AVG LRF BD FT/M3	.26		.27
CHIP YIELD UNITS/M3			
ALGORITHM GRADE #			
#1 SAWLOG	63.		55.
#3 SAWLOG	10.		27.
#4 CHIPPER	27.		6.
#5 CHIPPER	0.		18.

Figure 4.3 Block Volume Summary Damage Report - Sample Listing.