

Aggregate and Quarry Materials

Click [here](#) for Sample Site Plan Map

The **Aggregate Site Plan** must include:

1. Scale e.g. 1:100 – 1:5,000
2. North arrow
3. The outer boundary of the proposed application area in relation to other legal boundaries, with lengths/dimensions and a point of commencement identified as latitude/longitude or UTM coordinate
4. All proposed and existing [improvements](#) (e.g. buildings, structures, roads, powerlines, fences, gates, etc.) where it is clear which are proposed and which are existing. All improvements must be labeled or listed in a legend, must include coordinates and must show lengths/dimensions
5. Existing man-made or natural [features](#) within and directly surrounding the application area (e.g. waterbody, present natural boundary, height of land, contour lines where possible etc.)
6. Lengths/dimensions of the open pit (meters), lengths/dimensions of cleared area around pit for re-contouring (meters)
7. Overburden stockpile location (meters) and product stockpile location (meters)
8. Access road location and area (ha) and total area of disturbance (ha)

If relevant, also include:

9. Areas to be developed by year
10. Pit drainage, reclamation area by year
11. Crushing, washing, screening, material sorting areas
12. Timber edge(s), culverts/drains, temporary portable asphalt plant