

Unit 20. Tribune South [click here for a detailed map](#)

Marine Area	1966 ha	Shoreline	33.0 km
Substrate	mud	Slope	sloping
Exposure	low	Depth	mid-depth
Current	low	Benthic Summer Temp	warm
Roughness	moderate		

Management Emphasis – General Marine

Description

The unit comprises steep-sided channels with limited beach area. Most uses are concentrated near Sargeant Pass.

Unit Attributes

Heavy eelgrass, kelp in Sargeant Pass

Salmon holding area; juvenile salmon rearing area; salmon migration route to Kakweiken, Thompson and Glendale, especially Pink salmon (local knowledge)

Salmon stream north of log dump in Sargeant Pass (local knowledge)

Eelgrass throughout Sargeant Pass (local knowledge)

Orca summer resting, winter feeding area: Resident and West Coast transient populations are listed as threatened nationally (T), and imperiled provincially (S2). They are provincially red-listed.

Harbour Porpoise area: provincially blue-listed species

High prawn values

Finfish aquaculture potential: OA 1 (throughout)

Good off bottom scallop and oyster capability (Sargeant Passage)

Forest industry has identified potential log dump sites along west shore of Tribune Channel opposite Viscount Island

Mamalilikula traditional territory

Current Uses & Activities

First Nations: Shellfish harvest area within Sargeant Passage. Crab and prawn harvesting area.

Culturally significant areas towards Tribune Channel entrance.

Log handling and storage (1), heli-log sites, heli-spot sites

Salmon farms (2); 1 contingent upon final DFO approval

Safe anchorages in Sargeant Pass

Commercial crab, prawn, salmon fisheries

Acceptable Uses & Activities

Tenured Uses

- | | |
|---|--|
| <input checked="" type="checkbox"/> Community & Public Institutional | <input checked="" type="checkbox"/> Conservation |
| <input checked="" type="checkbox"/> Light Industrial | <input checked="" type="checkbox"/> Log Handling, Storage & Infrastructure |
| <input checked="" type="checkbox"/> Marine Telecommunications & Utilities | <input checked="" type="checkbox"/> Private Moorage |
| <input checked="" type="checkbox"/> Rural Development | <input checked="" type="checkbox"/> General Commercial |

Aquaculture:

- Finfish
- Marine Plant
- Shellfish Beach
- Shellfish Deep Water Aquaculture

Commercial Recreation:

- Lodges and Base Camps
- Guiding Operations

Ongoing Non Tenured Activities

- | | |
|---|---|
| <input checked="" type="checkbox"/> Commercial Fisheries | <input checked="" type="checkbox"/> First Nations |
| <input checked="" type="checkbox"/> Marine Transportation | <input checked="" type="checkbox"/> Public Recreation |

Code	
<input checked="" type="checkbox"/>	The use or activity is considered acceptable and appropriate. Applications for tenure of this use should be accepted for processing and evaluation.
<input type="checkbox"/>	The use is considered conditionally acceptable. Applications for tenure for use require more specific information on capability and potential to accompany a tenure application before it is accepted for processing.
<input type="checkbox"/>	The use is acceptable at existing levels of tenure, subject to limited modifications as required by government. Applications for new tenures should not be accepted. Abandoned or unutilized sites should not subsequently be made available for the same use.
<input checked="" type="checkbox"/>	The use is considered inappropriate. Applications for tenure of this use should not be accepted for processing and evaluation.

Management Provisions

This unit should be managed to maintain the existing range of opportunities and promote compatible new tenures where appropriate.

New tenures should not impede safe anchorage at Sargeaunt Passage.

New tenures should not alienate recorded commercial dive fishery sites.

Shellfish deepwater aquaculture tenures should not infringe on existing recreational, commercial and First Nations fisheries.