

Unit 21. Tribune East [click here for a detailed map](#)

Marine Area	3510 ha	Shoreline	39.2 km
Substrate	mud	Slope	sloping
Exposure	low	Depth	mid-depth
Current	low	Benthic Summer Temp	warm
Roughness	moderate		

Management Emphasis - General Marine

Description

The unit is a long passage with few significant biological features, limited shoreline and poor access to upland.

Unit Attributes

- Herring spawn (1 recorded: at mouth of Thompson Sound)
- Clam beds throughout inside of Kumlah Island (local knowledge)
- Orca summer resting, winter feeding area: Resident and West Coast transient populations are listed as threatened nationally (T), and imperiled provincially (S2). They are provincially red-listed.
- Minke whale summer feeding area
- High value prawn, moderate invertebrate values
- Carter Creek and 5 other streams known to have salmon (local knowledge)
- Juvenile and adult salmon holding area, migration route
- Small estuary east of Viscount Island
- Parks/protection areas north and south of Sargeant Pass
- Eelgrass throughout unit (local knowledge)
- Finfish aquaculture potential throughout (OA1)
- Forest industry has identified potential log dump sites along east & west shores north of Thompson Sound, east shore south of Thompson Sound
- Kwicksutaineuk/Ah'K'waha' traditional territory
- Indian Reserve at Kumlah

Current Uses & Activities

- First Nations: Fishing and cultural areas along Gilford Island; pictographs opposite Brown Point, sensitive to disturbance.
- Marine transportation activities
- Boat anchorage inside of Kumlah Island (local knowledge)
- Commercial prawn/shrimp, crab, salmon fisheries
- Sport salmon, ground fishery, prawn, shrimp, crab fisheries
- Log handling and storage (2), heli-log sites, camp tie-ups
- Year round commercial tenure (1)

Acceptable Uses & Activities

Tenured Uses

- | | |
|---|--|
| <input checked="" type="checkbox"/> Community & Public Institutional | <input checked="" type="checkbox"/> Conservation |
| <input checked="" type="checkbox"/> Light Industrial | <input checked="" type="checkbox"/> Log Handling, Storage & Infrastructure |
| <input checked="" type="checkbox"/> Marine Telecommunications & Utilities | <input checked="" type="checkbox"/> Private Moorage |
| <input checked="" type="checkbox"/> Rural Development | <input checked="" type="checkbox"/> General Commercial |

Aquaculture:

- Finfish
- Marine Plant
- Shellfish Beach
- Shellfish Deep Water Aquaculture

Commercial Recreation:

- Lodges and Base Camps
- Guiding Operations

Ongoing Non Tenured Activities

- | | |
|---|---|
| <input checked="" type="checkbox"/> Commercial Fisheries | <input checked="" type="checkbox"/> First Nations |
| <input checked="" type="checkbox"/> Marine Transportation | <input checked="" type="checkbox"/> Public Recreation |

Code
<input checked="" type="checkbox"/> The use or activity is considered acceptable and appropriate. Applications for tenure of this use should be accepted for processing and evaluation.
<input type="checkbox"/> The use is considered conditionally acceptable. Applications for tenure for use require more specific information on capability and potential to accompany a tenure application before it is accepted for processing.
<input type="checkbox"/> The use is acceptable at existing levels of tenure, subject to limited modifications as required by government. Applications for new tenures should not be accepted. Abandoned or unutilized sites should not subsequently be made available for the same use.
<input checked="" type="checkbox"/> The use is considered inappropriate. Applications for tenure of this use should not be accepted for processing and evaluation.

Management Provisions

This unit should be managed to maintain general activities and accommodate new development where appropriate.

New tenures should not alienate recorded commercial dive fishery sites.