



File: ORCS 17580-30/Rogers

**ORDER TO ESTABLISH
A LANDSCAPE UNIT AND OBJECTIVES**

ROGERS LANDSCAPE UNIT

Pursuant to Section 4 of the *Forest Practices Code of British Columbia Act*, I hereby establish the Rogers Landscape Unit, an area located east of the Lillooet River, Squamish Forest District, effective April 14, 2004.

The boundaries of the Rogers Landscape Unit are shown on the 1:50,000 scale map, dated March 10, 2004, attached to this Order.

In addition, I hereby establish objectives for the Rogers Landscape Unit, as attached to this Order, effective April 14, 2004.

(Original signed by)

**Regional Director, Coast Region,
Ministry of Sustainable Resource Management**

Date

Preamble

The goal of these objectives is to sustain biological diversity at the landscape level; permissible activities are described to streamline administrative procedures and address operational safety concerns.

First Nations traditional use of forest resources, treaty negotiations or settlements will not be limited by the following objectives.

Legal Objectives - Rogers Landscape Unit

Pursuant to Section 4 of the *Forest Practices Code of British Columbia Act*, the following are landscape unit objectives for the Rogers Landscape Unit.

Objective 1

1. Maintain or recruit old growth forests in established old growth management areas (OGMAs), as shown on the attached Rogers Landscape Unit map dated March 10, 2004 subject to timber harvesting and road construction in accordance with section 2, 3 and 4 below.
 2. (1) Where sufficient suitable replacement forest is available in the variants listed below, timber harvesting or road construction may be undertaken in OGMAs that are >10 ha in size for operational reasons up to a cumulative maximum of:
 - i) 30 ha in variant CWHds1,
 - ii) 60 ha in variant CWHms1,
 - iii) 10 ha in variant IDFww, and
 - iv) 60 ha in variant MHmm2,provided that replacement OGMA of equivalent or better quality and quantity is identified in order of priority, 1) immediately adjacent to the existing OGMA, or 2) in the same variant and landscape unit as the existing OGMA.
 - (2) The criteria in 2 (1) is to apply to individual OGMAs within the categories below and must ensure that OGMA ecological attributes and spatial distribution are maintained or improved:
 - i) OGMAs >10 ha to <50 ha in size where the proposed activity affects the OGMA by <5 ha,
 - ii) OGMAs ≥50 ha to <100 ha in size where the proposed activity affects the OGMA by <10ha,
 - iii) OGMAs ≥100 ha in size where the proposed activity affects the OGMA by <10%.
 - iv) Construction of ≤500m of road or a bridge within an OGMA where there is no other practicable option. As an alternative to finding replacement area, the licensee may permanently deactivate and rehabilitate a temporary road or bridge site within four years after construction.
 - (3) Where OGMA boundary adjustments and replacement areas are required under section 2 (1) and (2) they must be documented, mapped and submitted to the satisfaction of the Delegated Decision Maker (DDM) at the end of each calendar year for his/her approval.
 - (4) The provisions in section 2 (1) and (2) do not apply to the following OGMAs #2, 3, 4, 7, 48, 54, 55, 78, 87, 89, 92, 94, 118, 143, 172, 186, 196.
3. Permissible Activities:

- (1) Timber harvest may occur to prevent the spread of insect infestations or diseases that pose a significant threat to forested areas outside of OGMA. Salvage within OGMA will be done in a manner that retains as many old growth forest attributes as possible.
 - (2) Construction of rock quarries and gravel pits under authority of forest tenure where the development will be located immediately adjacent to existing roads under tenure and will affect the OGMA by <0.5 ha.
 - (3) Intrusions, other than those specified, that affect an OGMA by less than 0.5 hectare in total.
 - (4) Where OGMA replacement forest is required as a result of activities under 3 (1) or (2), it must be of equivalent or better quality and quantity and be identified in order of priority, 1) immediately adjacent to the existing OGMA, or 2) in the same variant and landscape unit as the existing OGMA; such that OGMA ecological attributes and spatial distribution are maintained or improved. OGMA replacement areas must be documented, mapped and submitted to the satisfaction of the DDM at the end of each calendar year for his/her approval.
4. Permissible Activities for Safety Purposes:
- (1) Maintenance, deactivation, removal of danger trees, or brushing and clearing on existing roads under active tenure within the right-of-way for safety purposes.
 - (2) Felling of guyline clearance, tailhold anchor trees, or danger trees (except high value wildlife trees) along cutblock boundaries or within the right of way on new road/bridge alignments to meet safety requirements.


Objective 2

Maintain stand level structural diversity by retaining wildlife tree patches (WTP). Cutblocks for which harvesting has been completed by each licensee by tenure will retain adequate amounts of wildlife tree patches to ensure that over each 3 year period, commencing on the date the objectives are established, the target percentage as noted in Table A is achieved. In addition:

- (1) WTPs must be well distributed across the BEC subzone and located within or immediately adjacent to a cutblock.
- (2) Each cutblock >10 ha in size must have a minimum of 2% wildlife tree retention.
- (3) No timber harvesting, including single tree selection, is to occur within WTPs for at least one rotation, except as noted in (4) below.
- (4) Salvage of windthrown timber and harvesting of remaining standing stems is only permitted within WTPs where catastrophic windthrow exceeds 50% of the dominant or co-dominant stems; or where forest health issues pose a significant threat to areas outside the WTP. Where salvage/harvesting is planned and authorized, replacement WTP of equivalent or better quality and quantity must be identified immediately to achieve the retention target.
- (5) WTPs must include, if present, remnant old growth patches and live or dead veteran trees (excluding danger trees).
- (6) WTPs must include representative larger trees for the stand and any moderate to high value wildlife trees (excluding danger trees).
- (7) Where differences exist between mapped and actual BEC subzones, subzones will be confirmed by site plan information.

Table A. Wildlife Tree Retention by BEC subzone in the Rogers Landscape Unit.

BEC Subzone	% Wildlife Tree Retention
CWH ds (Coastal Western Hemlock, dry subarctic)	9
CWH ms (Coastal Western Hemlock, moist subarctic)	6
IDF ww (Interior Douglas Fir, wet warm subzone)	5
MH mm (Mountain Hemlock, moist maritime)	2



Rogers Landscape Unit


Ministry of Sustainable Resource Management

- Landscape Unit Boundary
- Biogeoclimatic Ecosystem Boundary
- Protected Area
- Roads
- Water
- 20m Contours
- Lake
- River
- Swamp

OLD SERAL REPRESENTATION AREAS

- OLD GROWTH MANAGEMENT AREAS

Scale 1: 50 000



Projection/Datum: Albers / Nad 83
 Forest Cover: MOF FC1 1: 20 000
 Digital Mapping Base: TRIM 1: 20 000
 Contour Interval: 20 meters

Submitted by: LS_GG_MSRM

Date: March 10, 2004

Amendment: _____

Mapped by LS_GG March 10, 2004

Date: _____