

Sec. 4(6) Matrix Site Series Groups

For use in applying matrix site series groups target flexibility in the Thurlow, Fulmore, Gray and Estero landscape units.

Within each of the two tables below, the 5% combined target area flexibility for any site series group in the Thurlow, Fulmore, Gray and Estero landscape units can be met in any other Biogeoclimatic variant and site series group of the same or higher level in those four landscape units. This flexibility only occurs within each individual table; the 5% combined target area flexibility does not apply between the submontane and montane tables.

The intent is that target flexibility for lower productivity site series surrogates is applied only to equal or higher productivity site series surrogates. For the purposes of the land use order objectives productivity must at minimum be air photo interpretation verified.

Submontane table

| Variant | Level 1 SSG | Level 2 SSG | Level 3 SSG |
|---------|-------------|-------------|-------------|
| CWHxm2 | N/A | 01/03, 06 | 05/07 |
| CWHdm | N/A | 01/03, 06 | 05/07 |
| CWHmm1 | 03 | 01/06 | 05/07 |
| CWHvm1 | 03 | 01/06 | 05/07/08 |

Montane table

| Variant | Level 1 SSG | Level 2 SSG | Level 3 SSG |
|---------|-------------|-------------|-------------|
| CWHmm2 | 03 | 01 | N/A |
| CWHvm2 | 03 | 01/06 | 05/07/08 |