


Tridem Drive Configuration




Allowable Dimensions (m)	Tridem Drive
Tractor Wheelbase (WB-1)	6.6 - 6.8
Drive group spread (AS-1)	2.6 - 2.8
Trailer tridem group spread (AS-2)	2.7 - 3.1
Trailer tandem group spread (AS-3)	1.3 - 1.6
Axle spacing: drives to lead trailer (AS-4)	6.0 - 6.5
Axle spacing: lead to rear trailer (AS-5)	6.0 - 6.6

- Overall Length 27.5 m
- Overall Width 2.9 m
- Steer axle – 7 300 kg maximum
- Drive axle – 24 000 kg maximum
- 1st trailer axle unit- 24 000 kg maximum
- 2nd trailer axle unit- 17 000 kg maximum
- GCVW – 72 300KG maximum

No other additional dimensional allowances permitted. Axle weights must be legal with no logging allowances for overweight trucks. GCVW and axle weights are subject to posted bridge and seasonal load restrictions.

Tandem Drive Configuration



Allowable Dimensions (m)	Tridem Drive
Tractor Wheelbase (WB-1)	5.7 - 6.2
Drive group spread (AS-1)	1.3 - 1.55
Trailer tridem group spread (AS-2)	2.7 - 3.1
Trailer tandem group spread (AS-3)	NA
Axle spacing: drives to lead trailer (AS-4)	6.2 - 6.8
Axle spacing: lead to rear trailer (AS-5)	6.0 - 6.5

- OAL 27.5 m
- OAW 2.9 m
- Steer axle – 6 000 kg maximum
- Drive axle – 17 000 kg maximum
- 1st trailer axle unit- 24 000 kg maximum
- 2nd trailer axle unit- 24 000 kg maximum
- GCVW – 71 000KG maximum

No other additional dimensional allowances permitted. Axle weights must be legal with no logging allowances for overweight trucks. GCVW and axle weights are subject to posted bridge and seasonal load restrictions.