

Appendix – RR Channel Assignment Limitations

The following table denotes geographic limitations for use of various RR Channels as provided by Innovation, Science and Economic Development Canada (ISED).

RR Channel	Frequency	Frequency Offset	Assignment Limitations
1	150.08		
2	150.11	30	Do not use South East VI, Lower mainland & Sunshine coast
3	150.14	30	
4	150.185	45	
5	150.2	15	
6	150.245	45	
7	150.26	15	
8	150.32	60	
9	150.365	45	Do not use Limit Southern Vancouver Island
10	150.41	45	Do not use Limit Southern Vancouver Island
11	150.44	30	Do not use Limit Southern Vancouver Island
12	150.5	60	
13	150.53	30	
14	150.545	15	
15	150.56	15	
16	150.59	30	
17	150.68	90	
18	150.71	30	
19	150.77	60	

20	150.83	60	Do not use available withn 64 KM of Alaska boarder
21	151.01	180	Do not use within 64 km of all US boarder
22	151.13	120	Do not use within 64 km of all US boarder
23	151.19	60	Do not use within 64 km of all US boarder
24	151.22	30	Do not use within 64 km of all US boarder
25	151.31	90	Do not use within 64 km of all US boarder
26	151.34	30	Do not use within 64 km of all US boarder
27	151.37	30	Do not use within 64 km of all US boarder
28	151.43	60	Do not use within 64 km of Alaska border
29	151.46	30	Do not use within 64 km of US border to the south
30	151.49	30	Do not use within 64 km of all US boarders
31	151.52	30	Do not use within 64 km of all US boarders
32	151.58	60	Do not use within 64 km of all US boarders
33	151.61	30	OK
34	151.64	30	Do not use within 64 km of Washington boarder
35	151.67	30	Do not use within 110 km of Washington border west of Princeton
LD-1	151.7	30	ok
LD-2	151.745	45	Do not use within 64 KM of southern boarder with US; within 50 KM of Prince Rupert; or 200 KM of Juneau Alaska
LD-3	151.79	45	Do not use within 20 km of Victoria
LD-4	151.805	15	Do not use within 64 km of all US boarder
LD-5	151.85	45	Do not use witin in the Stikine River watershed