



File: File Number

Date

Name of Legal Entity
Address

Dear Salutation:

Pursuant to section 23 (1) of the *Forest and Range Practices Act*, I hereby consent to you connecting a road to the Name of FSR Forest Service Road at km km location in accordance with the following requirements:

1. Sight distance must be maintained from the junction along the Forest Service road in both directions metre distance metres (from table below) in accordance with the normal travel speed on the Forest Service road.

Forest Service Road Speed KPH	Sight Distance-Metres
Up to – 65 km/h	100 m
65 – 80 km/h	150 m

2. The access road must join the Forest Service road at right angles.
3. The grade of the junction must not exceed 2% (plus or minus) for at least 30 m from the edge of the Forest Service road. The approach must drain from the Forest Service road surfacing to the ditch line.
4. You must locate, erect, maintain and remove roadway signs as directed by a Forest Officer.
5. The access must be constructed with a 500 mm metal culvert laid to maintain drainage in the Forest Service road ditch. The culvert must be of sufficient length to extend 1 metre beyond the roadbed on both sides. (The minimum culvert diameter is 500 mm which will normally be sufficient.)
6. Ditching and drainage must be constructed so that all surface water will drain as close as possible into the former natural watercourses.
7. To prevent the tracking of mud and soil onto the Forest Service road surface, the connecting road must be gravelled at least 30 metres from the edge of the Forest Service road to the satisfaction of the Forest Officer.

Page 1 of 2

**Ministry of Forests,
Lands, Natural
Resource Operations
and Rural Development**

Office

Location:

Mailing Address:

Tel:

Fax:

FS1209 HEG 2011/04