

SC-8200
SC-8200

THEODOSIA 0.1km

2025 Inspection

CBR iPad Offline Ver 0.36B



CBR Data

Latitude 49°58'56.49"
Longitude -124°38'52.9"

Site Status Active

Insp. Status Inspect

Crossing Name Not Known

FSR # 6423 Branch # 5

Road Name THEODOSIA

User km 0.1

Previous Load
Rating (tonnes) 136

Structure Class Permanent Bridge

Portable N

Superstructure Steel I-beam

Deck Type Concrete

Abutment Left Steel Pipe and Precast Pad

Abutment Right Steel Pipe and Precast Pad

Spans 1

Total Length (m) 18.3

Deck Width (m) 3.6

Updated Data

Latitude °0'0"
Longitude °0'0"

HD Diff. (m) 5564011.0 Accuracy (m)

Inspection

Date of Inspection 2025-07-30 12:38:58 PM

Inspector Name Richard Mills

Inspector Comments Serial/ID Plate

Recommended Next Inspection 2028

Inspection Company MoF

P.Eng Comments

Ministry of Forests Reviewing Engineer: Richard Mills P.Eng.
Review Date: Feb 5, 2026
Load Rating: L150 or 136 tonnes
Recommended Next Inspection: 2028
Comments: Replace guardrails.

PERMIT TO
PRACTICE: 1003022

SC-8200
SC-8200

THEODOSIA 0.1km

2025 Inspection

CBR iPad Offline Ver 0.36B



Approach

Alignment **Good**

Bridge Ahead Signs
Missing ☐ 0 ☐ 1 ☒ 2

Brushing Required **Y**

Delineator Missing
Left ☒ 0 ☐ 1 ☐ 2

Delineator Missing
Right ☐ 0 ☒ 1 ☐ 2

Fender Condition **Good**

Posted Load Rating

Road Surface **Good**

Abutment

Log/Timber Cribs

Tie Backs

Bin Wall

Pier

Concrete **Good**

Caps or Sills **Good**

Piles or Posts **Good**

Ballast Wall **Good**

Wing Wall

Bracing **Good**

Hardware **Good**

Fill **Good**

Riprap **Good**

Bearings **Good**

Corrosion Protection **Good**

SC-8200
SC-8200

THEODOSIA 0.1km

2025 Inspection

CBR iPad Offline Ver 0.36B



Deck

Running Surface **Good**

Running Planks

Sub Deck

Ties

Nails

Deck to Girder Bolts **Good**

Concrete Deck **Good**

Grout Pockets

Deck Joints **Good**

Steel Deck Plate

Gravel Surface

Curb Rail/Blocks/Posts **Poor** Rotting, replace

Hand Rails/Walkouts

Hardware **Good**

Overall Deck Condition **Fair**

Gravel Depth (mm)

Pier Deck

SC-8200
SC-8200

THEODOSIA 0.1km

2025 Inspection

CBR iPad Offline Ver 0.36B



Steel/Concrete

Girders Good

Diaphragms Good

Bracing Good

Under Trussing

Hardware Good

Welded/grouted
shear connectors

Log

Log Curbs

Needle Beam

Needle Lashing/
Shimming

Needle Beam to Crib (m)

Needle Diameter (mm)

Stringer Number	Species	Peeled	Diameter (mm)	Rot Depth (mm)	Condition	Comment
--------------------	---------	--------	------------------	-------------------	-----------	---------

SC-8200
SC-8200

THEODOSIA 0.1km

2025 Inspection

CBR iPad Offline Ver 0.36B



Hazards

Estimated Present Water Level Depth (m)	0	High Water	☐	Debris	☐
Estimated Present Water Level Width (m)	0	Aggradation	☐	Scour	☐
Estimated High Water Level Clearance	3.0	Ice	☐		

Comments

Repairs and Monitoring

Repair Item	Repair Description
1 Structure. Full Curb Replacement. . Priority:High	Replace guardrails

2

3

4

5

6

7

Item	Monitor Description	Frequency
------	---------------------	-----------

1

2

3



Approach from Left Bank when facing downstream



Deck



Left Bank Abutment when facing downstream



Right Bank Abutment when facing downstream