

# ROAD INFORMATION SIGN PLACEMENT FOREST ROAD PROCEDURE #4

Thompson Rivers Resource Road Safety Committee

These procedures apply to all forest roads within the Thompson Rivers district maintained for industrial use.

## Known Hazards

- |                                       |                                       |
|---------------------------------------|---------------------------------------|
| 1. Signs having the wrong information | 2. Signs posted at the wrong location |
| 3. Signs fallen down or destroyed     | 4. Conflicting signage                |
| 5. Signs not posted                   | 6. Signs not clearly legible          |

### A. Forest Road Entrance Sign

1. To be placed where entering a forest road off a public road or where changing the radio protocol.
2. An adequate turn out should be available in front of the sign to allow the user to stop and safely read the sign.
3. The sign must be clearly visible and contain the following information;
  - a. The road name.
  - b. The RR channel or frequency to use.
  - c. The radio calling protocol, if required to identify unique situations.

### B. KM Marker Boards

1. Marker boards should be placed a minimum 1 kilometre apart, but can be adjusted slightly to maximize visibility from both directions or for other safety reasons.

### C. RR channel / Frequency Switch Sign

1. To be placed whenever switching a road channel frequency.
2. The sign must be clearly visible from both directions and contain the following information;
  - a. The road name (if it is a named road).
  - b. The RR channel or frequency it is being switched to.

### D. Must Call Sign

1. May be a separate sign or incorporated into a KM Marker, Forest Road Entrance or RR channel Switch Sign.
2. A must call sign is to be placed at all of the following locations;
  - a. At any point along a road where there is an increased safety risk or hazard and additional calling is required.

Follow the "3 C's":      Caution      Courtesy      Concentration