




OPEN FIRE REGULATIONS



40% of B.C. wildfires are human-caused and therefore preventable

CAMPFIRES, CATEGORY 2 FIRES AND CATEGORY 3 FIRES: WHAT'S THE DIFFERENCE?



CAMPFIRE:

- Any fire smaller than 0.5 metres high by 0.5 metres wide

REGULATIONS:



You must have ready access to 8 litres of water or a shovel for the entire time your campfire is lit.



Your campfire must be completely extinguished and the ashes must be cool to the touch before leaving the area for any length of time. (Hot coals can reignite the fire.)



During campfire prohibitions, only a CSA- or ULC-approved portable campfire apparatus may be used, and the flame height must not exceed 15 centimetres.



You must build a fire guard around your campfire.

CATEGORY 2 FIRE:

- 1 to 2 concurrently burning piles no larger than 2 metres high by 3 metres wide
- Stubble or grass burning over an area less than 0.2 hectares

REGULATIONS:



A fuel break must be established around any Category 2 burn area.



Fireworks are banned when a Category 2 fire prohibition is in effect.



Burning barrels are banned when a Category 2 fire prohibition is in effect.



At least one person equipped with a fire-fighting hand tool must monitor the fire at all times.

CATEGORY 3 FIRE:

- Any fire larger than 2 metres high by 3 metres wide
- 3 or more concurrently burning piles no larger than 2 metres high by 3 metres wide
- 1 or more burning windrows
- Stubble or grass burning over an area greater than 0.2 hectares

REGULATIONS:



A fuel break must be established around any Category 3 burn area.



Monitor your open burn to ensure that the fire doesn't spread beyond its intended size.



You must have a burn registration number to light a Category 3 open fire. Call the burn registration line **1 888 797-1717** to obtain one.

GENERAL REGULATIONS:



Never burn in strong wind conditions.



Your fire must be extinguished before leaving the area.



Always keep your fire a safe distance away from nearby branches, wood and other combustible materials.



Do not conduct Category 2 or Category 3 burns when venting conditions are "Poor" or "Fair". Always check here first: www.bcairquality.ca/readings/ventilation-index.html

*Further bans and restrictions can be implemented at the Wildfire Management Branch's discretion.



Anyone found in contravention of an open fire prohibition may be fined up to \$345. If your fire escapes and results in a wildfire, you may be fined anywhere from \$100,000 to \$1 million and be sentenced to one year in prison. Please check with local government authorities for any other restrictions before lighting any open fire.

Please report wildfires by calling ***5555 or 1 800 663-5555**.