

TRAILHEAD SIGN



Black lettering Impact 70 point  
character spacing 0%  
condensed horizontally 65%

Trail Area Location Map

White lettering  
Franklin Gothic Medium 14 point  
character spacing 0%  
line spacing 108% character height

White lettering  
Franklin Gothic Medium 18 point  
character spacing 0%

White lettering  
Franklin Gothic Medium 16 point  
character spacing 0%

Yellow lettering Impact 50 point  
character spacing minus 10%

White lettering  
Franklin Gothic Medium 12.5 point  
character spacing 0%

User Groups  
Clubs/Partners/Sponsors  
Province of BC

- Size 140mm x 370mm
- Background Colour Green: CMYK (100-0-100-0)
- Mounting - wood post measuring 100mm x 100mm  
- pre-treated or western red cedar  
- top of post 1.0m above ground
- Font Type/Size Large Fonts - IMPACT  
Small Fonts - Franklin Gothic Medium
- Icons Difficulty Rating Symbol  
User Groups  
Clubs/Partners/Sponsors  
Province of BC
- Font Colour Yellow Text: CMYK (0-13-100-0)  
White Text: CMYK (0-0-0-0)

SIGN COLOURS - Reflective paints

<b>BLACK</b> - C0, M0, Y0, K100	<b>GREEN</b> - C100, M0, Y100, K0
<b>WHITE</b> - C0, M0, Y0, K0	<b>YELLOW</b> - C0, M13, Y100, K0
<b>RED</b> - C0, M100, Y100, K0	<b>ORANGE</b> - C0, M50, Y100, K0

Standard		TRAIL SIGNS - TRAILHEAD	
File No:		Draft Date:	10/08
Approved By:	<i>W. Marshall</i>	Revision No:	Date: 11/08
Date:		Revision No:	Date:
		Revision No:	Date:
	Ministry of Tourism, Sport and the Arts	Drawing Scale:	1 - 2.5 Sheet Size: 8.5" X 11"
		Drawing No:	RST 481-TS-TH