


**MATERIAL LIST**

#	Size	Material	Remarks
1 pc. 4 pcs. 2 pcs. 1 pc	4'-0" x 4'-0" x 3/4" 2x4 x 3'-9" 2x4 x 4'-0" 2x4 x 2'-0"	select grade fir ply S4S - S.P.F. S4S - S.P.F. S4S - S.P.F.	FLOOR PANEL
2 pcs. 4 pcs. 2 pcs 2 pcs 4 pcs. 3 pcs.	2x4 x 4'-11" 2x4 x 4'-7 1/2" 1x6 x 5'-3/4" 1x6 x 4'-10 1/2" 2" x 4" 26"x 62"x 6 oz.	S4S - S.P.F. S4S - S.P.F. S4S - Clear spruce S4S - Clear spruce galv. L-bracket/screws corrugated clear or green fibreglas c/w alum. nails & neoprene washers	ROOF PANEL
1 pc.  2 pcs. 1 pc. 1 pc. 1 pc. 1 pc. 1 pc. 1 pc.	4'-0" x 7'-0"x1/2"  2x4 x 6'-5" 2x4 x 6'-6 1/2" 2x4 x 3'-5" 2x4 x 1'-3 1/2" 2x4 x 1'-1/2" 2x4 x 2'-0" 1x3 x 6'-0"	select sheath'g grade aspenite (alt. spruce / fir ply) S4S - S.P.F. studs " " " " " top plate " " bot. plate " " wall girt " " lintel S4S - S.P.F. door stop	FRONT PANEL
1 pc. 2 pcs. 1 pc. 1 pc. 1 pc.	2x4 x 1'-11 1/2" 1x3 x 5'-9" 1x3 x 1'-11 1/2" 1x3 x 1'-6 1/2" 1'-11 1/2" x 5'-11 1/2" x 1/2"	" " door girt S4S - S.P.F. door strap S4S - S.P.F. door strap S4S - S.P.F. door strap select sheath'g grade aspenite (alt. spruce / fir ply)	DOOR
2 pcs. 2 pcs. 2 pcs. 2 pcs. 4 pcs.	4'-0"x 7'-0"x 1/2" 2x4 x 6'-5" 2x4 x 5'-10 2/3" 2x4 x 4'-1/2" 2x4 x 4'-0" 2x4 x 3'-9"	select sheath'g S4S - S.P.F. studs " " " " " top plates " " bot. plates " " girts	SIDE PANELS (2)
1 pc. 2 pcs. 2 pcs. 1 pc.	4'-0"x 6'-5 1/2"x 1/2" 2x4 x 5'-10 1/2" 2x4 x 3'-5" 2x4 x 3'-2"	select sheath'g S4S - S.P.F. studs " " plates " " girts	REAR PANEL
3  1 1 3 lb. 1 lb.	3" x 2 1/2"  4 1/2" 2 1/2" 1 1/4" 2"	Stanley 151 C2a spring hinges door pull galv. hook & eye galv. box nails ring nails	HARDWARE

**FINISHES**

Location	Materials	Coverage
Exterior - walls	General paint shingle stain 01-117	2 coats
- roof	Dark Green	2 coats
Interior - walls	General paint alkyd primer 32-001 white	1 coat
	General paint alkyd house & trim 32-010	1 coat
- floor	General paint alkyd primer 32-001 General paint porch enamel 42-090 Twilight grey	1 coat 1 coat
- under side	Cuprinol wood preservative	2 coats

Standard TOILET - MATERIALS	
File No:	Draft Date: 07/05
Approved By: <i>W Marshall</i>	Revision No:      Date: 01/08
	Revision No:      Date:
Date:	Revision No:      Date:
 Ministry of Tourism, Sport and the Arts	Drawing Scale: 1 - 20      Sheet Size: 8.5" X 11"
	Drawing No: RST 481-T-2